

Statement of Work for Armory Rack Replacement and Repair at Malmstrom AFB, MT

24 April 2025

1. Introduction

This Statement of Work (SOW) outlines the requirements for the replacement and repair of weapons racks at the Security Forces Armory, Malmstrom Air Force Base, Montana. The contractor shall furnish all labor, materials, equipment, and supervision necessary to complete the project as described herein.

2. Scope of Work

The Contractor shall:

- **2.1 Rack Replacement:**
 - Provide and install sixteen (16) new Spacesaver Universal Weapons Racks (UWRs) with dimensions 42" wide x 16 1/8" deep x 45" high, and four (4) new Spacesaver UWRs with dimensions 42" wide x 16 1/8" deep x 61" high. Racks shall be delivered empty. Manufacturer part numbers for the racks shall be provided in the contractor's proposal.
 - Cut welds on existing racks, disassemble them, and dispose of the old material in government provided trash cans. Armory personnel will handle disposal means. None of the material being removed needs any kind of special disposal method.
 - Transfer existing Weapons Rack Accessories from the old racks to the new racks. "Weapons Rack Accessories" shall be clearly defined in the contractor's proposal and include a detailed list of the accessories to be transferred.
- **2.2 Rack Repair:**
 - Inspect all 20 existing 3-Spoke Handles on all armory racks and replace the broken handle on one of the weapon racks.
 - Repair or replace any defective 3-Spoke Handles as needed. Replacement handles shall be of equivalent quality and functionality to the original handles.

3. Project Schedule

- The project shall be completed in 7 days from the project start date.
- The Contractor shall provide a detailed project schedule with their proposal.
- Extended working hours may be required and shall be coordinated with the Mission Partner Representative.

4. Place of Performance

341 SFG Armory, Malmstrom Air Force Base, Montana. The armory is located in the basement of building 500, room number is 41B.

5. Government Provided Temporary Government Storage

- The government will provide a designated area for the temporary storage of weapons and components during the rack replacement.

6. Security Requirements

The Contractor shall comply with all applicable security regulations for Malmstrom AFB. Details regarding base access procedures will be provided upon contract award.

7. Deliverables

- Fully installed and functional weapons racks.
- All replaced 3-Spoke Handles.
- A final report documenting the work performed, including a list of all repaired/replaced components.