

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE		PAGE 1 OF 1 PAGES	
2. AMENDMENT/MODIFICATION NUMBER 040ADV-25-Q-0010-0002		3. EFFECTIVE DATE 04/25/2025		4. REQUISITION/PURCHASE REQUISITION NUMBER PR-24-GPO-2622		5. PROJECT NUMBER (If applicable)	
6. ISSUED BY CODE				7. ADMINISTERED BY (If other than Item 6) CODE			
				Same As Issuing Office			
8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)				(X)		9A. AMENDMENT OF SOLICITATION NUMBER 040ADV-25-Q-0010	
				(X)		9B. DATED (SEE ITEM 11) 04/10/2025	
				()		10A. MODIFICATION OF CONTRACT/ORDER NUMBER	
				()		10B. DATED (SEE ITEM 13)	
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.							
Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.							
CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.						
()							
()	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation data, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).						
()	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:						
()	D. OTHER (Specify type of modification and authority)						
E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)							
AMENDMENT CONTROL NUMBER: 040ADV-25-Q-0010							
SUMMARY OF CHANGES: The purpose of this amendment is to provide responses to the submitted questions.							
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
				Troy D. White, Contracting Officer			
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED	
						04/25/2025	
(Signature of person authorized to sign)				(Signature of Contracting Officer)			

1. Clarify if this is for engineering services only or is this a design build up also include the repair (so it includes construction not just assessment and design)?
As mentioned in the SOW this job requires scanning (or better technique to locate the root of cause) of the wall and any type of repairing per findings.
2. Is the 21-day start-to-finish timeline flexible?
Yes, we can provide some flexibility.
3. Can the area be sealed off for dust mitigation during the installation process?
Yes, and it will be the contractor's responsibility to seal off the area. The area is clean, and the affected wall is in the closed room.
4. Are there any limitations on using dehumidifiers in the area to help dry out the wall?
There are no limitations on using dehumidifiers.
5. There is a green color of varying shades in the original before pictures. Do you know if this is a previous coat of paint? The 1930's blueprints reference metallic waterproofing, so we are wondering if the green tint could be oxidation that may have penetrated the wall.
Green color shades are base primer and latex paint over top.
6. Please send pictures of the new leaks, are there any signs of leaks in the areas that were previously repaired?
No leaks have been discovered since the last repair in 2023.
7. Has an exterior dig up been completely ruled out as a potential solution?
No. The exterior is in DC jurisdiction. It may require additional permit to perform any exterior work
8. Are you open to a negative side solution such as an epoxy laminate system to cover the surface of the wall?
Yes, we are open to it. However, the contractor must ensure the best and effective methods to meet all performance requirements without compromising the integrity or intended function of the wall.
9. Were there any soil samples completed to know what the ground makeup is in the areas in question around the building? Or any nearby soil samples from any other underground activities that you would access to know what soil makeup in the general vicinity may be?
None of this work has been performed.

10. Are there any previous coring samples of the walls that were completed to show us what might be on the back side of the walls in question? **No core work has been done on this wall.**
11. Would coring be allowed to see what is behind the concrete walls? **The concrete wall varies in thickness from 14-,23 areas across the affected area. We would prefer to not destruct the structure of the wall.**
12. Can you provide the material spec information on what was used previously (The site had previously been injected with 6 gallons of polyurethane foam and approximately 3 gallons of Mutigel acrylic resin by The Contractor). **Unfortunately, we don't have spec information for the material that has been used on the wall.**
13. Are there any as-built drawings from the repairs that were previously completed? **There are no as-built drawings of the previously completed repair.**