

STATEMENT OF WORK

28 April 25

Project #: LXEZ201072

Project Title: Repair SOW Ops Facility, B3524

Facility: B3524

Installation: Kadena Air Base, Okinawa, Japan

Preparer 718 CES/CENMC **Project Manager:** [REDACTED]

Date Prepared: 250428

Date Modified: NA

Table of Contents

Contents

1	GENERAL INFORMATION	3
1.1	LEVEL OF CONSTRUCTION	3
1.2	PROJECT SUMMARY	3
1.3	PROJECT REQUIREMENT	3
1.4	GOVERNMENT FURNISHED EQUIPMENT/MATERIAL (GFE/GFM)	3
2	SITE CONDITIONS	3
2.1	WORK SITE LOCATION	3
2.2	AS-BUILT DRAWINGS	4
2.3	REGULATED BUILDING MATERIALS	4
2.4	USE OF LATRINE AND UTILITIES	4
3	PROJECT PHASING & SCHEDULE	4
3.1	PERIOD OF PERFORMANCE	4
3.2	PRE-DESIGN MEETING	5
3.3	DESIGN	5
3.4	CONSTRUCTION	6
4	DESIGN REQUIREMENTS	7
4.1	DESIGN CRITERIA	7
5	SUBMITTAL REQUIREMENTS	7
5.1	GENERAL	7
5.2	SUBMITTAL DOCUMENT FORMAT	7
6	OTHER REQUIREMENTS	8
6.1	GENERAL	8
7	PRE-FINAL INSPECTION	8
7.1	FINAL INSPECTION	8
8	ENVIRONMENTAL COMPLIANCE CRITERIA	8
8.1	GENERAL ENVIRONMENTAL COMPLIANCE	8
9	DETAILED DESCRIPTION OF WORK	8
9.1	B3524 PROJECT NUMBER LXEZ 201072	8
9.1.1	All work is summarized below and should be designed and executed according with course of action (COA) 1 in the attached planning charette report, A-10.	9
9.2.1	Architectural:	9
9.3.1	Electrical:	9
9.4.1	Mechanical:	9
9.5.1	Fire System/Life Safety/Mass Notification	9

STATEMENT OF WORK

28 April 25

10	ACM/LBP-RELATED WORK	10
10.1	General	10
10.2	Abatement of Identified Materials	10
11	ATTACHMENTS	10

DRAFT

STATEMENT OF WORK

28 April 25

1 GENERAL INFORMATION

1.1 LEVEL OF CONSTRUCTION

This project is for the design and construction of facilities defined as Permanent Construction per UFC 1-200-01, paragraph 1-3.2.

1.2 PROJECT SUMMARY

The project scope consists of, but is not limited to, providing all field investigations, surveys, design, plant, labor, supervision, materials, equipment, supplies, transportation, third-party services, and incidental related work to design and execute construction work defined in this Statement of Work and the attached documents. The work includes all necessary finishing work to provide the Government with a final product that is fully functional and leaves no areas of the facility that appear incomplete or unfinished.

1.3 PROJECT REQUIREMENT

This project shall accomplish a design-build repair of the roof of building 3524. The concrete roof will be replaced, including an anchoring system and seismic improvements. Insulation will be installed on the interior side of the exterior walls and below the roof slab. The electrical, ventilation air conditioning, and fire alarm/protection systems will be replaced throughout the building. The project will include the patching and repair of concrete spalling, structural repairs to the concrete masonry unit load-bearing walls, replacement of interior doors, and repairs to finishes including gypsum and drop ceilings. The roof and concrete beams as well as select foundation footings will be demolished; footing extensions and slab on grade improvements included where new or extended shear walls are required. Rooftop penthouses for mechanical equipment will be removed. Work for the project is described in more detail in Section 9 of this Statement of Work (SOW). Sustainable principles, to include life cycle cost-effective practices shall be integrated into the design, development, and construction of the project(s) in accordance with the latest version of UFC 1-200-02, High Performance and Sustainable Building Requirements. The Contractor shall evaluate government-provided records, the scope of work, and site conditions to identify the presence, location, and quantity of asbestos-containing material (ACM) and presumed asbestos-containing material (PACM), as well as lead-based paint (LBP) and other hazardous materials. This evaluation shall include sampling and testing of suspected ACM/LBP in accordance with applicable US federal and Japan regulations (specifically, the Japan Environmental Governing Standards - JEKS). Based on these findings, the Contractor will define the Class of Work for each disturbance and develop appropriate removal, abatement, and disposal plans. For the purposes of abatement planning, the presence of ACM/LBP in any sampled material will be assumed to indicate the presence of ACM/LBP in all identical materials throughout the building.

Construction activities may commence after the approval of the Environmental Protection Plan (EPP) and AF Form 103 (work clearance). The Contractor shall coordinate on-site safety requirements through the 718th Civil Engineer Squadron (718 CES).

1.4 GOVERNMENT FURNISHED EQUIPMENT/MATERIAL (GFE/GFM)

The following GFE/GFM will be provided:

- a. None

2 SITE CONDITIONS

2.1 WORK SITE LOCATION

Repair SOW Ops Facility, B3524 LXEZ201072

STATEMENT OF WORK

28 April 25

- a. See attached maps. A-5
- b. Affected facilities / infrastructure are:

- (1) B3524

Building 3524 is a single-story, 38,875 SF (3,612 SM) concrete building located on the eastern end of Kadena Air Base. The building was constructed in 1967 as an administrative facility; it consists of open and closed administrative workspace; an auditorium; an operations center; storage; a break room; and mechanical, electrical, and telecommunications rooms. In 2024, extensive concrete spalling from the ceiling caused major safety concerns and led to the evacuation of the facility until repairs could be made, although some critical equipment functions remain such as a telecommunications room that serves multiple facilities. The concrete has become carbonate due to the age of the structure, poor building envelope, prolonged exposure to the elements, and inadequate preventative maintenance. The process of carbonation is irreversible and difficult to stop in the presence of moisture, which means that the spalling will continue even if surface repairs such as patching are made. This also makes the facility more vulnerable to failure of the structural system in a major event such as a typhoon or earthquake. In addition to the spalling issues, there is significant cracking in the concrete masonry unit (CMU) walls at the top of the three rooftop penthouses, significant leaking around the central workspace, and the roofing material is worn and beyond its service life which has led to the described water infiltration causing other structural damage

- c. Occupancy of Premises

- (1) Government personnel will not occupy the facility under active construction.
 - (2) The Contractor will have full access during authorized working hours and shall be responsible for securing the construction area daily.

2.2 AS-BUILT DRAWINGS

See attached drawings as a reference.

The Government bears no responsibility for the accuracy or completeness of these drawings. Contractors shall conduct field investigations of the affected facility to ascertain the actual existing conditions prior to beginning the design. The Contractor is solely responsible for any errors, omissions, delays, or additional costs attributed to the failure to do so.

2.3 REGULATED BUILDING MATERIALS

- a. Asbestos Containing Material / Lead Base Paint (ACM/LBP)
- b. The project may require sampling and testing of ACM/LBP. The Japan Environmental Governing Standards (JEGS) will be followed during the sampling process and testing. See Attachment-3a Section 01 57 19.01, Temporary Environmental Controls – Kadena Air Base

2.4 USE OF LATRINE AND UTILITIES

Contractor can use available latrines and utilities if they are available]

3 PROJECT PHASING & SCHEDULE

3.1 PERIOD OF PERFORMANCE

- a. The Period of Performance (POP) allowed on this contract is detailed below. The Contractor shall be required to complete the entire work, ready for use. This includes pre-construction and material submittals, government reviews, material procurement, unfavorable weather, and construction time. The time for completion shall include final cleanup of the premises.

STATEMENT OF WORK

28 April 25

Days for Design:	297	calendar days
Days for Construction:	760	calendar days
Days for Administrative	30	calendar days
Total POP	1087	calendar days

- b. Notice to Proceed. Day one of the POP is the day after the day the Contracting Officer issues the Notice to Proceed (NTP) on the design. If no serious issues are identified during the Pre-Design Conference, the Contracting Officer normally issues the NTP at the end of the conference.
- c. Close-Out. All requirements of this contract including the design, submission and Government review of submittals, resolution of design issues, material acquisition, on-site construction work, site clean-up and return of the facility, ready for use, must be completed by the last day of the POP. Refer to section 01 78 00 for suspense of Closeout Submittals.

3.2 PRE-DESIGN MEETING

- a. Within 10 days of receiving the notice of award, the Contractor will schedule a Pre-Design Meeting with the Contracting Officer, Civil Engineer Squadron (CE) Project Delivery Team, and other project stakeholders.
- b. At the Pre-Design Meeting, the Contractor shall submit a Project Schedule for review by the Government and re-submit updates, as necessary, until project completion.
- c. During the meeting, the Contractor may ask any questions pertaining to the contract, including questions pertaining to the design, progress schedule, or other issues. If requesting changes to any elements of the contract, submit a written explanation justifying the change(s), accompanied by diagrams, technical data, and any other justifying documents to the Contracting Officer. The Government recognizes only those changes agreed upon in writing by the Contracting Officer as official changes to the contract.

3.3 DESIGN

- a. Design Schedule
 - (1) The design work shall be completed in accordance with the following sequence/timeframe. Written approval from CO is required to proceed to the next level of design submittal. Contractor shall attend review meetings as scheduled.

DESIGN SCHEDULE	SHALL BE COMPLETED WITHIN	
Submit 35% Design Documents	60	calendar days after NTP
Government 35% Design Review	19	calendar days after submission
Submit 65% Design Documents	60	calendar days after 35% design approval
Government 65% Design Review	28	calendar days after submission
Submit 95% Design Documents	45	calendar days after 65% design approval
Government 95% Design Review	21	calendar days after submission
Submit Revised 95% Design Documents	14	calendar days after 95% design approval
Submit 100 % Design Review	30	calendar days after 100% design approval
Government 100% Design Review	20	calendar days after 100% submission
Design Subtotal:	297	calendar days

STATEMENT OF WORK

28 April 25

b. Design Review Meetings

- (1) The Contractor shall attend meetings with the Government at the 35%, 65% and 95% design stage to discuss details of the design with Government stakeholders. Submit all required design documents just prior to, or at the onset of each meeting.
- (2) The Contractor shall prepare all meeting minutes to document both party's comments and distribute copies to attendees via email within 3-working days after each meeting.
- (3) The Contractor shall provide a proper resolution for all legitimate issues brought up by Government reviewers and return the completed PACAF Form 225 within 14 days.

3.4 CONSTRUCTION

- a. Pre-Construction Conference: The Contractor shall request a pre-construction conference with the Government no later than 35-calendar days prior to the start of on-site work.

b. Construction Schedule:

SITE WORK/CONSTRUCTION SCHEDULE	SHALL BE COMPLETED WITHIN	
a) Material Submittals:	100	calendar days after 95% design approval
b) Government Material Review:	10	calendar days
c) Procurement of Materials:	180	calendar days
d) Construction Time:	460	calendar days
e) Unfavorable Weather:	10	calendar days
Construction Subtotal:	760	calendar days

- c. Follow the working hours and days listed in the specifications. To wit, "Normal Construction Working Hours and Work Days shall be from 07:30 to 18:00, Monday through Friday, excluding U.S. Federal holidays."

- (1) Work outside of normal hours or days is prohibited without written approval of the Contracting Officer.
- (2) Federal Holidays are listed in the specifications.

- d. Weather Delays: The Contractor shall provide a weather delay request within 10 days of unfavorable weather that caused the work delay per FAR 52.249-10(b)(2).

e. Start Work Notification

- (1) No less than 7 days prior to the start of on-site work, the Contractor shall inform the Contracting Officer and CE PM in writing of their intended start date. The Contractor must have a fully coordinated the Work Clearance Request (AF Form 103) and have received approval of the Environmental Protection Plan (EPP) prior to being authorized to start on-site work.
- (2) See specifications for details concerning the AF Form 103.
- (3) See Section 01 57 19 30, TEMPORARY ENVIRONMENTAL CONTROLS, for details about drafting and submitting the EPP.

STATEMENT OF WORK

28 April 25

4 **DESIGN REQUIREMENTS**

4.1 **DESIGN CRITERIA**

See specification section 01 33 16.00 10, DESIGN DATA AFTER AWARD.

5 **SUBMITTAL REQUIREMENTS**

5.1 **GENERAL**

- a. See specification section 01 33 00, Submittal Procedures; and section 01 78 00, Closeout Submittals.
- b. Submittals for all materials and shop drawings must be coordinated and approved by the 718th Civil Engineer Squadron (718 CES) Project Manager.
- c. Project design will be coordinated with the 18th Contracting Squadron (18 CONS), the Using Agency, 718 CES and other agencies involved in project reviews.
- d. The Contractor's licensed Architects and Engineers shall stamp, date, and certify all professional design documents. Provide proper credentials prior to beginning design work. Construction documents must be stamped, signed and dated prior to construction and upon completion of the project.
- e. Submit a Basis of Design document, that show the design analysis calculations, for each construction discipline, with the 35%, 65% and 95% design submittal.

5.2 **SUBMITTAL DOCUMENT FORMAT**

See specification section 01 33 16.00 10, Design Data (DESIGN AFTER AWARD); section 01 78 00, Closeout Submittals; section 01 78 23, Operations and Maintenance Data; and section 01 78 24.00 10, Facility Data Requirements.

- a. Submit all design documents at each stage of the design and acceptance process.
- b. Provide two sets for each submittal: one set for 18 CONS/PKC and one set directly to the 718 CES/CENM flight managing the project.
- c. A set consists of one printed hard copy of each submitted document and a CD-R, DVD-R, or CD- ROM containing all the documents.
- d. Do not use media recorders that burn discs regionalized for Japan only. Media must be regionalized for the United States or not regionalized at all.
- e. Hard copies shall be submitted per the following schedule:

	Submittal	35% sets	65% sets	95% sets	Revised 95% sets
1	B1 Drawings (full size)	1	1	1	1
2	Specification Package with AF IMT 66	2	2	2	2
3	Annotated Design Review Comments	1	1	1	1
4	Design Analysis/Calculations	2	2	2	2
5	CD-R (all contract documents)	2	2	2	2
6	Draft DD Form 1354			2	
7	Draft Progress Schedule	2	2	2	2
8	Approved EPP			1	1
9	Detailed Cost Estimate (Contractor's bid)	1	1	1	

STATEMENT OF WORK

28 April 25

6 OTHER REQUIREMENTS

6.1 GENERAL

The project engineer, the user, and 18 CONS/PKC representatives shall accompany the Contractor to conduct joint job site inspection prior to initiation of the site work.

7 PRE-FINAL INSPECTION

The Contractor shall conduct a pre-final walk-through inspection in the presence of the COR and CE Project Manager and publish the pre-final inspection findings in a pre-final inspection report. The pre-final inspection shall be conducted a minimum of 10 calendar days before the final inspection date. A Beneficial Occupancy Determination (BOD) may be required for certain areas if it is in the best interest of the Government.

7.1 FINAL INSPECTION

- a. The final inspection report shall certify that all Contractor construction contract requirements have been met.
- b. The Contractor shall complete a DD Form 1354, Transfer and Acceptance of DoD Real Property, for Government approval. Submit a draft version of the DD Form 1354 with the 95% design documents. Submit an interim DD Form 1354 at the pre-final inspection and a final DD Form 1354 prior to final invoice. Prepare the DD Form 1354 in accordance with UFC 1-300-08, Criteria for Transfer and Acceptance of DoD Real Property.

8 ENVIRONMENTAL COMPLIANCE CRITERIA

8.1 GENERAL ENVIRONMENTAL COMPLIANCE

- a. The Contractor shall draft and submit an Environmental Protection Plan (EPP) per specification section 01 57 19.01 30, TEMPORARY ENVIRONMENTAL CONTROLS, and comply with the plan during the entire period of performance.
- b. Be advised that on-site construction work cannot begin until Government approval of the Contractor's EPP. The AF Form 103 Work Clearance Request will not be approved until the EPP is approved.
 - (1) Submit the above items early to avoid a delay in the construction schedule. The Contractor is solely responsible for any delays attributed to the Government's disapproval of plans that do not meet the contract requirements.
- c. REQUIREMENTS FOR HAZARDOUS BUILDING MATERIALS
 - (1) For unexpected discovery of hazardous building materials, comply with specification section 01 57 19.01 30.
- d. Note: If required by Japan regulations to submit facility-specific asbestos survey data to the GOJ, first consult with 18CONS and submit the completed GOJ PDF documents to the Contracting Officer/Administrator and request authorization to release Government information. Upon written approval, submit the Government reviewed and returned PDFs only to the GOJ

9 DETAILED DESCRIPTION OF WORK

9.1 B3524 PROJECT NUMBER LXEZ 201072

STATEMENT OF WORK

28 April 25

9.1.1 All work is summarized below and should be designed and executed according with course of action (COA) 1 in the attached planning charette report, A-10.

9.2.1 Architectural:

a. Demolish/Removal

- (1) Demolish the roof structure and roof beams and all other structural members to remain in place.
- (2) All impacted ceiling tiles

b. Construction

- (1) Roof replacement with new cast-in-place concrete slab; precast structural elements, such as hollow core slab or double tees topped with a concrete topping; or steel joists and metal deck. New connections and rebar will be doweled into the existing CMU and concrete, using an adhesive anchoring system.
- (2) Provide new ceiling tiles and associated components impacted from construction

9.3.1 Electrical:

a. Demolish/Removal

- (1) Switchboard, motor control centers (MCC) A, and MCC B and associated components
- (2) Lighting and associated electrical components

b. Construction

- (1) New Switchboard, motor control centers (MCC) A, and MCC B and associated components

c. Lighting and associated electrical components

9.4.1 Mechanical

a. Demolish/Removal

- (1) HVAC and Plumbing systems.
- (2) Chillers to remain in place

b. Construction

- (1) New HVAC and Plumbing systems
- (2) New HVAC shall fit in existing footprint

9.5.1 Fire System/Life Safety/Mass Notification

a. Demolish/Removal

- (1) Existing fire protection/suppression system
- (2) Fire Alarm/Detection System
- (3) Mass Notification System

b. Construction

- (1) New fire protection/suppression system
- (2) New Fire Alarm/Detection System
- (3) New Mass Notification System

STATEMENT OF WORK

28 April 25

10 **ACM/LBP-RELATED WORK**

10.1 **General**

- a. The Contractor shall ensure all ACM/LBP related assessments, surveys, sampling, reporting, abatement plan design and execution, and waste disposal is conducted by trained and certified in accordance with the applicable Code of Federal Regulations (CFR) and the requirements in the specifications and supplements identified in the SOW.

10.2 **Abatement of Identified Materials**

- a. Attachment A-3 List material identified as requiring abatement

11 **ATTACHMENTS**

1. Specifications for General Requirements and Existing Conditions
2. Technical Specifications
 - a. Kadena Air Base CAD Standard
 - b. KABI32-2001 – Fire Prevention and Protection
3. Additional Environmental Specifications
4. Kadena Design Guide
5. Work Site Location M
6. As-Built Drawings
7. Special Contract Requirements
8. Other Contract Requirements
9. ACM/LBP Test Results
10. Planning Charette Report COA 1