

STATEMENT OF WORK

Replace DDL RO Water System

1.0 Background

NASA/Goddard Space Flight Center requires replacement of the reverse osmosis water generator station for the DDL.

2.0 Scope of Work

Provide a RO system to replace existing system with the following.

- Vertical configuration, compact design
- 12 membrane
- 460VAC
- UV unit with Light Trap

Provide on-site installation. Reuse existing utilities is ok, such as power and drain.

All contractor visitors to GSFC need to be US citizen or LPR. Foreign visitors will be considered and will require 45 days to get approved site access.

The contractor shall provide all labor and materials necessary to perform the work required by the Government. Before commencing the work, the contractor will provide a plan, detailing the applicable emergency and safety procedures for the work to be performed.

3.0 Place of Performance

Vendor facility and installation at Goddard Space Flight Center, building 30 basement.