



DEPARTMENT OF THE ARMY
U.S. ARMY CORPS OF ENGINEERS, NEW YORK DISTRICT
JACOB K. JAVITS FEDERAL BUILDING
26 FEDERAL PLAZA
NEW YORK, NEW YORK 10278-0090

CENAN-EN-MW

13 March 2025

MEMORANDUM FOR Chief, Contracting Division

SUBJECT: Sources Sought Analysis for, Brand Name, Market Research for FIMI Contract 3D (Ocean Beach Well Relocation) at Ocean Beach, NY.

1. A source sought announcement to:

- A. To notify potential Offerors of the Governments intent to solicit a brand name(s) only component for this project.
- B. To identify potential sources that can provide an equivalent to the brand name only item.
- C. Notification of the Army's intent to solicit brand name components as described below:

(1) Flowserve Limitorque Model QX Series Actuator

The requirement is to provide Flowserve Limitorque actuators in Contract 3D (Ocean Beach Well Relocation). The Flowserve Limitorque actuator is a motorized valve actuator that provides automated and precise control of water flow within the well and pump facility. It ensures efficient modulation of valves, optimizing pressure regulation and preventing fluctuations that could impact system performance. This actuator enhances operational reliability by allowing remote control and monitoring, reducing the need for manual valve adjustments. The Flowserve Limitorque actuator is proprietary to the facility's existing automation and control network, ensuring seamless integration, maintaining consistency across actuated valves, and simplifying maintenance and spare parts inventory.

(2) Hach Model DPD1R1 pH Analyzer and Hach Model CL17sc 857700 Chlorine Analyzer

The requirement is to provide Hach Model DPD1R1 pH analyzers and Hach Model CL17sc 857700 chlorine analyzers in Contract 3D (Ocean Beach Well Relocation). The Hach pH analyzer and chlorine analyzer are critical instruments for monitoring and maintaining water quality within the well and distribution system. The pH analyzer ensures proper pH balance, which is essential for preventing corrosion or scaling in pipes and equipment, while the chlorine analyzer provides real-time data on disinfectant levels to ensure compliance with water safety standards. These analyzers allow for continuous monitoring and precise adjustments to treatment processes, ensuring consistent water quality. As proprietary components of the facility's existing water quality monitoring system, these Hach analyzers maintain compatibility with established protocols, ensuring consistency in data logging, calibration, and maintenance procedures.



DEPARTMENT OF THE ARMY
U.S. ARMY CORPS OF ENGINEERS, NEW YORK DISTRICT
JACOB K. JAVITS FEDERAL BUILDING
26 FEDERAL PLAZA
NEW YORK, NEW YORK 10278-0090

(3) Lightning Model XP650 Lime Slurry Mixer

The requirement is to provide Lightning Model XP650 lime slurry mixers in Contract 3D (Ocean Beach Well Relocation). The Lightning lime slurry mixer is designed for the controlled and efficient mixing of lime slurry used in pH adjustment and water stabilization. Proper mixing is essential to prevent sedimentation and ensure uniform chemical distribution, preventing pipeline clogging and treatment inefficiencies. This mixer's design supports long-term durability and reliable performance under continuous operation, minimizing maintenance interruptions. The Lightning lime slurry mixer is proprietary to the existing chemical feed system, ensuring optimal compatibility, reducing the need for additional modifications, and maintaining operational consistency within the facility's water treatment processes.

(4) Sparling Instruments Model FM656 Tigermag EP Electromagnetic Flow Meter

The requirement is to provide Sparling Instruments Model FM656 Tigermag EP electromagnetic flow meter in Contract 3D (Ocean Beach Well Relocation). The Sparling Tigermag electromagnetic flow meter is a highly accurate, non-intrusive flow measurement device essential for monitoring water movement in the well and pump facility. Using electromagnetic technology, it provides precise, real-time flow readings without moving parts, reducing mechanical wear and maintenance needs. This meter ensures reliable flow data critical for process optimization, pump performance assessment, and regulatory reporting. As a proprietary component of the facility's existing metering system, the Sparling Tigermag ensures seamless integration, maintaining consistency in calibration, SCADA communication, and flow measurement methodologies.

(5) Encore 700 Diaphragm Metering Pump

The requirement is to provide Encore 700 diaphragm metering pump in Contract 3D (Ocean Beach Well Relocation). The Encore diaphragm metering pump is a high-precision dosing pump used for injecting treatment chemicals such as coagulants, acids, or disinfectants into the water system. Its diaphragm design provides consistent, controlled chemical dosing while minimizing leaks, ensuring safe and efficient treatment processes. This pump supports accurate chemical feed rates, reducing waste and optimizing treatment efficiency. The Encore model is proprietary to the existing chemical feed system, ensuring compatibility with current dosing controls, reducing operational inconsistencies, and simplifying maintenance and spare parts procurement.

(6) Lonza Constant Chlor MC4-50 Calcium Hypochlorite Tablet Chlorinator

The requirement is to provide Lonza Constant Chlor MC4-50 calcium hypochlorite tablet chlorinator in Contract 3D (Ocean Beach Well Relocation). The Lonza calcium hypochlorite tablet chlorinator is a disinfection system that provides controlled chlorine dosing using solid tablets, ensuring a steady and effective disinfection process. This system is particularly suited for well water treatment, offering a reliable solution for microbial control without the complexities of liquid chlorine handling. Its design minimizes operator intervention while providing consistent chlorine residuals necessary for compliance with water safety regulations. The Lonza chlorinator is proprietary to the facility's disinfection system, ensuring continuity in chemical application, reducing training requirements, and maintaining operational efficiency.



DEPARTMENT OF THE ARMY
U.S. ARMY CORPS OF ENGINEERS, NEW YORK DISTRICT
JACOB K. JAVITS FEDERAL BUILDING
26 FEDERAL PLAZA
NEW YORK, NEW YORK 10278-0090

(7) Lutz-Jesco America Corp MEMDOS E 4 Diaphragm Metering Pump

The requirement is to provide Lutz-Jesco America Corp MEMDOS E 4 diaphragm metering pump in Contract 3D (Ocean Beach Well Relocation). The Lutz Jesco diaphragm metering pump is a specialized dosing pump designed for the precise injection of treatment chemicals into the water system. Its diaphragm mechanism ensures leak-free operation, offering a high level of accuracy in chemical dosing to maintain optimal water treatment performance. This pump is critical for metering applications requiring consistent and repeatable dosing, preventing overuse or underdosing of chemicals. The Lutz Jesco model is proprietary to the facility's chemical feed system, ensuring compatibility with existing components, minimizing integration challenges, and supporting efficient long-term maintenance.

(8) SCADA System Integrator (Subcontractor): Eagle Control Corp, Great Rock Automation, and/or PCS Pump & Process

The requirement is to provide a SCADA System Integrator (Subcontractor) from the following: Eagle Control Corp, Great Rock Automation, and/or PCS Pump & Process. The intent is to sole source services from the aforementioned subcontractors for integration of a new water well and associated pump facility into the existing SCADA network at Ocean Beach. The subcontractors will be responsible for programming, configuring, and integrating the well's control systems to ensure seamless operation within the broader water distribution infrastructure. SCADA system integration is a specialized task that requires extensive knowledge of the existing hardware, software, and communication protocols to maintain operational consistency and efficiency. These subcontractors have direct experience with the current SCADA architecture at Ocean Beach and possess the expertise to efficiently integrate the new well and pump facility without disrupting service.

2. Any vendor that wishes to provide an alternate source to the brand names above that is compatible with the above must provide a response with data supporting the claim within 15 business days of this announcement to New York District Corps of Engineers, Contracting Division.

3. This is a market survey and notification of intent only. This is not a request to respond to a solicitation. This requirement will be solicited at a future date.

Tiffany R. Montoya
Technical Manager