

## PERFORMANCE WORK STATEMENT

For

### Scaffolding Platform Rentals and Install/Dismantle – C-5

31 MAR 2025

**1.0 DESCRIPTION OF SERVICES.** The Contractor shall provide tools, materials, supplies, parts, equipment, PPE, transportation, travel, training/inspection option(s), delivery, and labor as necessary to provide the safety critical temporary fall protection on-site Scaffolding Platform Rentals and Install/Dismantle for the C-5 Crown Skin workload in Bldg. 125 which shall be utilized for the maintenance of two (2) C-5 aircraft to be stationed on the flightline at separate intervals dubbed Phase I (C-5 #1) and Phase II (C-5 #2) in support of the 402nd Aircraft Maintenance Group (AMXG) at Robins AFB.

#### 1.1 Over and Above Work. Work discovered during the course of performance that is:

**1.1.1** Within the general scope of the contract, not covered by the line item(s) for the basic work under the contract, and necessary in order to satisfactorily complete the contract.

**1.1.2** Upon discovery of the need for over and above work, the Contractor shall prepare and furnish to the Government a work request. Upon request the Contractor shall promptly submit to the Contracting Officer, a proposal for the over and above work. The Government and Contractor will then negotiate a settlement for the over and above work. Contract modifications will be executed to definitize all over and above work.

**1.2** The Contractor shall provide the scaffolding platform rentals and associated services with the modular building renovations to include but not limited to the following:

| Item #                                                                                                                                                                                                                                               | Item Description                                                                                                                                                                                                                                | QTY   |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| Scaffolding Platform Rentals and Install/Dismantle – C-5<br>(Phase I and Phase II)                                                                                                                                                                   |                                                                                                                                                                                                                                                 |       |
| (Includes the pre-award site visit, work-site prep, 28-day platform rentals and associated labor/materials/supplies, any modifications, inspection/training options, FOB destination delivery/pick up, applicable tags/documentation, and clean-up.) |                                                                                                                                                                                                                                                 |       |
| PHASE I (C-5 #1)                                                                                                                                                                                                                                     |                                                                                                                                                                                                                                                 |       |
| 1                                                                                                                                                                                                                                                    | Fuselage Platform <ul style="list-style-type: none"><li>External, 60' along both sides on the fuselage, with a working level at 24' and 31'. The working level at 31 feet will need to be cantilevered to get closer to the fuselage.</li></ul> | 1 ea. |
| 2                                                                                                                                                                                                                                                    | Fuselage Platform Crossover Bridge <ul style="list-style-type: none"><li>Connects both sides of the fuselage platform</li></ul>                                                                                                                 | 1 ea. |

|                   |                                                                                                                                                                                                                                                                |       |
|-------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 3                 | Cargo Compartment Platform <ul style="list-style-type: none"> <li>Internal, 35' x 15' inside of the fuselage with a working level at 16'</li> </ul>                                                                                                            | 1 ea. |
| 4                 | Hayloft Platform <ul style="list-style-type: none"> <li>Internal, 25' inside of the hayloft with a working level of 6-10'.</li> </ul>                                                                                                                          | 1 ea. |
| --                | FOB Destination Shipping - Freight delivery/1 ea.                                                                                                                                                                                                              | --    |
| --                | <b>Labor</b> – includes all labor for the following Phase I tasks:                                                                                                                                                                                             | --    |
| 5                 | <ul style="list-style-type: none"> <li>Installation/erecting</li> </ul>                                                                                                                                                                                        | 1 ea. |
| 6                 | <ul style="list-style-type: none"> <li>Dismantle</li> </ul>                                                                                                                                                                                                    | 1 ea. |
| 7                 | <ul style="list-style-type: none"> <li>Relocate <ul style="list-style-type: none"> <li>Includes removing associated scaffolding materials/supplies to the designated storage location.</li> </ul> </li> </ul>                                                  | 1 ea. |
| PHASE II (C-5 #2) |                                                                                                                                                                                                                                                                |       |
| 8                 | Fuselage Platform <ul style="list-style-type: none"> <li>External, 60' along both sides on the fuselage, with a working level at 24' and 31'. The working level at 31 feet will need to be cantilevered to get closer to the fuselage.</li> </ul>              | 1 ea. |
| 9                 | Fuselage Platform Crossover Bridge <ul style="list-style-type: none"> <li>Connects both sides of the fuselage platform</li> </ul>                                                                                                                              | 1 ea. |
| 10                | Cargo Compartment Platform <ul style="list-style-type: none"> <li>Internal, 35' x 15' inside of the fuselage with a working level at 16'</li> </ul>                                                                                                            | 1 ea. |
| 11                | Hayloft Platform <ul style="list-style-type: none"> <li>Internal, 25' inside of the hayloft with a working level of 6-10'.</li> </ul>                                                                                                                          | 1 ea. |
| --                | FOB Destination Return Shipping - Freight Pick-up/1 ea.                                                                                                                                                                                                        | --    |
| --                | <b>Scaffolding Labor</b> – includes all labor for the following tasks:                                                                                                                                                                                         | --    |
| 12                | <ul style="list-style-type: none"> <li>Installation/erecting <ul style="list-style-type: none"> <li>Includes removing scaffolding materials/supplies from designated storage location and transporting to Phase II designated worksite.</li> </ul> </li> </ul> | 1 ea. |
| 13                | <ul style="list-style-type: none"> <li>Dismantle</li> </ul>                                                                                                                                                                                                    | 1 ea. |
| 14                | <ul style="list-style-type: none"> <li>Removal</li> </ul>                                                                                                                                                                                                      | 1 ea. |
| --                | Scaffolding Options                                                                                                                                                                                                                                            | --    |
| 15                | Scaffold Platform Inspection(s)<br>(Includes completed platforms for Phase I and II)                                                                                                                                                                           | 6 ea. |

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                 |       |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|-------|
| 16                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Operator Training<br>(Includes completed platforms for Phase I) | 3 ea. |
| <p>Completion of on-site scaffolding platform rental services at Robins AFB for Phase I (C-5 #1) shall be accomplished within sixty-three (63) calendar days after contract award date and Phase II (C-5 #2) scaffolding rental services shall be accomplished within forty-eight (48) calendar days after the completion of Phase I platform(s) dismantling and relocation whereas Phase II shall be erected, dismantled, and picked up within 12-months after the contract award date.<br/>(See para. 1.4.1.1. for additional details for rescheduling option.)</p> <p>--</p> <p><b>**All Items shall be delivered via FOB Destination Shipping**</b></p> |                                                                 |       |

**1.3 Rental Services.** The Contractor shall provide the Scaffolding Platform Rentals and Install/Dismantle – C-5 (Phase I and Phase II) services (as listed in paragraphs 1.0 and 1.2 table) to perform install/erecting and dismantle/relocation/removal/clean up tasks which shall be accomplished by the Contractor within 12 months after contract award date whereas said services shall meet or exceed the Government’s specifications in accordance with the associated environmental and safety and health standards. Also, the Contractor shall ensure that all applicable materials utilized for the completion of the scaffolding services tasks shall be the quality products which include but not limited to the following:

**1.3.1 Meets or exceeds applicable environmental and safety compliance.**

**1.3.1.1 Certifications.** The Contractor shall be certified and compliant IAW the International Organization for Standardization (ISO) 9001:2015 quality management system (QMS) standard as applicable to regulatory, safety/reliability requirements that are in line with the applicable regulatory requirements necessary to achieve effective scaffolding fall arrest protection for the scaffolding platform rental services as listed in para. 1.0 and 1.2 table. Also, Contractor shall provide active certification(s) documentation issued by a certification authority (registrar) on or before contract award date that is equivalent or better than the following standards and regulations:

- a. **Applicable Standards:** The scaffolding platform rentals shall be 100% compliant with applicable Air Force Occupational Safety/Health (AFOSH), OSHA, and ANSI/ASSP rules and regulations as listed that are in effect at time of installation:
  - All equipment supplied in the performance of this contract shall meet the latest applicable standards as detailed in paragraph 2.4. All applicable new or revised standards that are not in effect at time of bid closing but become effective prior to or during system installations shall be identified by the Contractor. The Contractor shall notify the Government of any deviations for system design necessary to maintain compliance with the current revisions for said standards. If the said revised standards conflict with other required

standards, the most stringent standards shall apply.

- Certification of the capacity of the underlying structure. Instead, we will furnish loading information as part of our drawing submittal package for review and approval by the Project Engineer.

b. Occupational Safety & Health Association (OSHA) 29 CFR Part 1910 and 1926 Standards, subpart L to include but not limited to standard 1926.451 and 1926.52.

c. DAFMAN 91-203 - Air Force Occupational Safety, Fire & Health Standards

d. American National Standards Institute (ANSI)/American Society of Safety Professional (ASSP) A10.8-2019 relative to scaffolding safety requirements.

e. Any fall arrest protection standards that would be applicable to the platform design associated with the scaffolding rental services (i.e. guard rails).

**1.3.2 Site-Visit (Optional).** The Contractor shall have an opportunity to attend an optional site visit to review worksite on the flightline at Robins AFB prior to solicitation—said site-visit is not a requirement for contract award.

1.3.2.1 The Contractor shall have the option to provide feedback in writing to the Contracting Officer (CO) concerning inquiries after the site-visit—guidance will be provided to the Contractor by the CO concerning inquiries prior to the start of the said site-visit. Also, the Contractor shall not contact the Government Representative(s) (as listed in para. 4.1.1) concerning site-visit inquiries.

1.3.2.2 This Performance Work Statement (PWS) is subject to change after the site-visit at the Government Representative's discretion.

**1.3.3 Contractor Qualifications.** At minimum, the Contractor shall be qualified to meet or exceed the following scaffolding requirements within but not limited to the scope of business that shall be equivalent or better for the industries scaffolding installation, and/or any other applicable industry expertise relative to the scaffolding platform rentals. Also, the Contractor shall be knowledgeable of—to include but not limited to—the following:

1.3.3.1 Up-to-date OSHA, AFOSH, and ANSI/ASSP standards/regulations (as listed in para. 1.3.1 and the relative work/safety practices for the handling/disposal of applicable materials and performance of processes associated with the scaffolding fall protection tasks to be performed at the designated worksite whereas said tasks involve potential safety hazards and

other associated risks.

- 1.3.3.2 Meet or exceed the any applicable local/state/federal rules and regulations in accordance with current accepted industry standards that regulate the Scaffolding profession and the safety of the occupants utilizing said equipment prior to contract award and for the duration of performance on this contract.
- 1.3.3.3 Scaffolding platform rentals and associated equipment, material/supplies, maintenance, and inspection necessary to meet the requirements of this PWS and the specifications of the original equipment manufacturer (OEM) of the scaffolding platform components.
- 1.3.3.4 Installing/erecting scaffolding platforms within the external layout of an aircraft, within enclosed spaces relative to an aircraft compartment/hayloft and the capabilities for identifying existing/potential fall hazards.
- 1.3.3.5 Ensure all workers are trained and qualified with the scaffolding tasks necessary to meet requirements of the PWS.
- 1.3.3.6 Provide a certified Project Manager (PM) and/or Professional Engineer (PE) that has the skills, knowledge, and necessary certification(s) that is equivalent or better than the qualifications for the current industry expertise of a “Competent Person” (CP) that demonstrates credibility and expertise in the scaffolding field. Also, the said CP shall have and maintain said CP qualifications throughout the duration of the contract performance to ensure a 100% successful outcome for the completion of this requirement in accordance with this PWS in its entirety.
- 1.3.3.7 Provide qualified scaffold erector(s) that has the necessary skills, knowledge, and expertise in accordance with local, state, and federal rules and regulations to include but not limited to the following:
  - a. Erect the scaffolds in accordance with the manufacturer’s recommendations.
  - b. Provide scaffolding platforms that are safe for the user and free from recognizable and preventable hazards from the duration of this contract.
  - c. Ensure that the scaffold platform rentals are equipped with the necessary access, dismounting/exiting the said platform.
  - d. Maintains applicable anchorage and structure integrity for working surfaces that will be utilized by to withstand the weight user(s) and/or materials in accordance with the scaffold industry standards.

- e. Inspect all scaffold components prior to assembly to ensure that said components are matched for compatibility relative to the Government's scaffold platform specifications, quality, and safety standards whereas defective parts shall not be utilized for the any phase of the scaffold platform rental install to include but not limited to the following applicable components: mudsills, screw jacks, frames, braces, planks, access ladders, brackets, and any other components that may be cause safety hazards.

**1.3.4 Drawing/Specs Package.** The Contractor shall provide one (1) set of preliminary design drawings to the Government Representative(s) within three (3) calendar days after contract award date via electronic mail whereas the said design shall be compatible with the applicable scaffolding platform rentals' work areas for Phase I (C-5 #1) and Phase II (C-5 #2) as listed in para. 1.0, 1.2 table, and section 1.3.7). The design drawings shall detail all points associated with the C-5 aircrafts' external and internal structure(s). The Government will review and provide approval for drawing(s) deemed acceptable.

1.3.4.1 After the Government Representative(s) approve the preliminary drawings, the Contractor shall deliver a finalized copy of the selected scaffolding platform rental project drawing(s) and specification(s) package via electronic mail (email) to the Government Representative(s) within two (2) calendar days after receipt of the said Government's approval which shall be stamped by the Contractor's designated Professional Engineer (PE) listed in para. 1.3.3 that meet or exceeds the certification requirements for engineering of said platform rentals which shall be ANSI compliant as listed para. 1.3.1.

1.3.4.2 **Design Modifications.** The Contractor shall notify the Government Representative(s) prior to modifying the initial scaffolding platform rental designs whereas the Government Representative must approve all design modifications prior to inclusion into the initial approved design scheme and the Government Representative(s) will have the option to request drawing modifications as necessary whereas the Contractor shall provide a final copy with the said modifications (if applicable) within 48 hours from date of receipt of said modifications—the Government Representative(s) will notify the Contractor when said drawings are acceptable and approved.

1.3.4.3 **Design Drawings Package.** Contractor shall deliver a preliminary and final design package with drawings and associated documentation for the scaffolding platform rentals and shall include a complete Bill of Materials for all designs within 48 hours after the Government Representative(s) has approved the final copy of the design package. **(CDRL A001, DI-SESS-81002F/T, Developmental Design Drawings/Models and Associated Lists)**

1.3.4.4 **Scaffolding Design(s).** The Contractor shall provide the Phase I and II scaffolding designs for all scaffolding platform rentals which shall comply with the Contractor's OSHA-compliant safety plan for said scaffolding rentals that shall include but not limited to the safety features as listed in para. 1.3.1.

1.3.4.5 After all modifications have been approved by the Government Representative, the Contractor shall deliver a finalized copy of the selected scaffolding platform rental services design drawing(s) via electronic mail (email) within 48 hours after the receipt of the Government's approval whereas the Contractor's designated Professional Engineer (PE) listed in para. 1.3.5.3 that meet or exceeds the certification requirements for engineering of said system which shall be ANSI compliant as listed para. 1.3.5.

1.3.4.6 Drawings provided by the Government will be released to the selected Contractor as requested after the contract award date.

**1.3.5 Schedule.** The Contractor shall contact the Government Representative(s) within 48 hours after contract award concerning the installation of all scaffolding platform rentals, confirm associated platform drawings, and to coordinate the on-site scheduling date/time of the said installation services for Phase I (C-5 #1) and II (C-5 #2) that shall occur as follows:

1.3.5.1 **On-Site Visit(s).** The Contractor shall coordinate with the Government Representative(s) within three (3) calendar days after contract award relative to the services referenced in paragraph 1.0, 1.2 table, and 1.3.7 concerning the details of specific date(s)/time(s) to schedule the on-site visit(s) for the performance of the scaffolding platform rental services at Robins AFB. At that time, the Contractor shall provide the on-site arrival time(s) for performance of said services in writing via electronic mail (email). After a mutually agreed upon date and time, the Contractor shall accomplish the delivery of materials/supplies in conjunction with arrival for on-site visit(s) to perform the said rental services.

1.3.5.2 If the Government Representative is not able to schedule Phase II (C-5 #2) according to the initial scheduling plan, the Government will have the option to re-schedule, said Phase II within twelve (12 months) after the contract award date.

**1.3.6 Initial Walk-Through.** Upon arrival at the designated worksite for Phase I and II, the Contractor shall coordinate with the Government Representative(s) to review the scaffold installation work area and the material/supplies layout area whereas the Government Representative will provide an overview of the scaffolding tasks to be accomplished by the Contractor in accordance with this performance work statement (PWS) prior to the final walk-through for Phases I and Phase II. At that

time, the Contractor shall accomplish the following scaffolding rental services requirements:

- 1.3.6.1 Upon arrival to the worksite at Robins AFB, the Contractor shall provide the Government Representative with a detailed bill of materials (BOM) or equivalent as listed in para. 1.3.18.
- 1.3.6.2 Confirm amount of storage space required for said material, supplies, and/or components and seek approval of Contractor supplied storage units to be utilized.
- 1.3.6.3 The Government will ensure that the designated work area is accessible prior to the Contractor's arrival at Robins AFB.
- 1.3.6.4 The Government will ensure that the designated work area is accessible prior to the Contractor's arrival at Robins AFB.
- 1.3.6.5 **Review Work Area Layout.** The Government Representative(s) will coordinate with the Contractor to provide an overview of the work area layout during Phase I and Phase II tasks whereas the Contractor shall notify the Government concerning Phase I and/or II layout issues/resolutions prior to accomplishing Phase II rental services—the said notification shall apply to Phase II, as applicable.
- 1.3.6.6 **Access to Equipment.** The Government will provide the Contractor with access to the said C-5 aircraft #1 and #2 to conduct the applicable scaffolding rental services as listed in para. 1.0 and 1.2 table.
- 1.3.6.7 **Material/Supplies.** If the Contractor's methods for material handling require general precautions whereas said materials that are brought to the worksite which shall be stored in accordance with the product's labels and/or associated material safety standards whereas the list can be utilized to determine specific protective measures to be taken and the includes the following:
  - a. The Contractor shall deliver materials to the worksite upon arrival to begin work whereas the said materials shall meet the following guidelines:
    - The Contractor shall provide all Materials/supplies necessary to accomplish all scaffolding rental services.
    - The Contractor shall provide quality scaffolding materials/components with safety a top priority for the performance of this requirement whereas the Contractor shall seek approval of the Government Representative prior implementing modifications of



said materials (i.e., adding additional levels to a platform).

- b. Personal protective equipment (PPE) requirements in accordance OSHA guidelines (listed in para. section 1.3.1) to include but not limited to steel toe shoes, safety glasses, and ear plugs. All Contractor PPE shall be at the expense of the Contractor as listed in para. 1.3.8.10.
- c. After the initial walk-through, the Contractor shall provide all necessary materials/supplies and labor to accomplish the scaffolding rental in accordance with this PWS.

**1.3.7 Scaffold Platform Rentals (Phase I and II).** After the delivery of materials/supplies, the Contractor shall provide to the Government Representative(s) the initial 28-day rental period(s) (as listed in para. 1.2 table) which includes the C-5 aircraft external Fuselage area, internal Cargo compartment area, and the internal Hayloft area for both phases {Phase I (C-5 #1) and Phase II (C-5 #2)} for a total of six (6) rental platform designs that shall be installed in the B125 hangar in accordance with the Contractor's Engineering design drawings (listed in para. 1.3.4) which shall include but not limited the following applicable PWS requirements:

1.3.7.1 All (Phase I and II) said rental services to include but not limited to the materials/supplies/workmanship/finished product for the safety-critical scaffolding platform rentals shall meet or exceed the current AFOSH, OSHA, and ANSI rules/regulations/standards (as listed in para. 1.3.1.2) in effect at time of installation and the approval by the Government Representative(s).

1.3.7.2 **Scaffold Platform Type.** The Contractor shall coordinate with the Government Representative(s) concerning the scaffolding platform type (i.e., supported type) in accordance with OSHA 29 CFR 1926.451 (as listed in para. section 1.3.1) to provide a scaffolding platform type that shall consist of the necessary platforms (one or more) supported by rigid, load bearing members, such as poles, legs, frames, outriggers, and/or any other materials/components whereas the said platform shall meet the Government's measurement and safety requirements for each scaffolding platform rental (as listed in para. 1.0 and 1.2 table) for Phase I and II to include but not limited to the following said OSHA requirements:

- a. **Load Capacity.** Each scaffold and scaffold components shall be capable of supporting without failure, its own weight and at four (4) times the maximum intended load applied or transmitted to it relative to the scaffold platform type for Phases I and II design.
- b. Fall protection shall be priority for the duration of the scaffolding rental services contract performance.

- c. If the Contractor determine that there are issues (safety or otherwise), deviation(s) from said requirements must be approved by the Government Representative(s) prior to any modifications.

1.3.7.3 Prior to the delivery of materials/supplies, the Government Representative will coordinate with the Contractor to prepare the necessary on-site Government-approved “lay down” area in the vicinity of the Contractor’s work area to accommodate scaffolding rentals’ materials/supplies. The Contractor shall notify the Government Representative(s) of any issues (i.e., available space, location, etc.) associated with the said “lay down” area at the time of knowledge and prior to placement of materials/supplies whereas any modifications of said area must be approved by the Government Representative(s).

1.3.7.4 The Government Representative will prep the designated “lay down” area prior to the Contractor’s delivery.

1.3.7.5 **Work Area Layout Prep.** Prior to erecting the Phase I scaffolding platform rentals, the Contractor shall coordinate with the Government Representative to confirm that the work area layout is available to be utilized to as a “holding area” for material/supplies to be stationed near the designated aircraft that require the rental services whereas the Contractor shall deliver/unload materials and begin work within fifteen (15) calendar days.

- a. The Contractor shall accomplish work area preparations within fourteen (14) calendar days after contract award date and after the Government’s approved on-site scheduled date.
- b. **Floor Space.** After contract award date, the Government will notify the Contractor concerning the availability of floor space in the work area of B125 which will be prepped to allow the Contractor to implement the performance of the delivery/unloading/install/dismantle/relocation/removal of the scaffolding materials/supplies.
- c. **Storage Space.** During the Contractor’s install/dismantle/removal task, the Government will provide temporary storage space in the building 125 vicinity to allow the Contractor to store the necessary materials/supplies and/or equipment associated with performance of the contract requirements.
- d. The Contractor shall provide the bill of materials to the Government Representative(s) within five (5) calendar days prior to delivery at Robins AFB.

**1.3.8 Phase I (C-5 #1).** The Contractor shall provide three (3) scaffolding rental

platforms that include the following:

1.3.8.1 **Layout (Phase I).** After the Contractor has unloaded the materials/ supplies onto the designated work area layout (as listed in para. 1.3.8.2), the Contractor shall begin Phase I for the on-site scaffolding twenty-day (28) rental services (as listed in para. 1.0, 1.2 table and 1.3.) whereas the Contractor shall accomplish the install/erecting of the scaffold rental and the removal/dismantle/relocate/storage of the said rental materials/ supplies within sixty-three (63) calendar days after contract award date.

1.3.8.2 **Fuselage Area.** The fuselage area scaffolding labor per 28-day rental period shall include but not limited to the following requirements:

- a. Install within five (5) calendar days
- b. Move within eight (8) calendar days
- c. Removal of erected platform within three (3) calendar days
- d. If removal occurs after Phase I, the Contractor shall prepare rental materials/supplies and relocate all items to designated storage unit as listed in para.

1.3.8.3 **Internal Cargo Area.** The internal cargo area scaffolding Labor per 28-day rental period shall include but not limited to the following requirements:

- a. Install within five (5) calendar days
- b. Move within eight (8) calendar days
- c. Removal of erected platform within three (3) calendar days

1.3.8.4 **Hayloft Area Internal Cargo Area.** The internal cargo area scaffolding Labor per 28-day rental period shall include but not limited to the following requirements:

- a. Install within five (5) calendar days
- b. Move within eight (8) calendar days
- c. Removal of erected platform within three (3) calendar days

1.3.8.5 During the performance of work at Robins AFB, the Contractor shall wear the appropriate personal protective equipment (PPE) while performing said scaffolding services tasks in accordance with applicable OSHA safety standards.

**1.3.9 Phase II (C-5 #2).** The Contractor shall accomplish Phase II scaffolding rental services within forty-eight (48) calendar days after receipt of the Government-approved scheduling of the install date which shall include the said rental services in accordance Phase I services listed in para. 1.3.8 and this PWS requirements.

1.3.9.1 After work area has been prepped the Contractor shall deliver and unload the materials/supplies within one (1) calendar as listed in para. The Contractor shall be responsible for any equipment (i.e., crane(s), forklift(s), etc.) required to provide scaffolding platform rental services which shall require approval by the Government Representative prior to delivery at Robins AFB.

**1.3.10 Place of Performance.** The scaffolding rental and clean-up services (as listed in para. 1.0, 1.2 table, and 1.3) shall be accomplished by the Contractor at the worksite inside building 125 located on the WR-ALC flightline at Robins AFB. All Contractor personnel for this requirement shall be unescorted during the performance of these services—the Contractor(s) shall request and must meet the requirements for a Contractor's identification badge that shall allow the Contractor to receive access and perform services at Robins AFB (see section 4.7.4 for further details).

**1.3.11 Post-Phase I and II Walk-Through.** Upon the completion of the scaffolding rental tasks, the Contractor shall coordinate with the Government Representative(s) to review all completed said tasks, inspect the worksite's completed scaffold's, confirm clean-up requirements listed in para. 1.3.6 have been accomplished.

1.3.11.1 **Rental Extension.** If the scheduled rental period ends and the Government's utilization of the scaffolding rental platform(s) requires an extension of the Contractor's scaffolding platform rental services, the Government will have the option—within 12-months after the contract award date—to extend the utilization of the completed scaffolding platform rental(s) period as necessary based on a per-day, per-week, and/or per-month period relative to Phase I (C-5 #1) and Phase II (C-5 #2) prior to the Contractor's dismantling of the said completed scaffolding rental platform(s).

- a. If the Government Representative(s) implements the option to extend said rental services, the Government Representative(s) will coordinate with the Contractor to request an extension of the rental period in accordance with the requirements of this PWS.
- b. The Government will coordinate with the Contractor to schedule a pick-up date prior to the completion of the extended rental.
- c. The Contractor shall provide pick-up services for Contractor's

materials/supplies at no additional expense to the Government.

**1.3.12 Scaffolding Platform Inspection(s) (Phase I and II).** Upon completion of the Phase I and II scaffolding platform rental services, the Contractor shall conduct a walk-through inspection of the erected scaffolding platform(s) while the Government Representative(s) examines the said finished platforms for any safety issues whereas the Government will determine whether all applicable platforms have been “properly erected”. If there are issues found during said inspection, the Contractor shall resolve said issues at the time of knowledge during the inspection or schedule a return date within the contractual lead time which requires approval of said date by the Government Representative(s) and Contracting Officer.

1.3.12.1 The Government Representative shall have the option to request that the Contractor implements an on-site inspection of each completed scaffolding platform(s) (see para. 1.1) in accordance with OSHA guidelines whereas the Government Representative will coordinate the inspections immediately after the completion of each platform and prior to implementing the on-site training option as listed in para. 1.3.

**1.3.13 Operator Training (On-site).** The Government Representative(s) will have the option to include operator and safety training for the completed platform(s) for the Government personnel for a minimum of ten (10) trainees after the completion of Phase I and II platforms whereas the said training must be scheduled and completed within 12 months from the contract award date. If the scaffolding training is requested to be scheduled by the Government Representative(s) (see para. 1.1), the Contractor shall provide the following training in accordance with OSHA guidelines:

1.3.13.1 After the installation is fully complete, the Contractor shall coordinate with the Government Representative(s) to schedule and provide the on-site operator training services for a maximum of ten (10) Government trainees whereas the said training shall be accomplished immediately after the said erection of the scaffolding platforms are complete. Also, the Contractor shall provide a certified training technician with knowledge of the operation of the said platforms. In addition, the scheduled on-site training shall be accomplished within four (4) calendar days after completion of said platform(s).

1.4.1.1 In the event—if the Contractor is unable to perform on the scheduled platform(s) completion/training date(s), the Contractor shall notify the Government Representative(s) and the Contracting Officer within one (1) day of knowledge to immediately reschedule the said training whereas the rescheduled date(s) shall meet the Government Representative(s) approval.

**1.3.14 Clean-up/Disposal.** After the completion of all scaffolding rental services, the Contractor shall implement the following clean-up/disposal measures:

- 1.3.14.1 Ensure all items that were tasked for disposal in para. 1.3.4.3.a are disposed on in the designated dumpster.
- 1.3.14.2 Ensure that worksite shall be free of materials associated with the Contractor's personnel rental services.
- 1.3.14.3 Paint pots shall not be cleaned at sinks or other drainage facilities, nor shall any debris be allowed to run into drainage lines of the building or any location at Robins AFB without the coordination and approval of the Government Representative(s).
- 1.3.14.4 Remove any packaging materials/associated remnants of spillage, debris and/or any other associated items that require "off-base" disposal.
- 1.3.14.5 After clean-up is complete and prior to exiting the worksite, the Contractor shall coordinate with the Government Representative(s) to inspect the work area for approval that the clean-up has been accomplished.
- 1.3.14.6 If the Contractor finds that there are other materials and/or tasks required to complete the performance of the scaffolding rental services, the Contractor shall notify the Government Representative at the time of knowledge. After the Government Representative deems that there is potential for additional work and that the Government approved—the Contractor shall prepare a cost proposal and submit to the designated Contracting Officer to include additional work for the said rental services in accordance with para. 1.1.

**1.3.15 Work-site Requirements.** The Contractor shall adhere to but not limited to the following work-site requirements:

- 1.3.15.1 Upon arrival at the designated worksite at building 125 (flightline), the Contractor shall seek Government Representative(s) approval concerning any issues associated with the performance of the work tasks and/or any other access associated with the selected this requirement—prior to implementing said tasks. Also, Contractor shall adhere to the following special instructions:
  - a. The Contractor shall not store any parts, materials, or equipment on Government property outside of the designated temporary storage location without written approval by the Government Representative(s).
  - b. The Contractor shall provide all necessary equipment to perform the requirements of this contract (as listed in para. 1.0, 1.2 table, and 1.3.8) whereas the Contractor shall not (under any circumstance) utilize any Government equipment to include but not limited to lifts, ladders, stools, tools, etc. during the installation of deliverables under this contract.

**1.3.16 “FOD” Prevention Awareness.** The Contractor shall adhere to AFI 21-101 (paragraph 14.19), Foreign Object Damage (FOD) Prevention Program. The purpose of the FOD program is to eliminate the introduction of any foreign object(s) that could potentially cause damage to any on-site aircraft. Also, the FOD prevention is a critical priority within the aerospace industry which must be accomplished by all contractors throughout the duration of the performance of all contracted on-site services. In addition, FOD can be problematic during operational and maintenance activities which include but not limited to the following FOD impact awareness:

1.3.16.1 FOD can be caused by un-accounted for hardware, safety wire, tools, supplies, etc., during operations and maintenance. Therefore, any loose objects—regardless of their origin—can cause catastrophic and costly damage to an aircraft and/or associated high-end items stationed in high-risk FOD areas.

1.3.16.2 FOD regulations apply to contracted services whereas work is performed and/or travel within, on, around, and/or through potential impactful areas near aircraft, support equipment, engines, and/or components which include but not limited to personnel operating vehicles and/or equipment located on the Air Force Material Command (AFMC) flight lines, runways, taxiways, amps, and/or equipment stationed within aircraft hangars or maintenance areas.

**1.3.17 HAZARDOUS CHEMICALS.** The Contractor shall not release any hazardous and/or dangerous materials on-site at Robins AFB during the execution of this contract. Also, all chemicals, cleaning agents, and/or other required liquids to be used during Contractor performance shall have the applicable Material Safety Data Sheet (MSDS) documentation. In the event, an accidental spill and/or bodily contact related to the MSDS-listed materials occurs during said performance, the Contractor’s MSDS shall be readily available for review as needed.

1.3.17.1 The Contractor shall immediately notify the Government Representative(s) throughout the performance of this contract when the said Contractor has knowledge of any hazardous, dangerous, and/or life-threatening situation.

1.3.17.2 The Contractor shall be responsible for but not limited to the necessary maintenance, fueling, and/or safety of Contractor property (i.e., equipment, tools, vehicles) and/or Contractor personnel. Also, the Contractor shall accomplish the necessary refueling of lift trucks at a designated location outdoors with the approval of the Government Representative(s).

**1.3.18 PERMITS & UTILITY OUTAGES (as applicable).** The Contractor shall obtain the necessary permits and coordinate/maintain awareness of utility outages with the

Government Representative(s) to accomplish contract requirements in accordance with but not limited to the following guidance:

1.3.18.1 The Contractor shall ensure that Contractor Representative(s) attends all permit and outage request meetings.

1.3.18.2 Adequate number and type of portable fire extinguishers, supplied by the contractor, will be as close to the work as possible. At least two 10 lb. ABC type fire extinguishers shall be located at close proximity to the work being performed at all times. The fire inspector issuing the welding/burning permit will determine the required level of protection at the time of permit issuance.

1.3.18.3 Utility outages will be signed off on during the weekly outage meeting held on Wednesdays at 1000 hours in building 1555. Request utility outages in writing to the Base Civil Engineer, with a copy to the Contracting Officer a minimum of twenty-one (21) calendar days before the proposed outage.

1.3.18.4 Outages shall be scheduled at the Government's convenience and may be at times other than normal working hours. For example, the times may be on weekends or during the second and third shifts (including holidays, holiday weekends, and work curtailment days). These are at no additional cost to the Government.

1.3.18.5 Scheduling of outage hours are subject to change—Government Representative(s) with coordinate with the Contractor concerning outage rescheduling.

**1.3.19 Work Completion Certificate.** Upon the completion of all planned rental services work activity, the Contractor's PE shall provide a work completion certification certificate to the Government Representative prior to acceptance via electronically certifying that the selected scaffolding platform rentals are operable in its entirety—to include but not limited to any associated components, the necessary system safety measures, is structurally stable, and meets or exceeds the compliance in accordance with all applicable OSHA/ANSI regulations and standards. **(CDRL A002, DI-MGMT-82050/T NOT 1, Work Completion Certification Certificate)**

**1.3.20 Documentation.** The Contractor shall provide the necessary documentation relative to a detailed Bill of Materials (BOM) or equivalent (as applicable) for materials that shall be utilized for the scaffolding rental services and applicable marking/labeling as listed in para. 1.0, 1.2 table, and 4.20) for Phase I and II to include but not limited to the following. **(See CDRL para. A001)**



1.3.20.1 The said BOM will be utilized by the Government Representative to maintain an accounting of work-related items for the duration of the Contractor's performance of all tasks and the scaffolding rental period.

1.3.20.2 The said BOM shall include all items that require storage accommodations for the scaffolding rental components and any associated storage unit(s) relative to this requirement such as all material/supplies and associated components, quantities/measurements /condition of item (used or new)/value required for setup/storage {such as frames, assemblies/subassemblies, platforms/decks, braces, associated accessories, and any necessary safety equipment (i.e., warning tags)}.

1.3.20.3 Inspection safety tags or equivalent

**1.3.21 Report.** Upon completion of the maintenance and/or repair tasks under the rental services agreement, the Contractor shall provide a copy of the Maintenance Service Report to the Government Representative within 48 hours in .pdf format via electronic mail (email) for all work performed under the contract to include all repairs and/or modifications resulting from those services. **(CDRL A003, DI-MGMT-80995A/T, Maintenance Service Report)**

**1.3.22 Acceptance.** Upon completion of the scaffolding platform rental and associated services whereas all work performed meets or exceeds the Government's specifications for the safe utilization of each platform which includes green tagging that deems each scaffolding platform in its entirety is safe to use, the Government Representative will accomplish acceptance of said services.

**1.3.23 Warranty.** None.

**1.3.24 Deliverables.**

| CDRL# | Document ID           | Title                                                     | Paragraph# |
|-------|-----------------------|-----------------------------------------------------------|------------|
| A001  | DI-SESS-81002F/T      | Developmental Design Drawings/Models and Associated Lists | 1.3.4.3    |
| A002  | DI-MGMT-82050/T NOT 1 | Work Completion Certification Certificate                 | 1.3.19     |
| A003  | DI-MGMT-80995A/T      | Maintenance Service Report                                | 1.3.21     |
| A004  | DI-MGMT-80368A/T      | Status Report/EnMS Training                               | 4.13.2     |
| A005  | DI-SAFT-82080 NOT 1/T | Contractor's Safety Plan                                  | 4.14.1     |
| A006  | DI-SAFT-81563 NOT 2   | Accident/Incident Report                                  | 4.15       |

**2.0 SERVICES SUMMARY (SS).** None

### 3.0 GOVERNMENT FURNISHED PROPERTY (GFP).

None – there is no GFP attachment for this acquisition.

### 4.0 General Information.

**4.1 Government Representatives.** The following individuals will serve as the Primary and Alternate Government Representatives as the points of contact through which all contractor-provided services will be requested and accomplished for AMXG. Government Representatives will not supervise the Contractor, and they are not empowered to make any contractual commitments or to authorize any contractual changes on the Government's behalf. The following individuals will serve as Government Representatives for AMXG.

| Primary Government Representative | Alternate Government Representative |
|-----------------------------------|-------------------------------------|
| Name: Matthew Wiggin              | Name: Anthony Morley                |
| Unit: 402 AMXG                    | Unit: 402 AMXG                      |
| Phone: 478-222-2753               | Phone: 478-222-5516                 |
| Email: matthew.wiggin@us.af.mil   | Email: anthony.morley@us.af.mil     |

**4.2 Shipping/Delivery/Period of Performance.** The Government Representative(s) above will contact the Contractor within three (3) calendar days after contract award concerning the scheduling of the scaffolding platform services listed in para. 1.3. Completion of on-site scaffolding platform rental services at Robins AFB for Phase I (C-5 #1) shall be accomplished within sixty (60) calendar days after contract award date and Phase II (C-5 #2) scaffolding rental services shall be accomplished within forty-eight (48) calendar days after the completion of Phase I platform(s) dismantling and relocation whereas Phase II shall be erected, dismantled, and picked up within 12-months after the contract award date—(See para. 1.4.1.1 for additional details for rescheduling option.). If applicable, any Inspection/training options shall be accomplished within 12-months after contract award date. Also, any associated deliveries coordinated with the Government shall be FOB Destination.

### 4.3 Ship To Address.

Delivery Address:

Attention: Matthew Wiggin

Unit: 402 AMXG

DODAAC: F3Q2AJ

Address: 92 Phantom Street

Bldg 125

Robins AFB, GA 31098

(deliver to this address)

(Note: The scaffolding is to be delivered to Bldg. 125—dock to be specified prior to arrival.)

**4.4 Contractor Program Manager.** The Contractor shall provide a Program Manager who shall be the single point of contact between the Contractor and the Government. The name, phone number, and email address of the Contractor's Program Manager(s) shall be provided in writing to the Contracting Officer, Government Representatives, and/or COR no later than five (5) calendar days after contract award date

**4.5 Place of Performance and Hours of Work.** On-site contract services shall be performed at the Warner Robins Air Logistic Complex. The work will take place in external area of building 125 at Robins Air Force Base, GA. The Contractor's work hours (shifts) shall normally be from 7:00 AM to 4:00 PM EST, Monday through Friday. The Government may adjust the Contractor's work hours based on workload requirements, with the flexibility to start work earlier, work odd shifts, and/or work weekends. The Government will provide the Contractor the required work hours (schedule) for contractor personnel and will provide a 48-hour notice prior to changing any work hours.

**4.6 Recognized Holidays.** Unless otherwise required by the Government, the Contractor shall not have access to Government facilities to work or telework on all federal holidays or during facility closings as authorized by the Government. If the holiday falls on Saturday, it is observed on Friday. If the holiday falls on a Sunday, it is observed on Monday.

#### **4.7 Security Requirements.**

**4.7.1 Government Security Regulations.** The Contractor shall ensure personnel, information, system, facility, and international security requirements are met in accordance with 32 CFR Part 117, National Industrial Security Program Operating Manual (NISPOM), Department of the Air Force Instruction (DAFI) 31-101, Integrated Defense.

**4.7.2 Contractor Security Clearance.** This requirement does not require a security clearance. The Contractor shall ensure Contractor personnel have a valid security clearance appropriate to the access required for proper accomplishment of contract/order requirements. Contractor personnel shall not be authorized access to classified and/or sensitive, but unclassified, information and/or materials or be permitted to work on classified and/or sensitive, but unclassified, projects and/or programs without a proper security clearance and a need-to-know. Contractor personnel whose clearances have been suspended or revoked shall immediately be denied access to classified and/or sensitive, but unclassified, information.

**4.7.2.1 Communications Security (COMSEC).** The Contractor shall use only secure communications methods and/or equipment to transmit or otherwise transfer classified and/or sensitive, but unclassified, information in accordance with 2 CFR Part 117, National Industrial Security Program Operating Manual (NISPOM).

**4.7.3 Access to Government Facilities/Contractor ID (Badging).** The Contractor shall ensure Contractor/subcontractor personnel who require access to Robins AFB or other Government facilities comply with the security requirements of the installation.

4.7.3.1 The Contractor shall ensure a Defense Biometric Identification System (DBIDS) ID card is obtained by all contractor/subcontractor personnel who require recurring access to a Government facility, but not local area network (LAN) access. The Contractor shall submit a letter to the PCO or COR listing all contractor/subcontractor personnel requiring access to the facility. The PCO or COR will approve the request and forward it to the designated badging agent to accomplish Robins AFB access affidavit. The badging agent then submits to "Pass and Registration" for issuance of the contractor's DBIDS ID card. Contractor/subcontractor personnel shall report to the issuing/registration office to obtain the DBIDS ID card(s) with required documentation.

4.7.3.2 All personnel requesting installation Contractor DBIDS ID (credentials) must present a valid state issued identification card or driver's license and a social security card or certified birth certificate or passport before they will be issued a credential. For those operating a motor vehicle on base, they will need to provide valid proof of registration and insurance. If Contractor employees are not a U.S. citizen, they must possess proof showing they are allowed to work in the United States/Georgia. Persons must present a previously issued Contractor identification card if applicable. Any foreign visitor/contractors must coordinate with the Foreign Disclosure Office. DBIDS ID cards are normally valid up to one year.

4.7.3.3 The Air Force has mandated contractors requesting a badging ID, consent to a check of their criminal history prior to being allowed access to installations. The check will be conducted at the Visitor Control Center (VCC) off Watson Boulevard, Robins AFB, GA. Contractors requiring unescorted access will need their driver's license or state-issued ID, and a social security card, which will be checked by name, dates of birth and social security number. The COR will work with the badging agent and the Contractor to submit required documentation to the Visitor Control Center (VCC). The contractor ID card/badge authorizes unescorted entry to Robins AFB for the bearer only. A contractor with a DBIDS ID card does NOT have sponsorship capability.

4.7.3.4 The Contractor shall submit a letter to the PCO immediately if contractor/subcontractor personnel no longer require access, upon transfer/termination of contractor/subcontractor personnel or upon completion/termination of the contract/order. The letter shall identify the name(s) and social security number(s) of the Contractor/subcontractor personnel. The Contractor shall return the ID card(s) to the

issuing/registration office upon expiration, upon transfer/termination of Contractor/subcontractor personnel, or once contractor/subcontractor personnel no longer require access to the facility. If Contractors do not turn in their ID, the Contractor shall contact the designated badging agent to terminate installation access.

**4.7.4 Operations Security (OPSEC).** The purpose of OPSEC is to reduce the vulnerability of USAF missions to adversary collection and exploitation of critical information. The Contractor shall comply with DoDD 5205.02E “DoD Operations Security”, DoD Manual 5205.02-M and AFI 10-701 “Operations Security” to protect United States (U.S. Government interest. The Contractor shall ensure compliance with OPSEC requirements including procedures to protect classified and/or sensitive, but unclassified, Government projects and/or programs. The Contractor shall ensure Contractor personnel who perform work at Robins AFB, or another Government facility comply with the OPSEC procedures of the facility.

**4.7.5 Security Incident or Violation.** The Contractor shall immediately notify the Government Security Office of any potential or actual security incidents or violations including potential or actual unauthorized disclosure or compromise of classified and/or sensitive, but unclassified, information.

**4.7.6 Supply Chain Risk Management.** The Contractor shall implement risk management procedures to ensure that system, equipment, components, software, maintenance equipment, and supplies do not incorporate counterfeit parts, malicious code, or other elements that would allow adversaries to gain access to data and critical program information and disrupt operations. Contractor risk management procedures shall comply with:

- DoDI5000.83 DAFI 63-113, *Technology and Program Protection to Maintain Technological Advantage*
- SAE Aerospace Standard AS5553D, *Counterfeit Electrical, Electronic, and Electromechanical (EEE) Parts; Avoidance, Detection, Mitigation and Disposition*,
- National Institute of Standards and Technology (NIST) Special Publication 800-53 Rev 5, *Security and Privacy Controls for Information Systems and Organizations*

**4.8 Contractor Identification.** Contractor personnel shall wear visible identification designating them as contractors at all times while on Robins Air Force Base.

**4.9 Contractor Vehicle Entry.** The Contractor shall contact the Robins Air Force Base Visitor's Center to and comply with local procedures for obtaining credentials and vehicle entry. Information may be obtained by calling the following phone number: Commercial 478-222-1972.

**4.10 Agency Affirmative Procurement Program).** In accordance with FAR 23.404(b)(1), 100% of purchases of Environmental Protection Agency (EPA)-designated products included in the Comprehensive Procurement Guidelines (CPG) list [<https://www.epa.gov/smm/comprehensive-procurement-guideline-cpg-program>] and/or United States Department of Agriculture (USDA)-designated products included in the bio based product listings [<http://www.biopreferred.gov>] shall, at a minimum, meet the EPA or USDA standards for recovered materials or bio based content, respectively, unless an item cannot be acquired competitively within a realistic timeframe, meet appropriate performance standards, and/or be acquired at a reasonable price.

**4.10.1** In accordance with FAR 23.107-1, the Contractor shall provide estimates and verification of recovered material for EPA-designated CPG products and certification for both EPA-designated CPG products and USDA-designated bio based products. In accordance with the Robins Air Force Base, Georgia / Affirmative Procurement Program (formerly Green Procurement Program (GPP)) Plan, the Contractor shall provide estimates and certifications to the Government for completion of the applicable attachment(s) to be included in the Purchase Request (PR) package.

#### **4.11 Other Government Furnished Equipment and Services.**

**Base Support:** The Government shall furnish property incidental to the place of performance (i.e., ID badges). The contractor shall ensure use of all government provided equipment/facilities is limited to performance of contract related official Government business. Upon completion or termination of the contract or expiration of employee identification passes, the prime contractor shall ensure that all GFE to include equipment and base ID passes, is returned to the WAWF POCs and each individual is processed through the directed Out-processing checklist.

**4.12 Environmental Management System (EMS).** Environmental Management Systems (EMS) Awareness Training: All contractor personnel working on Robins AFB who perform activities on the installation are required to complete Air Force-provided initial EMS Awareness Training. It is the responsibility of the Prime Contractor to ensure that all sub-contractors, vendors, and employees complete this training prior to beginning work on Robins AFB. Notification of training completion shall be sent to the Robins AFB Contracting Officer (CO) to be maintained in the contract file for tracking purposes. Failure to provide documentation of EMS Training may result in termination of the contract.

**4.12.1** EMS training is provided by Environmental Management. Request for Robins EMS Awareness training through email at [78cegv.FrontOfc@us.af.mil](mailto:78cegv.FrontOfc@us.af.mil). Contractors have two options to satisfy the mandatory EMS Awareness Training requirement. (Front Desk: 478-926-8178.)

**4.12.2 Option 1:** Contractors can register for an account through The Environmental Awareness Course Hub (TEACH), the Air Force training database:

<https://usaf.learningbuilder.com/account/login/?ReturnUrl=%2f>

Search for Course ID: EMS110UHHZ00293

Directions:

1. Hover your mouse over the Courses and Transcripts tab.
2. Click on Transcripts
3. Click into the TEACH Course Completion Log by clicking the orange Continue or Begin button.
4. When you are on the transcript, click on the blue “Search for Course” button.
5. When the pop up appears enter the course name or course number and press search.
6. Once you find the course you want to add, click on the +Select button to add the course to your transcript.

(Note: TEACH may not supported by Internet Explorer; recommend using chrome.)

**4.12.3 Option 2:** Contractor requests a copy of the Robins EMS Awareness Training PowerPoint Presentation from Environmental Management. The request should be sent to the Environment Management Workflow Box at the following email address, [78ceg.cev.FrontOfc@us.af.mil](mailto:78ceg.cev.FrontOfc@us.af.mil). Once the presentation is received, the contractor is responsible for ensuring that all his/her employees view the training.

**4.13 ISO 50001-Energy Management System.** Due to the WR-ALC being ISO 50001 certified, all contractors are subject to the Energy Management System (EnMS) requirements and shall abide by certification guidelines whenever applicable.

**4.13.1 EnMS Training.** All contractor personnel working on Robins AFB who perform activities on the installation are required to complete Air Force provided initial EnMS Training. It is the responsibility of the Prime Contractor to ensure that all sub-contractors, vendors, and employees complete this training prior to beginning work on Robins AFB.

4.13.1.1 EnMS training is provided by the Energy Assurance Office. The Contractor shall request the training by sending an email to [402MXSG.MXDEA.EnergyAssurance@us.af.mil](mailto:402MXSG.MXDEA.EnergyAssurance@us.af.mil).

**4.13.2** Notification of training completion shall be sent to the Energy Assurance Office [402MXSG.MXDEA.EnergyAssurance@us.af.mil](mailto:402MXSG.MXDEA.EnergyAssurance@us.af.mil) and the CSMO POC to be maintained for tracking purposes. Failure to provide documentation of EnMS Training prior to beginning work may result in termination of the contract. **(CDRL A004 DI-MGMT-80368A/T, Status Report/EnMS Training)**

**4.14 Contractor Safety Program.** (See Appendix C, Part II, Para 7) The Contractor shall establish and maintain an acceptable safety program in accordance with their accepted Safety and Health Plan. The Air Force is part of the OSHA Voluntary Protection Program (VPP). All shall familiarize themselves with the requirements of VPP. Information on the VPP can be accessed at <http://www.osha.gov/dcsp/vpp/index.html>. Additionally, the Contractor is responsible for the safety and health of all subcontractor employees. No more than two Class C mishaps per contract year and Zero Class A or B mishaps will be tolerated. All changes to the plan must also be submitted in writing and approved by the Government.

**4.14.1 Safety and Health Plan:** Submit draft of company safety plan for review/approval within 10 working days after contract award to 402mxw.se.wf@us.af.mil. Government will have 5 working days to review and return if any changes are noted. If no changes are made or if government does not reply in 5 working days then the draft will be considered the final. Safety plan can be in Contractor format electronically sent. Also submit the Appendix C that was supplied by the Government and annotate in the Appendix C anything the Contractor does not believe is applicable to the type of work to be performed. **(CDRL A005, DI-SAFT-82080/T NOT 1, Contractor's Safety Plan).**

**4.14.2** The Contractor Safety Plan shall address in detail the items listed in the Contract Appendix C, Part II through Part IV as applicable. For task specific procedures identified in the Contract Appendix C, the contractor's internal procedures for those tasks must be identifiable within the submitted Safety Plan or shall be provided in an amendment or addendum to the company's Safety Plan. If task specific procedures identified in the Contract Appendix C, are not submitted with the contractor's Safety Plan, the submitted Safety Plan will be returned as NOT ACCEPTED. The contractor will have 5 working days to resubmit the Safety Plan, amendment, or addendum to address or correct issues identified for non-acceptance. The Safety Office will provide acceptance or non-acceptance of the resubmission within 5 working days of receipt to the government POC who will notify the CO.

**4.15 Mishap Notification.** (See Appendix C, Part II, Para 5) The Contractor shall notify the Robins AFB Safety Office telephonically at (478) 327-4862 during duty hours and (478)-926-3567 after hours, within four (4) hour after initial notification of all mishaps or incidents for damage to DoD property (material plus labor) entrusted by this contract and employee injuries as a result of the contract operation. A follow-up (written or e-mail) of this mishap/incident notification shall be sent within three calendar days to the Government Representative, the Procurement Contracting Officer (PCO), Contract Surveillance Management Office (CSMO) Representative and the Administrative Contracting Officer (ACO) (with a copy to program manager), who will forward it to the Safety Office. The information that is not available at the time of the initial notification shall be provided within 20 calendar days after the mishap. Mishap notification shall contain, as a minimum, the following information:



- a. Contract, Contract Number, Name and Title of Person(s) Reporting
- b Date, Time and exact location of accident/incident
- c. Brief Narrative of accident/incident (Events leading to accident/incident)
- d. Cause of accident/incident, if known
- e. Estimated cost of accident/incident (material and labor to repair/replace)
- f. Impound Authority Name and Phone Number (as applicable)
- g. Nomenclature of equipment and personnel involved in accident/incident
- h. Corrective actions (taken or proposed)
- i. Other pertinent information

**(CDRL A006, DI-SAFT-81563 NOT 2, Accident/Incident Report)**

**4.16 Travel Anticipated.** Travel shall be IAW the Joint Travel Regulation (JTR) and shall require approval in writing by the CO, COR and PM fourteen days prior to start of travel or incurring any travel related expenses. Travel shall be firm fixed price. The Contractor is responsible for making all necessary travel arrangements. The Contractor shall propose all estimated travel costs for each occurrence.

**4.17 Essential Services During Crisis.** The Services Acquisition Lead (SAL) has determined, by placing in writing their decision, that this requirement is not Mission Essential (M-E) in accordance with DFARS 237.76, Continuation of Essential Contractor Services.

**4.18 Inspection of Services/Inspection of Supply:** In accordance with the Inspection of Services clause(s) identified in the contract/order, the Government reserves the right to inspect Contractor performance.

**4.19 Invoice/Payment and Receipt/Acceptance:** In accordance with DFARS clause 252.232-7003, Electronic submission of Payment Requests and Receiving Reports, the Contractor shall submit/process payment requests (invoices, Receiving Reports or combos) and receipt/acceptance documents via Procurement Integrated Enterprise Environment (PIEE) through module Wide Area Workflow (WAWF). Access at the following site: <https://piee.eb.mil/>

**4.20 Marking Requirement:** Unique Item Identification (UID) is required for all items to be delivered to the Department of defense (DoD) that meet the criteria established by the DFARS Clause 252.211-7003.

**4.20.1 Markings/Labels.** The Contractor shall ensure that the scaffolding safety tags (as applicable) listed in para. 1.0, 1.2 table) shall have the applicable markings, labeling, and coloration scheme as necessary that meet the standards and specifications for the applicable safety tag program requirements.

4.20.1.1 The Contractor shall coordinate with the Government Representative with any other associated marking/labeling requirements, concerns, and/or issues within five (5) ARO days relative to the markings/labeling requirements.

## 5.0 APPENDICES.

### 5.1 Appendix A, References:

| <b>Name of Publication</b> | <b>Sections that Apply</b> | <b>Date of Publication</b> | <b>Title of Publication</b>                            |
|----------------------------|----------------------------|----------------------------|--------------------------------------------------------|
| AFI 21-101                 | paragraph 14.19            | Current ver.               | Foreign Object Damage (FOD) Prevention Program         |
| DAFMAN 91-203              | Entirety                   | Current ver.               | Air Force Occupational Safety, Fire & Health Standards |
| OSHA 29 CFR Part 1910      | As applicable              | Current ver.               | Occupational Safety & Health Standards                 |
| OSHA 29 CFR Part 1926      | As applicable              | Current ver.               | Occupational Safety & Health Standards                 |
| ANSI Z359/ASSP             | As applicable              | Current ver.               | Fall arrest protection standards                       |