

Please respond to the following four (4) questions for each of the two projects individually. This will ensure we utilize the information appropriately for each of the projects. Please provide your response via email to the Points of Contacts listed within SAM.gov by the stated deadline.

1) With the scope as stated below for each project, the intent is to require a 300-calendar day period of performance. Is a 300-calendar day period of performance sufficient? If not, what time frame would be recommended?

2) What are current lead times for the following items:

HVAC Equipment _____

Electrical Panels _____

Pre-Engineered Metal Buildings _____

3) How does working at Savannah River Site (SRS) or similar high security operations affect construction duration?

4) Please describe any other risks we should consider when developing our Period of Performance and Schedule.

Scope of Work

Project 1:

Maintenance Building: Two-story +/- 55,000 square foot Maintenance Building with varied programmatic functions including lobbies, vestibules, individual offices, common office work spaces, conference rooms, a single two-story maintenance bay that will also function as a tornado shelter, crew rooms, locker rooms, equipment storage areas, break and lunch rooms, print/ copy rooms, a security office, janitor closets, IT & Communications rooms, an elevator and elevator room, mechanical, electrical and fire-life safety rooms, horizontal & vertical circulation & exiting and other programmatic functions as related to the full function and use of the building. 50-year life. Project includes:

i. A fully sprinkled, two-story engineered steel frame and concrete structure with insulated metal wall and roof panels on an engineered concrete slab over an engineered building pad dimensioned approximately 300' x 115'.

ii. Programmatic rooms and spaces listed above.

iii. A Maintenance Shop housed in the two-story Maintenance Bay with overhead monorail & crane with piping systems for Argon/ Nitrogen/ Compressed Air and welding activities support infrastructure.

iv. Mechanical heating, cooling & ventilation systems.

v. Full civil site design to include rough & final grading, paving, drive & parking aisles, site lighting, sidewalks and other related elements.

vi. Integration of adjacent and supporting underground utility infrastructure at pre-designated points of connection.

vii. Lightning protection system.

viii. Storm water management via metal gutter and downspout system on building and integration with site design.

ix. Interior and exterior building lighting as necessary.

x. Exit signage, building signage and wayfinding.

xi. (3) Accessory Storage Shed Structures integrated with primary building systems related to Maintenance Bay uses described above. One shed for storage of Flammable Fluids, One shed for storage of Flammable Cylinders, and one

shed for functioning and storage of air Compressors. Approximate size of each shed is 10' wide x 20' long x 8' high at lowest point.

Project 2:

Procurement Warehouse: 22,030 square foot procurement warehouse that will be constructed on an engineered building pad and site. The A-E is responsible for design integration of pre-prepared building utility and system infrastructure that are located at pre-determined points of connection. Project includes:

- i. A fully sprinkled, engineered multi-span gabled rigid frame steel structure with insulated metal wall and roof panels on an engineered concrete slab over an engineered building pad dimensioned 200'x 100' with a 35'x 58' side wing.
- ii. Mechanical heating, cooling & ventilation for warehouse and office spaces or other areas as necessary to meet storage and use criteria.
- iii. Exterior Point of Connection for Emergency Power Generator (generator by others).
- iv. Stub-In Interior Points of Connections for potential future Restroom.
- v. Building related site design to include exterior concrete stairs, ramps, sidewalks, guardrails and elements directly attached to the building.
- vi. Interior warehouse office space adjacent the loading dock for 6 employees with fixed or operable aluminum windows that may include an office mezzanine as necessary to meet programmatic requirements.
- vii. Tornado Shelter /Tornado Protected Space for 6 standing individuals.
- viii. Fire riser room and related fire life-safety infrastructure.
- ix. Electrical room or closets and related electrical power infrastructure.
- x. Communications room or closets and related communications & internet technology infrastructure.
- xi. Loading dock & receiving area with (3) 12' wide x 14' high motorized overhead rolling doors.
- xii. Loading dock leveler system and dock bumpers/ protection.
- xiii. Forklift ramp with (1) 12' wide x 20' high motorized overhead rolling door.
- xiv. Lightning protection system.
- xv. Storm water management via metal gutter and downspout system on building that connects to pre-prepared storm water drainage system infrastructure.
- xvi. Interior and exterior building lighting as necessary.
- xvii. Exit signage, building signage and wayfinding.