

JLG Telehandler Repairs

Scope of Work

The Mat Sinking Unit requires a contractor to perform repairs on its JLG 1255 Telehandler. The machine requires repairs to an oil leak, replacing the engine hood, replacing a windshield, replacing the tires, and performing 1000 hour maintenance on the machine. The contractor shall perform repairs at their facility. The government is responsible for transportation of the machine to and from the contractor facility. The contractor shall complete all requirements as listed below in the requirements. All parts shall be replaced with OEM JLG parts. All maintenance shall be performed in accordance with JLG standards and maintenance recommendations. The machine has a Cummins QSF3.8L Tier 4 F engine. All parts replaced in the engine to repair the oil leak shall be Cummins OEM parts.

Machine Info: JGL 1255, Serial # 016013332

Requirements

- Replace crankshaft front seal and oil pump including the following parts:
 - Front Main Seal – 5338295 – 1 each
 - Oil Pump – 5330566 – 1 each
 - Oil Pan Seal – 5256541 – 1 each
 - Front Cover Gasket – 4980605 – 1 each
 - Belt – 70026229 – 1 each (JLG part)
- Remove and replace all four (4) tires with foam filled tires
 - Tire size – 400/75-28 – foam filled – 4 each
- Replace Engine Door including following parts:
 - Hood Assembly – 1001235963S – 1 each
 - Decal – 1001169624 – 1 each
 - Decal – 1001160775 – 1 each
- Replace Windshield:
 - Front Glass Windshield – 1001154419 – 1 each
- Perform 1000 Maintenance on machine:
 - 1000 Hr Maintenance Kit – 1001199740 – 1 each
- Test Machine after all maintenance/repairs are completed
- Wash outside of machine free of dirt/mud/debris

Warranty

The contractor is responsible for a parts and labor warranty on all parts replaced that is equivalent with the manufacturer's warranty that begins from the day that the machine is received by the government after repairs are complete.

Delivery

The Mat Sinking Unit will deliver and retrieve the machine to and from the contractor. The contractor facility shall be located within 80 miles of 2577 Haining Rd, Vicksburg, MS, 39183.

Performance Period

All requirements shall be completed no later than two weeks from the time of award.