

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT		BPA NO.	1. CONTRACT ID CODE	PAGE 1	OF 7	PAGES
2. AMENDMENT/MODIFICATION NUMBER 0004		3. EFFECTIVE DATE 04-03-2025		4. REQUISITION/PURCHASE REQ. NUMBER		
5. PROJECT NUMBER (if applicable) None						
6. ISSUED BY Department of Veterans Affairs NCO 22 - Network Contracting 3601 S. 6th Avenue Tucson AZ 85723		CODE 36C262		7. ADMINISTERED BY (If other than Item 6) Department of Veterans Affairs NCO 22 - Network Contracting 3601 S. 6th Avenue Tucson AZ 85723		
8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code) To all Offerors/Bidders		☒ (X)		9A. AMENDMENT OF SOLICITATION NUMBER 36C26225Q0494		
		☒ (X)		9B. DATED (SEE ITEM 11)		
		☐		10A. MODIFICATION OF CONTRACT/ORDER NUMBER		
				10B. DATED (SEE ITEM 13)		
CODE		FACILITY CODE				
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS						
☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☒ is extended, ☐ is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified. ** HOUR & DATE for Receipt of Offers is EXTENDED to: 04-09-2025 8:00 AM PDT						
12. ACCOUNTING AND APPROPRIATION DATA (If required)						
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.						
CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.					
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).					
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:					
☐	D. OTHER (Specify type of modification and authority)					
E. IMPORTANT: Contractor ☐ is not, ☒ is required to sign this document and return <u>1</u> (one) copies to the issuing office.						
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) The purpose of this amendment is to update the statement of work and extend the offer due date.						
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.						
15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print) Koby Thiel Contracting Specialist				
15B. CONTRACTOR/OFFEROR (Signature of person authorized to sign)		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA (Signature of Contracting Officer)		16C. DATE SIGNED

STATEMENT OF WORK

LOMA LINDA VETERANS AFFAIRS HEALTH CARE SYSTEM REVERSE OSMOSIS, DEIONIZED WATER, AND WATER SOFTENER SYSTEM MAINTENANCE AND SERVICE

I. BACKGROUND

Loma Linda Veterans Affairs Health Care System requires deinstallation, installation, preventative maintenance, inspection, and repair services of reverse osmosis (RO), deionized water (DI), and water softener systems for the campus at its Main Building, 11201 Benton St, Loma Linda, CA 92357 and its Ambulatory Care Center, 26001 Redlands Blvd, Redlands, CA. 92373.

II. DESCRIPTION OF SERVICES

The contractor shall provide all labor, materials, and supervision necessary to install and deinstall systems as well as perform monthly maintenance per manufacturers specifications for each unit listed in section III, "Unit Locations", of this Statement of Work (SOW). The contractor shall provide a copy of the manufacturer's maintenance program per unit at the start of the performance agreement period. The contractor shall supply and maintain a maintenance log at each unit to record resin, membrane, filter, and media replacement, as well as water test dates with results and salt deliveries.

Systems shall be installed (with a delivery method of F.O.B Destination) in conjunction with the designated Loma Linda VA Medical Center POC are to be to the following specifications:

Main Hospital:

- Pretreatment
 - Thermostatic mixing valve to ensure optimal system feed water temperature.
 - Sediment filtration to remove 98% of suspended solids 1 micron and larger.
 - Water softening to aid in prolonging the RO membrane life by reducing hardness.
 - Sampling ports and instrumentation required to meet compliance requirements set forth by AAMI ST1.
- Primary Treatment
 - 14400 GPD reverse osmosis system which removes contaminants from the water to produce AAMI ST108 compliant critical water.
 - DI tanks are maintained to produce the critical water supply below 0.1 micro siemens / cm.

- Sampling ports and instrumentation required to meet compliance requirements set forth by AAMI ST108.
 - Configured for chemical disinfection.
- Storage & distribution:
 - Polypropylene storage tank provides a Critical Water reserve to support peak demands.
 - Stainless steel multi-stage distribution pump with variable speed control.
 - Single-pass ultraviolet disinfection system to inhibit bacterial growth.
 - Bacteria and endotoxin final filter to capture any remaining contaminants upstream of the department.
 - Sampling ports and instrumentation required to meet compliance requirements set forth by AAMI ST108.
- System must monitor the following parameters:
 - Cartridge filter health
 - Water Softener / Anti-Scalant performance
 - Chlorine removal efficacy
 - Reverse osmosis system performance
 - Deionization performance
 - Distribution pump status
 - Ultraviolet disinfection lamp health
 - Supply water conductivity
 - Leak detection with main feed water shutoff
 - Additional parameters reducing unplanned downtime
 - Must have 24/7 service, monitored by technicians
 - A Maintenance plan that meets AAMI ST108 standards and all requirements of this Statement of Work:
 - Scope of testing determined by “AAMI ST108 – Water for the processing of medical devices”
 - Acceptable Water quality determined by AAMI ST108 “Table 2 - Categories and performance qualification levels of water quality for medical device processing”
 - Water quality monitoring per AAMI ST108 “Table 4 Water quality monitoring requirements”
 - Frequency of testing per AAMI ST108 “Table 5 – Frequency for water quality monitoring at water generation system” and “Table 6 – Frequency for water quality monitoring at point of water use”
 - Monthly reports delivered and reviewed with end user

Ambulatory Care Center:

- Must have a minimum 2,500 GPD reverse osmosis system which removes contaminants from the water to produce ANSI/AAMI ST108 compliant Critical Water
- Must have Sampling ports and instrumentation required to meet compliance requirements set forth by ANSI/AAMI ST108 (i.e. carbon filtration product water, RO product water).
- Must provide a minimum 100-Gal storage tank needed to act as a Critical Water reserve to support peak demands.
- Must have a distribution pump with variable speed control capable of >50 psi at 25 gpm, maintaining constant circulation velocity in distribution loop between 3-5 fps.
- Supply and return plumbing interface for a distribution loop of 1" piping needed.
- Must provide a Conductivity meter to monitor supply water quality and calculate reverse osmosis system.
- Must provide differential pressure sensors to monitor cartridge filter health (i.e. sediment, carbon, final)
- Must provide a hardness analyzer to monitor water softener / anti-scalant performance.
- Must provide total residual chlorine monitoring to monitor removal efficacy of carbon treatment.
- Must have Flow meters to monitor reverse osmosis system performance.
- Must provide Conductivity meter monitoring the deionization media and Critical Water supply water quality.
- Water produced by the equipment must maintain the "Critical Water" performance characteristics stated in ANSI/AAMI ST108:2023 Water for the processing of medical devices.
- System must have a Flow meter to monitor flow in the Critical Water recirculation loop.
- System must have a single-pass ultraviolet disinfection system to inhibit bacterial growth.
- System must have Leak detection capabilities with main feed water shutoff.

Inspections will be conducted twice a month on all membranes, resin, filters, UV lights, and media and replaced if needed. All inspections will be coordinated with the Facility Maintenance Point of Contact (POC). The contractor will also inspect salt levels and add salt as needed. The contractor will deliver bags of salt to reverse osmosis, deionized

water, and water softener locations within the VA facility grounds as needed per the manufacturer's specifications for each unit.

WATER SOFTNER/RO SYSTEMS: For medical necessity, reliability, and preventive maintenance all UV lights, resins, membranes, all filters, and media for all units will be replaced at least one time during the base year, first option year, and second option year period of performances regardless of the condition at the time of replacement.

DI SYSTEMS: Resin tanks will be changed at a minimum of four (4) times and filters two (2) times per period of performance year. The contractor will change the resin tanks and filters of all DI water system tanks with new ones regardless of their conditions at the time of replacement. This includes any seals, washers, or gaskets necessary to perform the task and at no additional cost to the government.

Contractor shall provide notification to VA Engineering personnel by phone or e-mail at least 48 hours before delivery or maintenance service will be provided. Contractor shall be available 24 hours 7 days a week; 365 days to respond to emergency maintenance as needed. Response time for emergency service for equipment issues shall be no more than four (4) hours after the emergency call is placed and communicated. The contractor must provide an emergency telephone number for purposes of accepting service calls 24 hours/ 7 days a week. The contractor must acknowledge receipt of notification by calling the Facility Program POC within two (2) hours of the originating call. Contractor is responsible for repairing and restoring reverse osmosis, deionized water, and water softener systems to full performance per manufacturer's specifications.

Only those services specified herein are authorized under this contract. Before performing any service or repairs of a non-contract nature, the Program POC or Contracting Officer must be advised of the reasons for this additional work. If appropriate, the Contracting Officer or his/her designee may authorize the additional services or repairs under a separate purchase authorization. The contractor is cautioned that only the Contracting Officer may authorize additional services or repairs and that reimbursement will not be made unless this prior authorization is obtained.

III. TESTING

- 1) Peracetic acid disinfection of the reverse osmosis system and the Critical Water storage system, distribution system, and loop (billed as a separate line item)

- based on actual frequency) o Requires scheduled equipment down time during dwell period of the disinfectant 2-4 hours
- 2) Replacement of all system filters including pretreatment, carbon, RO membranes, and endotoxin final filters at recommended intervals determined by routine monitoring.
- 3) Regeneration of deionization polishing tanks and replenishment of anti-scalant or softener salt
- 4) Replacement of ultraviolet irradiation systems' lamp(s) and quartz sleeve(s) at annual intervals.
- 5) Emergency service labor and replacement components included for items under warranty.
- 6) Emergency service labor and replacement components billed separately for items not under warranty
- 7) 24/7/365 emergency service call center with a 2-hour phone response time from a service technician.
- 8) Reports provided for all services performed

IV. Sampling

1. The vendor will provide two weeks testing and then Monthly moving forward the following elements, Ph, Alkaline, Hardness, HPC, LAL, TOC, COND, CU, FE, MN, Chloride, Zinc, Nitrate, Phosphate, sulfate, silicate, TDS and Total Chlorine residual and temperature.
2. Regular Sampling: the contractor team will collect water samples at regular intervals as per ANSI/AAMI ST108 standards. These samples will be taken from ten critical test points in the treatment process to ensure comprehensive analysis. Storage Tank, blended supply, after softener after carbon filter after RO membranes and critical cold supply critical cold return, and critical hot supply and critical hot return and critical point of use faucet, utility hot faucet and utility cold faucet.
3. The testing points must include Microbiological Contaminants testing: Microbiological testing is crucial to evaluating the presence of microorganisms in the water that could compromise the sterility of medical devices.
 - a.) Chemical/Physical Parameters: Testing focuses on assessing important parameters such as pH, conductivity, and residual disinfectants such as chlorine which can interfere with the effectiveness of cleaning agents, or indicate maintenance needs to be performed.
 - b.) Organic Contaminants: Organic contaminants, such as TOC (Total Organic Carbon) can provide a favorable environment for microbial growth.
 - c.) Corrosive Agents: Chloride, nitrate, and iron are examples of corrosive agents that can corrode even stain.

VII. FEDERAL HOLIDAYS

New Year's Day	01 January
Martin Luther King's Birthday	3rd Monday in
January President's Day	3rd Monday in
February	
Memorial Day	Last Monday in May
Juneteenth	19 June
Independence Day	04 July
Labor Day	1st Monday in September
Columbus Day	2nd Monday in October
Veterans Day	11 November
Thanksgiving Day	4th Thursday in November
Christmas Day	25 th of December

If a holiday falls on Sunday, the following Monday shall be observed as the National Holiday. When a holiday falls on a Saturday, the preceding Friday is observed as a National Holiday by U.S. Government agencies.

VIII. BADGES AND PARKING

All contractor personnel are required to wear I.D. badges during the entire time he/she is on Government property. I.D. badges must have an identification picture and shall state the name of the individual and the company he/she represents.

It is the responsibility of the contractor's personnel to park in the appropriate designated parking areas. Parking information is available from Police Service. Loma Linda will not validate or make reimbursement for parking violations of the contractor's personnel under any circumstance.

IX. OVER AND ABOVE REPAIR:

Upon discovery of over and above repairs or unforeseen requirements, Contractor shall immediately notify the POC. Parts shall not be procured nor installation or repairs initiated until approval is obtained from the Contracting Officer and appropriate Facilities Staff/POC. Charges for repair, labor and parts shall originate only when required and upon prior approval being granted by the Contracting Officer.