

DESCRIPTION AND SPECIFICATIONS

Statement of Work (SOW)

C.1. PURPOSE AND SCOPE

1.1. This Multiple Award Task Order Contract (MATOC) is an Indefinite Delivery/Indefinite Quantity (ID/IQ) contract for a broad range of maintenance, repair, and alteration projects. Inclusive are maintenance, repair, remodeling, renovation and minor new construction which may include incidental design services. Both Design-Bid-Build (from here on referenced as construction) and Design-Build (design and construction) type projects may be performed under this contract. Design-Bid-Build (Construction) is defined as the traditional delivery method for construction projects where design and construction are sequential and contracted for separately with two contracts and two contractors. The drawings and specifications created under an initial Architect/Engineer contract are used as the bid documents in the following construction contract. Whereas, Design-Build combines the architectural, engineering, and construction services required for a project into a single contractual agreement. Under such an agreement, the Government contracts with a single entity; the contractor providing the end product is responsible for both design and construction.

1.1.1. Bids or proposals to complete an individual project will be requested by issuance of a Request for Task Order Proposal (RTOPs). Resulting awards will be issued as Task Order's (TOs). The Contractor shall have an office located within 150 mile radius to Fort Benning, Georgia. All work will be performed on real property located in facilities assigned to Fort Benning, Georgia, the Army Ranger Facility at Camp Frank D. Merrill, Dahlonga, Georgia, Camp James E. Rudder at Eglin Air Force Base and the Directorate of Family Morale, Welfare and Recreation (DFMWR) Recreation Center in Destin, Florida.

1.2. The primary goal of the MATOC is speedy acquisition of government facility construction requirements. In the event of an emergency requirement, the contractor's response time for pre-bid/proposal site visit and bid/proposal submission may be severely shortened. Therefore, it is imperative that contractors, and/or their representative, designate an individual who has the authority to bind or otherwise obligate the company.

1.3. The TOs will vary in size ranging from \$2,000.00 to approximately \$5,000,000.00 with most anticipated to be between \$25,000.00 to \$5,000,000.00. Majority of the work will be performed on administrative, recreational, billeting, workshops, and maintenance and training facilities. Projects to include tasks in a variety of trades such as carpentry, roofing, excavation, interior work (to include remodeling and interior modifications), electrical work, steam fittings, plumbing, sheet metal, painting, demolition, concrete masonry, welding, mechanical, landscaping, and other general construction work.

1.4. Contractor Responsibility. Provide all parts, labor, plant, equipment, material, supplies, supervision, management, transportation, and all other requirements to successfully perform all MATOC projects. Work shall be performed in strict accordance with all terms and conditions of the MATOC and resulting TO, to include but not limited to, the TO Statement of Work (SOW), specifications, drawings, applicable wage determinations and all other documents incorporated into the TO.

1.4.1. The MATOC Contractor(s) (from here on referenced as Contractor(s)) shall be responsible for all costs associated with fulfilling the requirements of each individual TO. They shall ensure compliance with best commercial practices of the trade, or class of work involved, and that work is executed in a careful and orderly manner by workmen skilled in their respective trades. All applicable codes, laws, and regulatory requirements shall be adhered to while performing work under this contract.

C.2. WORK BY THE GOVERNMENT. The Government reserves the right to undertake performance by Government forces or other Contractors, for the same type or similar work as contracted for herein, as the Government deems necessary or desirable, and to do so will not breach or otherwise violate this contract.

C.3. PLACE OF PERFORMANCE

Construction work performed under this MATOC will be at Fort Benning, GA, which is located southeast of the city of Columbus, in Muscogee and Chattahoochee counties, GA, and Russell County, AL. Work will also be performed at the Army Ranger Facility which is located at Camp Frank D. Merrill, Dahlonega, Georgia, Camp James E. Rudder at Eglin Air Force Base and the Directorate of Family Moral, Welfare and Recreation (DFMWR) Recreation Center in Destin, FL. All locations are easily accessible by rail and public highways.

C.4. HOURS OF OPERATION

4.1. Working hours for the Contractor will be 8:00 A.M. to 4:30 P.M., Monday through Friday, excluding Saturdays, Sundays, and Federal Holidays. If the Contractor wishes to work during periods other than above, additional Government inspection forces will be required. The Contractor must notify the Contracting Officer (KO) three (3) working days in advance of his/her intention to work during other periods to allow assignment of additional inspection forces when the Contracting Officer determines that the additional inspection force is reasonably available. All inspections will be done during normal duty hours. Due to certain circumstances (i.e., emergencies or urgent requirements), deviation of contractor's working hours will be as indicated in the RTOP.

4.2. Federal Installations under this contract observe the following legal holidays:

- New Year's Day, 1 January
- Martin Luther King's Birthday, Third Monday in January
- President's Day, Third Monday in February
- Memorial Day, Last Monday in May
- Independence Day, 4 July
- Labor Day, First Monday in September
- Columbus Day, Second Monday in October
- Veterans Day, 11 November
- Thanksgiving Day, Fourth Thursday in November
- Christmas Day, 25 December

NOTE: Any of the above holidays falling on a Saturday will be observed on the preceding Friday. Holidays falling on a Sunday will be observed on the following Monday. The normal hours of work on the previously identified federal installations are from 8:00 A.M. to 4:30 P.M., Monday through Friday, excluding holidays. Access to work sites may be restricted to these hours and days. Work that requires inspection during accomplishment or that prevents inspection of a previous work after accomplishment normally will not be allowed during other than the normal work hours specified above.

C.5. CONTRACTOR PERSONNEL

5.1. The Government will not exercise any supervision or control over contractor or subcontractor employees (from here on referenced as employees) performing work under the contract. Such employees shall be accountable solely to the Contractor, not the Government. The Contractor, in turn, shall be accountable to the Government for all contractor employees.

5.2. The Contractor is fully responsible for the performance and conduct of their employees at all times while on Government property performing work under the contract.

5.3. The Contractor shall take appropriate personnel action, as required, in the event any employee becomes involved with civilian or local authorities because of misconduct. The Contractor's employees are subject to the same general rules of conduct while on the Government installation that apply to Government civilian employees.

5.4. The Government reserves the right to refuse access to Government installation grounds to any contractor employee if the KO determines it to be in the best interest of the Government.

5.5. The Contractor shall not allow any employee to perform work under the contract while under the influence of alcohol, drugs, or any other incapacitating agent.

5.6. All Contractors' employees, including existing and new employees, are required to be verified through the Government's E-Verify System which confirms employees are authorized and eligible to work in the United States. Assurance of compliance with the provisions of this article by subcontractors is the Contractor's responsibility.

C.6. PROGRAM MANAGEMENT

6.1. As a minimum, the overall program manager(s) for the Contractor shall be authorized as a legal representative of the contractor who can sign contracts and other legally binding documents related to the contract on the Contractor's behalf. The program manager or other authorized legal representative shall be available within 2 hours to meet on-site with Government personnel.

6.2. The Program Manager shall have the level of experience and competency required to successfully manage all business related, construction, and design, if applicable, work performed under the contract.

6.3. The Program Manager shall have the ability to manage and control multiple projects with experienced contractor and subcontractor personnel at multiple job locations. They shall ensure all personnel are qualified, competent, and capable of handling all assigned tasks.

6.4. Assign a Site-Superintendent for each project in accordance with FAR 52.236-6 Superintendence by the Contractor. A working site-superintendent may be authorized for projects that are under \$150,000 or as indicated in the RTOR.

6.5. Program Manager, project superintendents and engineers must read, write, and speak fluent English.

C.7. PROGRESS SCHEDULE. The Contractor shall submit within five days after receipt of the TO, to the KO for approval, a practicable schedule for each TO awarded over \$150,000.00 and for a period of actual work performance exceeding sixty (60) calendar days. The Government reserves the right to request a schedule in TOs awarded for less than \$150,000.00 and/or that last for less than sixty (60) days. Schedule shall comply with FAR 52.236-15 -- Schedules for Construction Contracts.

C.7.1 The Contractor shall enter the actual progress on a progress report as directed by the Contracting Officer, and upon doing so shall immediately deliver three (3) copies of the annotated progress report to the Contracting Officer. If it is the opinion of the Contracting Officer that the Contractor has fallen behind the approved schedule, the Contractor shall take steps necessary to improve its progress, including those that may be required by the Contracting Officer, without additional cost to the Government. In this circumstance, the Contracting Officer may require the Contractor to increase the number of shifts, overtime operations, days of work, and/or the amount of construction plant, and to submit for approval any supplementary schedule or schedules in chart form as the Contracting Officer deems necessary to demonstrate how the approved rate of progress shall be regained.

C.8. PROGRESS MEETINGS. Contractor interface with the Government will be on a continual basis, and periodic meetings are expected to discuss the progress and quality of work being performed. The Contractor's representative (i.e., Project Site-Superintendent) shall be available to meet with the KO and/or Contracting Officer's Representative (COR)/ Inspector at the job site, or other designated site, to discuss work progress. Meetings will be scheduled by the KO and/or COR/Inspector with timely notification to the Contractor. At the progress meetings, the Contractor shall demonstrate work progress utilizing the government approved Construction Schedule.

C.9. RECORD AND AS-BUILT DRAWINGS:

9.1. . Definitions

9.1.1. Record Drawings. Are identified as the Government's most recent as-built drawings of existing facilities.

9.1.2. As-Built. Final drawings that are submitted by the contractor upon completion of the project and prior to final payment.

9.2. At the job site and as work progresses, the Contractor shall keep an accurate record of all changes and corrections to the drawings, as applicable. The as-built drawings shall indicate, in addition to all changes and corrections, all physical changes to the construction area and the actual location of all new utility lines. At the time of beneficial occupancy of each structure or facility involved under the contract, the Contractor shall submit to the KO "as built" prints showing the aforementioned data. If the Contractor fails to maintain the as-built drawings as required herein, the KO will consider that satisfactory progress has not been achieved for the period in question, thereby requiring the retention of up to 10% of any payments to be made until such drawings are made correct. Estimated cost of preparing the as-built drawings will be deducted from any such payment. The Contractor shall provide the Government with two (2) sets of hard white prints (24" x 36", D size) and one (1) CD disk in Micro Station (V8) or AutoCAD format of the as-built drawings. All final drawings shall be to scale as indicated on drawings.

C.10. CONSTRUCTION SITE STANDARDS. The Contractor is reminded that the construction site must be operated and maintained according to contract specifications and is subject to inspection and enforcement according to all federal, state and local codes/regulations.

C.11. AVAILABILITY OF WORK SITE

11.1. The Contractor shall coordinate the work so as to allow minimum inconvenience to the Government.

11.2. If deviation from official contract work hours is required; the Contractor shall submit a written request to deviate from official work hours three (3) working days in advance of the requirement to the KO and include:

- 1) State reason why deviation is necessary
 - a) Requested working hours
 - b) Dates required and/or duration
- 2) Work to be performed
- 3) Confirm if digging, utility cut-offs, or other work requiring Construction Contract Inspector will be done
- 4) Indicate if work will or will not be at an additional cost to the government
- 5) Indicate that the work will or will not have any adverse effect on daily government activity

11.3. The Contractor will continue performing during official contract work hours until KO's approval is obtained to deviate.

C.12. CONSTRUCTION SITE MAINTENANCE. The Contractor shall store all supplies and equipment on project site so as to preclude theft or damage. Maintain site in a neat and orderly manner. Protection and security for materials and equipment on site is the sole responsibility of the Contractor. The Contractor may be required to install temporary construction fencing to protect the site, at no cost to the Government.

C.13. WORK IN SPECIAL SECURITY AREAS. The Government shall provide all escorts if contractor accesses to security areas, while working on construction projects, is required.

C.14. SUB-CONTRACTS. MATOC contractors shall comply with requirements set forth in 52.222-11 -- Subcontracts (Labor Standards), to include but not limited to, prompt submission of Standard Form (SF) 1413, Statement and Acknowledgment with all applicable clauses, prior to sub-contractor performance.

C.15. TEMPORARY STORAGE FACILITIES

15.1. The location for exterior stock piling (laydown yard) of materials shall be indicated in the RTOR. The Contractor shall be responsible for protecting any authorized materials stored or stockpiled against weather, damage, theft, and other risks of loss. The Government assumes no responsibility for any material or equipment left in the storage area.

15.2. If approved by the KO for placement at any project site, all contractor-owned construction sheds, trailers, offices or other such facilities requiring utility services shall be metered, at contractor's expense, for each utility involved. Utility expenses shall be borne by the Contractor.

C.16. ON-SITE OFFICE TRAILERS. If a trailer is required for work and at the discretion of the Government, an office trailer may be located at the project site. The Contractor shall request KO approval for the trailer location. The Contractor shall make the request in writing at least seven (7) calendar days prior to the pre-construction meeting. All office trailers shall be located in areas as directed by the KO and/or COR/Inspector. Any office trailer shall not be more than 10' x 32' in size, provided with a skirt on all sides, in like-new condition, and painted in accordance with the appropriate installation guidance. Office trailers in need of painting and/or repairs, or that are in an unsightly condition will not be allowed at the project site. Displayed on the exterior of all trailers shall be a nameplate which has the name of the Contractor's company, name for Contractor's point(s) of contact (POC) and telephone number where he/she can be reached, contract number, project number and title, and date trailer was placed on site where located.

C.17. STORAGE TRAILERS/FACILITIES STORAGE UNITS

17.1. Unless otherwise indicated, no storage facilities are available for contractor owned materials. Buildings and structures that are part of the contract may be used for storage providing the space is not required for occupancy and contractor accepts full responsibility for the materials stored therein.

17.2. Availability and size of the material laydown yard shall be restricted as noted on the RTOR documents. The Contractor shall consolidate all bulk and/or large quantities of materials at the construction site in area(s) approved by the KO and/or COR/Inspector. All such items shall be stored neatly grouped together. Bulky or unsightly construction materials, heavy and/or light equipment, or tanks shall not be delivered to or stored on the construction site for any period longer than seven (7) calendar days prior to use, installation in the project, or start of construction. The Contractor shall store all supplies and equipment on project site so as to preclude theft or damage. Protection and security for materials and equipment on site is the sole responsibility of the Contractor. The Contractor shall not use any area(s) for material or equipment storage that has not been approved by the KO.

17.3. The size and color of storage units, CONEX boxes, and dumpsters shall be discussed and approved by the KO and/or COR/

17.4. Government Inspector during the pre-construction conference. All storage units shall be painted in accordance with all appropriate installation guidance. Displayed on the exterior of all storage units shall be a nameplate with the name of the Contractor's company, name for Contractor's point(s) of contact (POC) and telephone number where they can be reached, contract number, project number and title, and date unit was placed on site where located.

C.18. SITE ACCESS. When roads and thoroughfares are available, the Contractor shall use established roadways when transporting personnel and/or material in the execution of work. The Contractor shall strictly adhere to the foregoing and shall not develop new ingress or egress roads without specific written instructions from the KO. Streams, trails, and alternate access routes may only be utilized upon prior approval of the KO. Extreme

care must be utilized to prevent the harm of Government Installation property and endangered plants, species, and wildlife.

C.19. PARKING. Contractor or employees shall not park any privately owned vehicle (POV) or company and/or delivery vehicle on grassy areas near or in the construction site without prior approval from the KO. When allowed, parking on grassy areas will only be for short-term delivery purposes (to include heavy tools, equipment, construction materials, etc.). Use designated hard surfaces or existing parking lots near or within the project site for parking of POVs or company and/or delivery vehicles. Tire and track impressions (ruts) created on wet or soft soil by vehicles and/or equipment used in the Contractor's operations shall not be left for more than one day after removal of such vehicle or equipment that caused the rutting. The Contractor shall restore the affected area(s) of the site to its original condition within that one-day period.

C.20. EXCAVATIONS REQUIREMENTS

20.1. The Contractor shall coordinate through the COR/Government Inspector to obtain excavation permits. The contractor shall ensure that utility clearances have been obtained prior to performing work under an individual TO.

20.1.1. The Contractor shall have a completed and approved Directorate of Public Works Excavation Permit in their possession prior to any excavation, to include sign or fence-post holes. All land disturbance shall comply with the Fort Benning Form 144-R, Record of Environmental Consideration or as indicated in the RTOR.

20.2. The Contractor shall be responsible for coordinating the locating of government-owned communication lines prior to excavation.

20.2.1. The Contractor shall contact "811," the Utility Protection Agency, and obtain a ticket number receipt to locate utility lines at least 72 hours prior to any excavation or as indicated in the RTOR.

20.2.2. The Contractor shall contact the Fort Benning Directorate of Public Works, (706) 545-7264, with the Utilities Protection Center (UPC) ticket number.

20.3. Utilities are usually located within 5-10 workdays from the date of request, but due to weather conditions, construction workloads, etc., longer periods of time for these utility locates may be experienced.

20.4. Responsible for coordination with any known or suspected non-governmental utilities such as telecommunications or cable television. The permit will remain valid for a period of 14 days or as otherwise directed by the issuing authority.

20.5. Utility locations, if and when shown on drawings, are approximate. The Contractor shall field verify all utility locations and have the appropriate utility company mark their location before digging or trenching. This shall include but is not limited to the use of sonic, electronic or magnetic detection devices, by noting pull box and utility box locations at the surface, and by potholing. The Contractor shall be responsible for repairing any utilities damaged during construction at no additional cost to the Government.

C.21. MARKINGS

21.1. After the markings have been made, Contractors are required to maintain a minimum clearance of two feet between a marked, underground utility line and the cutting edge of any power-operated excavating equipment.

21.2. The Contractor shall maintain any paint marks or stakes indicating underground utilities/lines as required during the duration of work or 30 calendar days from date of approved permit (whichever is later).

C.22. DAMAGE TO UTILITIES

22.1. In the event of a contractor-caused utility failure/disruption, the Contractor will first make the area safe, then immediately contact DPW Emergency Maintenance Division, (706) 545-2135, the KO, and the COR/Government Inspector.

22.2. If, during the course of excavation, a utility line has been exposed, before backfilling, the Contractor must inspect these utilities to ascertain if the utilities have been damaged. If damage of any kind is discovered or suspected, it is the Contractor's responsibility to immediately notify the utility owner directly. The Contractor must **NOT** attempt to repair damaged utilities.

22.3. If the damaged utilities were previously known or shown to the Contractor, or there is negligence on their part, the utilities shall be repaired at the Contractor's expense. If the damaged utilities were not known or shown to the Contractor, and there is no negligence on their part, then they will be repaired at Government expense.

C.23. EXISTING UTILITIES

23.1. All temporary outages of any utility services required for the performance of work shall be scheduled through the COR/Government Inspector no less than ten (10) calendar days in advance of such outages. The proposed schedule of outage shall include at a minimum: Dates and duration of outages, type of service disrupted, and location of outage required. The Contractor may request waiver from this requirement from the COR/Government Inspector when the utility outage will be of a very limited nature (e.g., a small portion of a facility or site, single building, etc.).

23.2. If during work performance, the Contractor has determined that a utility-related situation involves risk to life or substantial risk to property, utilities shall be immediately disrupted to reduce the emergency and alleviate risk. If such a risk exists, or if such a disruption does occur, the Contractor shall immediately (in no case more than one (1) hour following the occurrence) notify the KO and COR/Government Inspector verbally and follow it up in writing within four (4) working hours from occurrence.

23.3. Utilities included shall be indicated in the individual RTOR.

23.4. The Contractor shall plan his work to minimize all outages. The Contractor will not be permitted to perform work requiring a utility outage during normal work hours without prior approval from the KO and/or COR/Government Inspector.

C.24. SECURITY REQUIREMENTS

The Contractor shall comply with Government personal identity verification procedures implemented in Homeland Security Presidential Directive (HSPD) – 12, Office of Management and Budget (OMB) Guidance M-05-24, and Federal Information Processing Standards Publication (FISP PUB) number 201. Contractor and all associated subcontractor employees shall comply with applicable installation, facility and area commander installation/facility access and local security policies and procedures provided by government representative. The contractor shall also provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office. Contractor workforce shall comply with all personal identity verification requirements as directed by Department of Defense (DoD), Headquarters Department of the Army (HQDA) and/or local policy. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

C.24.1 AT Level I Training: All contractor employees, to include subcontractor employees, requiring access Army installations, facilities and controlled access areas shall complete AT Level I awareness training within 30 calendar

days after contract start date or effective date of incorporation of this requirement into the contract, whichever is applicable. The contractor shall submit certificates of completion for each affected contractor employee and subcontractor employee, to the COR or to the contracting officer, if a COR is not assigned, within 30 calendar days after completion of training by all employees and subcontractor personnel. AT level I awareness training is available at the following website: <http://jko.jten.mil>. AT Level I training is an annual requirement if option years are exercised.

C.24.2 Access and General Protection/Security Policy and Procedures: Contractor and all associated sub-contractors employees shall provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office. Contractor workforce must comply with all personal identity verification requirements (FAR clause 52.204-9, Personal Identity Verification of Contractor Personnel) as directed by DOD, HQDA and/or local policy. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

C.24.2a Contractors Requiring a Common Access Card (CAC): N/A.

C.24.2 b Contractors that do not Require CAC, but Require Access to a DoD Facility or Installation: Contractor and all associated sub-contractors employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (TSDB) (Army Directive 2014-05/AR 190-13), applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative), or, at OCONUS locations, in accordance with status of forces agreements and other theater regulations.

C.24.3 AT Awareness Training for Contractor Personnel Traveling Overseas: N/A.

C.24.4 iWATCH Training: The contractor and all associated sub-contractors shall brief all employees on the local iWATCH program (training standards provided by the requiring activity ATO). This local developed training will be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR. This training shall be completed within 30 calendar days of contract award and within 30 calendar days of new employees commencing performance with the results reported to the COR NLT 30 calendar days after contract award.

C.24.5 Army Training Certification Tracking System (ATCTS) Registration for Contractor Employees who Require Access to Government Information Systems: N/A.

C.24.6 OPSEC Standing Operating Procedure/Plan: The contractor shall adhere to the Government's Operations Security (OPSEC) Standard Operating Procedure (SOP)/Plan during the entire period of performance.

C.24.7 Operations Security (OPSEC) Training: N/A.

C.24.8 Information Assurance (IA)/Information Technology (IT) Training: N/A.

C.24.9 Information Assurance (IA)/Information Technology (IT) certification: N/A.

C.24.10 Contractors Authorized to Accompany the Force: N/A.

C.24.11 Performance or Delivery in a Foreign Country: N/A.

C.24.12 Handling or Access to Classified Information: N/A.

C.24.13 Threat Awareness Reporting Program: N/A.

Additionally, the contractor shall adhere and conform to all safety, security and attendance requirements that apply to the supported office. The contractor is required to attend and participate in all organizational meetings, training, and emergency preparedness events and is required to vacate the Government office work site when no sufficient Government oversight is available.

C.25. SECURITY PLANNING

25.1 General

25.1.1 All personnel employed by the Contractor in the performance of this contract, or any representative of the Contractor entering the federal installation shall abide by all security instructions and directives of the Directorate of Emergency Services (DES), Ft. Benning, GA. Employees are responsible for safeguarding all government property provided for contractor use.

25.1.2 At the close for each work period, government facilities, equipment, and materials shall be secured, lights, heat and water turned off and all doors and window secured.

25.1.3 The Contractor and subcontractor shall not employ persons for work on this contract if such employee is identified as a potential threat to the health, safety, security, general well being or operational mission of the installation and its population, nor shall the Contractor or subcontractor employ persons under this contract who have an outstanding criminal warrant as identified during the Criminal Background Check.

25.1.4 Contractors shall ensure their employees and those of their subcontracts have the proper credentials allowing them to work in the United States. Employees and subcontractors determined to be undocumented or illegal aliens will be referred to the proper authorities.

25.1.5 The Contractor shall not be entitled to any compensation for delays or expenses associated with complying with the provisions of this clause. Furthermore, nothing in this clause shall excuse the Contractor from proceeding with the contract as required.

25.1.6 All contractors and subcontractors when working in a controlled, restricted or other sensitive areas must be escorted at all times. The military agency or unit responsible for the project or work is responsible for providing the escorts. The Contractor shall follow existing procedures and instructions for obtaining entrance to restricted or controlled areas.

25.2 Badging and Identification (ID) Policy

25.2.1 For identification and security purposes, contractor employees shall wear badges at all times, when performing work under this contract. Additional contractor personnel identification is neither required nor recommended.

25.3 Background Checks

25.3.1 A favorable Criminal Background History (CBH) check will be completed for all contractors, subcontractors, and their employees prior to being granted access/entry onto the federal installations identified under this contract. CBH checks will be considered current for a 24-month period from the date they were obtained, and valid for all contracts performed within the 24-month time period. Additionally, as the service and higher headquarters guidance becomes available, DES will randomly select and conduct National Crime Information Center (NCIC) checks w/fingerprints and US Citizenship and Immigration Services (USCIS) checks on **100%** of contractors, subcontractors, and their employees prior to issuing installation entry credentials. In the interim, local warrants and limited criminal history checks will be conducted via Division of Criminal Investigations (DCI). **NOTE:** Contractors may request exceptions to these requirements and procedures through the contracting office. The installation commander or designated representative must approve all exceptions to these requirements.

25.3.2 There are multiple sources available that may be used to conduct CBH checks. These sources include city, county, and state law enforcement agencies, and commercial vendors. Contractors may choose any available source for conducting these checks as long as the check includes a statewide check of the individual's criminal background history.

25.3.3 CBH checks will, as a minimum, cover the individual's places of residency for a 24-month time period prior to contract award. CBH checks are considered favorable if they do not contain any of the following eight disqualifiers:

- (1) US citizenship, immigration status, or Social Security Account Number cannot be verified.
- (2) Barred from entry/access to any military installation or facility.
- (3) Wanted by federal or civil law enforcement authorities, regardless of offense/violation, (i.e., and “order to arrest” has been issued by a judge).
- (4) Conviction of firearms or explosives violation within the past three years.
- (5) Incarcerated for 12 months or longer within the past three years, regardless of offense/violation.
- (6) Any conviction of espionage, sabotage, treason, terrorism, or murder.
- (7) Conviction of sexual assault, armed assault/robbery, rape, child molestation, drug possession with intent to sell, or drug distribution within the past 10 years.
- (8) Name appears on any federal agency’s “watch list” or “hit list” for criminal behavior or terrorist activity.

25.3.3.1 If any of the eight disqualifying factors are identified on a CBH check, the subject of the CBH check in question will be denied access/entry to the installation.

25.3.3.2 **EXCEPTION:** CBH checks are not required for contractors, subcontractors, or their employees if they have a current, favorable government personnel security background investigation that is electronically available and verifiable through the Joint Personnel Adjudication System (JPAS).

25.3.4 Contractors will brief all their employees on requirements for obtaining a CBH check. They shall require them to execute and sign the consent form authorizing DES to conduct CBH or NCIC checks. In addition, they will advise all perspective employees that they are subject to being randomly selected to undergo a DCI/NCIC check and fingerprint check, via FBI databases, a Social Security Administration (SSA) and US Citizenship and Immigration Service (USCIS) check. **NOTE:** Contractors may obtain CBH checks on, their employees and subcontractor employees, or each individual may obtain his/her own CBH check.

25.3.5 Contractors will collect CBH checks on their employees and on their subcontractor(s) employees, and review them for disqualifying factors. If disqualifying factors are found, the prime contractor will inform the employee that he/she not be allowed access/entry to the installation. Additionally, contractors will collect all signed consent forms for DCI/NCIC checks. Contractor shall provide all CBH checks on contract employees and subcontractor employees to the Contracting Officer prior to the commencement of work.

25.3.6 Contractors are responsible for providing written notification (within 5 days) to the Contracting Officer of any changes in personnel who require access/entry to the installation. This includes newly hired personnel and personnel who were discharged, quit, or contractors become aware of disqualifying factors after CBH, NCIC and USCIS checks were completed. **NOTE:** All requirements for the CBH, NCIC and USCIS checks must be completed on new hires prior to allowing them access/entry to the installation.

25.3.7 Contractors are responsible for retrieving government issued credentials and vehicle passes from employees no longer requiring access/entry to the installation (regardless of reason access/entry is no longer allowed) and returning them to the Government. Additionally, they are responsible for retrieving government issued credentials and vehicle passes from all employees and returning them to the badging office upon completion of a particular contract.

C.26. CONTRACTOR VEHICLES AND ACCESS TO GOVERNMENT INSTALLATIONS

26.1 General:

Effective 1 October 2014, all personnel requiring access to the installation shall possess either a Common Access Card (CAC), Military ID or Individual temporary pass issued by the Fort Benning Directorate of Emergency Services (DES) pursuant to Army Directive 2014-05, Policy and Implementation Procedures for Common Access Card Credentialing and Installation Access for Un-cleared Contractors.

Common Access Card (CAC): All contractors requiring access to the installation on a recurring basis for a period of 6 months or more, shall receive a CAC. CACs are issued through the Contractor Verification System (CVS) program. Issuance of a CAC requires a favorable Federal Bureau of Investigation (FBI) fingerprint check, successful submission of a National Agency Check with Inquiries (NACI) (equivalent or higher) background investigation to the Army’s investigative service provider and a favorably adjudicated

NACI (equivalent or higher) investigation from a Federal department or agency will be accepted. **To avoid delays in gaining required access to the installation, all contractors eligible for a CAC are encouraged to contact their Contracting Officer Representative (COR) to begin the process to obtain CACs as soon as possible.**

Long term, unescorted access: Contractors, sub-contractors and vendors requiring physical access to the installation for longer than 24 hours and less than 6 months, but do not require logical access to a DOD computer network, are not eligible for a CAC. These contractors will have a government employee sponsor who will provide the contractual agreement with a cover memorandum signed by either the Contracting Officer or COR affirming the need for long term, unescorted access. The expiration date of the access will be the end of the contract or visit, or the expiration date of the sponsor's credential, whichever comes first. Sub-contractors will be bound by the same requirement.

Military ID: Military ID cards for retirees, reservists and dependents is for non-contractor use. All contractors and sub-contractors possessing a valid Military ID and requiring access to the installation on a recurring basis for a period of 6 months or more shall be required to obtain a CAC.

Individual Temporary Pass: All contractors and sub-contractors who do not possess a CAC or valid Military ID shall report to the Visitors Center located at I-185/Lindsey Parkway to obtain an Individual temporary pass. A temporary pass will **ONLY** be issued to persons who produce a valid current government ID with a picture and are able to pass a NCIC Interstate Identification Index check and local exclusion roster.

Acceptable forms of ID are:

1. Valid current State Driver's license that is for driving AND identification. Drivers Licenses issued by states for driving and not identification will not be accepted.
2. State identification card
3. Passport (Foreign Passports must show point of entry stamp).

During a pre-work conference, the Contractor shall provide the COR a list of all contract and sub-contract employees who require a CAC and/or a temporary pass. The COR will coordinate with the DES for temporary passes not to exceed 6 months for contract employees not possessing a current CAC or military ID. The COR will initiate and coordinate the process for obtaining Contractor CACs. The contractor shall coordinate with the COR for return of CAC at the end of the contract or the end of the individual employee's tenure, whichever comes first. The contractor shall also coordinate with the COR for new or replacement CACs or temporary, long term unescorted passes as required.

Failure to receive a CAC may result in the contractor personnel being denied admission to the installation. Failure to receive a temporary pass will result in the contractor personnel being denied admission to the installation.

For additional information, see:

Homeland Security Presidential Directive 12, Policy for a Common Identification Standard for Federal Employees and Contractors located at <http://www.dhs.gov/homeland-security-presidential-directive-12#1>

Army Regulation (AR) 190-13, the Army Physical Security Program located at <http://www.fas.org/irp/doddir/army/ar190-13.pdf>

Army Directive 2011-08, Army Implementation of Homeland Security Presidential Directive -12 located at http://armypubs.army.mil/epubs/pdf/ad2011_08.pdf

26.1.1 Unless specifically stated elsewhere in the contract or RTOR, the Contractor shall provide all motor vehicles and any other transportation equipment required in the performance of this contract.

26.1.2 The motor vehicles shall meet all of the requirements of this contract and shall be subject to inspection and approval by the KO or their designee. In the rare event a COR/Government Inspector is not appointed, inspection

and approval for vehicles may be conducted by any Government individual as authorized by the KO.

26.1.3 Delivery vehicles, etc., will be granted entry to the installation upon presentation of a valid bill of lading and/or delivery slip. This document must have a delivery point that is on Fort Benning and/or Camp Merrill and an installation point of contact with a phone number. ***During increased Force Protection Conditions this requirement could change and become more stringent. In such cases, it is imperative that you contact the KO for guidance on how to proceed.***

26.1.4 When an employee is operating a company vehicle, the employee must show a copy of the vehicle registration and a notarized letter from the Contractor indicating the employee is the sole driver of the vehicle and is covered by insurance.

26.1.5 If an employee intends to operate a personal vehicle on the government installation, they must register their vehicle at the Visitor Center located at the ACP #1, Benning Blvd. gate entrance. Proof of insurance, a copy of the vehicle registration, and contractor badge will be required to obtain the vehicle pass.

26.1.6 Contractor employees must have a current and valid driver's license when operating a motor vehicle on the installation.

26.1.7 All vehicle passes will be displayed in the windshield of the vehicle it was issued for.

26.2 Vehicle Registration and Installation Access

26.2.1 The contractor shall comply with all applicable requirements of Fort Benning USAIC Regulation No. 190-5, Motor Vehicle Traffic Regulation, in effect during performance of this contract. It is the responsibility of the Contractor to ensure compliance on the part of its employees with this requirement.

26.2.2 Vehicle registration, proof of insurance and a valid driver's license must be presented for all vehicles while operating on the installation. All vehicles entering the installation or sensitive areas are subject to search. Any refusal or non-consent by an employee will result in termination of their installation access and immediate confiscation of this access badge or pass.

26.2.3 During Force Protection Condition (FPCON) Normal and Alpha, personnel without installation issued passes or credentials must be sponsored onto the installation.

26.2.4 During FPCON Bravo, personnel without installation issued identification shall be physically escorted onto the installation.

26.2.5 During Higher FPCONs (Charlie and Delta) the government installation will curtail non-essential operations/functions; access by Non-Essential Contractors will be suspended as the direction of the Installation Commander.

26.2.6 All vehicles are subject to a random inspection and the Government reserves the right to limit access. Be prepared and remain flexible for changes to entering the installation.

C.27. EMERGENCY USE OF GOVERNMENT HOSPITAL FACILITIES

27.1 Medical services for Contractor personnel are the responsibility of the Contractor. However, on an emergency basis, the Government will provide medical services for job-related injuries while an employee is performing under this contract. Such emergency medical care will be limited to those services necessary to prevent undue suffering or loss of life and will be provided only during the period of the emergency. In such circumstances, action shall be taken by the Contractor to transfer employees of the Contractor to a health care provider as soon as the emergency period ends. Medical facilities are located at the Martin Army Community Hospital, Bldg. 9200, Fort Benning, GA. The Contractor shall reimburse the Government for emergency medical services provided upon receipt of invoice from the medical facility.

27.1.1 The Contractor shall also provide the Government hospital facility the name of a physician and/or hospital to

which injured personnel can be transferred for further treatment and care after receiving any initial emergency treatment at the installation hospital. The civilian physician of the contractor's employees shall provide all follow-on care after the initial emergency care.

27.2 Safety: All Local, State and Federal Occupational Safety and Health Administration (OSHA) standards are included into this contract in full force and effect. The most stringent of the standards will apply.

27.2.1 The Contractor shall comply with the safety rules of the Government installation at which the work is being performed.

27.3 Public Convenience and Safety: The Contractor shall conduct his operations to offer the least possible obstruction and inconvenience to the public, vehicular, and the normal day-to-day routine of the Government installation where work is to be performed. Unless safety otherwise prevents such actions, personnel and traffic shall be permitted to pass through the work area with as little delay as possible. Where the nature of construction operations in progress and the equipment and machinery in use are of such character as to endanger passing traffic, the Contractor shall provide such lights and signs, erect such fences or barriers, and station such guards as may be necessary to give adequate warning and to avoid damage or injury to passing traffic. Signs, flags, lights, and other warning and safety devices shall conform to applicable laws, safety regulations and requirements. All lane closures shall be coordinated in advance with the COR/Government Inspector, traffic engineer and the DES. All traffic control procedures shall be in accordance with GA and/or FL Department of Transportation (DOT) regulations.

C.28 TEXTING WHILE DRIVING. Executive Order 13513, Federal Leadership on Reducing Text Messaging while Driving, dated October 1, 2009 bans text messaging while driving or operating a motor vehicle on an active roadway with the motor running, including while temporarily stationary because of traffic, a traffic light, stop sign, or otherwise.

C.29 EMPLOYEE HEALTH AND SAFETY

29.1 In order to provide safety controls for protection to the life and health of employees, and other persons; for prevention of damage to property, materials, supplies, and equipment; and for avoidance of work interruptions in the performance of this contract, the Contractor shall comply with all pertinent provisions of the U.S. Army Corps of Engineers Safety and Health Requirements Manual EM 385-1-1, as amended. The Contractor shall also take or cause to be taken such additional measures as the KO may determine to be reasonably necessary for the purpose.

29.2 Records: The Contractor shall maintain an accurate record of, and shall report to the KO, in the manner and on the forms prescribed by the KO, exposure data and all accidents resulting in death, traumatic injury, occupational disease, and damage to property, materials, supplies and equipment incident to work performed under this contract.

29.3 The KO will notify the Contractor of any noncompliance with the foregoing requirements and the action to be taken. The Contractor shall, after receipt of such notice, immediately take corrective action. Such notice, when delivered to the Contractor or their representative at the site of the work, shall be deemed sufficient for the purpose. If the Contractor fails or refuses to promptly comply, the KO may issue an order suspending all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to any such suspension shall be made the subject of claim for extension of time, or for excess costs or damages by the Contractor.

29.4 Compliance with these requirements by subcontractors will be the responsibility of the contractor.

29.5 Noise Control: Contractor shall comply with all applicable state, local, and installation laws, ordinances, and regulations relative to noise control, to include applicable quiet hours exclusive to each installation.

C.30. ENVIRONMENTAL COMPLIANCE: All work performed under this contract shall comply with the following:

30.1 The Resource Conservation and Recovery Act of 1976 (RCRA), 42 U.S.C. 6962.

30.2 Executive Order 13101 of September 14, 1998, Greening the Government through Waste Prevention, Recycling, and Federal Acquisition.

30.3 Executive Order 13123 of June 3, 1999, Greening the Government through Efficient Energy Management.

30.4 The Energy Policy Act of 2005, Public Law 109-58

30.5 Energy Policy and Conservation Act (42 U.S.C. 6361(a)(1))

30.6 Resource Conservation and Recovery Act of 1976, as amended (42 U.S.C. 6901, *et seq.*).

30.7 National Energy Conservation Policy Act (42 U.S.C. 8253, 8259g, 8262g, and 8287).

30.8 Executive Order 11912, April 13, 1976, Delegations of Authority under the Energy Policy and Conservation Act.

30.9 Executive Order 13221 of July 31, 2001, Energy-Efficient Standby Power Devices.

C.31. ENVIRONMENTAL PROTECTION

31.1 Installation Restoration Program (IRP) Requirements (The following will apply to TOs covering excavations within an IRP site):

31.1.1 Contaminated Soil and Free Product: Areas that will be disturbed have the potential to have free product migrate into and under the construction site. Any material (soil) that is suspected of containing petroleum products shall be reported immediately to the DES. In addition, the Contractor shall notify the KO. If discovered, the Contractor shall mitigate any potential threat to the workers, public, and environment. Record the quantity of any fuel removed. Contaminated soil and/or free product shall not be used for backfill or removed from the military installation without written approval from the KO. Once removal is approved, Contractor will dispose of material under the guidance of the Pollution Prevention Officer of the installation where encountered. All hazardous waste manifests shall be prepared by the contractor and shall be coordinated, approved and signed by the applicable installation Hazardous Waste Manager prior to removal of such waste from the installation.

31.1.2 Additional Excavation: Prior to any excavation beyond the immediate area or boundary of the construction site, the Contractor shall coordinate with and obtain the KO's approval, and submit a digging permit.

31.1.3 All prime and sub-contractors shall be made familiar with the fire reporting and evacuation procedures for the federal installations identified under this contract.

31.1.4 Contaminated Soil Notification: If during construction, contaminated soil is encountered that was not previously known to exist, the Contractor shall cease work in the affected area and immediately contact DES. The Contractor shall then notify the KO and COR/Government Inspector.

31.2 Asbestos Requirements:

31.2.1 THE CONTRACTOR IS WARNED THAT EXPOSURE TO AIRBORNE ASBESTOS HAS BEEN ASSOCIATED WITH FOUR DISEASES: LUNG CANCER, CERTAIN GASTROINTESTINAL CANCERS, PLEURAL OR PERITONEAL MESOTHELIOMA, AND ASBESTOSIS.

31.2.2 Studies indicate there are significantly increased health dangers to persons exposed to asbestos who smoke, and further, to family members and other persons who become indirectly exposed as a result of the exposed worker bringing asbestos-laden work clothing home to be laundered.

31.2.3 The Contractor is advised that friable and/or non-friable asbestos-containing material may be encountered in area(s) where contract work is to be performed. Friable asbestos-containing material means any material that contains more than one percent asbestos by weight that hand pressure can crumble, pulverize, or reduce to powder when dry. Non-friable asbestos-containing materials are materials in which a matrix material, saturate, impregnates, or coating binds asbestos fibers. Non-friable asbestos-containing materials do not normally release airborne asbestos fiber during routine handling and end use. However, excessive fiber concentrations may be produced during controlled

abrading, sanding, drilling, cutting, machining, removal, demolition, or other similar activities.

31.2.4 Care must be taken to avoid releasing, or causing to be released, asbestos fiber into the atmosphere where they may be inhaled or ingested.

31.2.5 The Occupational Safety and Health Administration (OSHA) has set standards at 29 Code of Federal (CFR) 1926.58 for exposure to airborne concentrations of asbestos fibers, methods of compliance, medical surveillance, housekeeping procedures, and measures that must be taken when working with or around asbestos- containing other materials. 29 CFR 1926.58 has been identified as applicable to construction (29 CFR 1926.55 *Gases, vapors, fumes, dusts, and mists*). The Environmental Protection Agency (EPA) has established standards at 40 CFR 61.140-156, *National Emission Standards for Asbestos*, for the control of asbestos emissions to the environment and the handling and disposal of asbestos wastes.

31.2.6 Asbestos containing materials are not permitted by current criteria and shall not be used in minor new construction or modification projects (STL 1110-1-118, 27 May 1983). The Contractor shall review plans and specifications for all minor new construction and modification projects to insure that asbestos- containing materials are not used. Any asbestos material installed by the Contractor shall be removed and disposed of by the Contractor at the Contractor's expense and shall not be subject to a claim against the Government.

31.2.7 Maintenance, modification, or demolition activities where exposure to asbestos dust may occur from previously installed friable or non-friable asbestos-containing material shall be identified and the asbestos-containing materials shall be abated and disposed of in accordance with (IAW) law. All precautions, to include proper work practices, medical surveillance, respiratory protection, industrial hygiene and environmental protection requirements of OSHA (29 CFR 1926.58), EPA (40 CFR 61.140- 156), shall be strictly adhered to.

31.2.8 Contractors are reminded that they are subject to OSHA, EPA and local compliance and inspection for asbestos removal. Contractor must perform asbestos removal work in accordance with installation specifications, Corps of Engineers specifications and EPA National Emission Standards for Hazardous Air Pollutants (NESHAPs) for asbestos and any subsequent updates thereof. This includes state and EPA Region 4 notification, which shall be accomplished at least 20 days prior to starting any asbestos abatement or removal.

31.2.9 Asbestos Notification: If during construction, asbestos is encountered that was not previously known to exist, the Contractor shall cease work in the affected area and notify the KO and COR/Government Inspector.

C.32 LEAD BASED PAINT, CONTAMINATED SOIL, AND ASBESTOS REQUIREMENTS.

Contractor shall check for lead-based paint/contaminated soil/asbestos and, where required, develop project documents for abatement and/or encapsulation. The Contractor shall take an adequate number of samples and test to confirm presence. Where presence of existing will have an impact on project accomplishment, identify location and quantity of such on drawings. The Contractor shall develop specifications and drawings that indicate method of either abatement or encapsulation and ensure specifications incorporate the most recent requirements and changes of subpart D of 29 CFR part 1926, 29 CFR 1926.58, 40 CFR 61.140-156, and any other applicable law or code.

C.33 FUEL SPILLS. In the event of a fuel spillage during the performance of this contract, the Contractor shall be responsible for its containment, clean up, and related disposal costs. The operator shall have sufficient spill supplies readily available on the pumping vehicle and/or at the site to contain any spillage. In the event of a contractor-related release, the Contractor shall immediately notify the Fire Department at (706) 545-2222 (Fort Benning) or (706) 864-3364 x612 (Camp Merrill), or calling 911 at all other federal installations identified under this contract. Immediately following notification to the Fire Department, the Contractor shall contact the COR/Government Inspector, and take appropriate actions to correct its cause and prevent future occurrences. If Federal, state, or local authorities assess any monetary fine, penalty, or assessment related to the release of any substance by the contractor, their employees, or agents during the performance of this contract, the Contractor shall be solely liable for its payment. The Contractor will authorize the US Government to withhold such from payment and otherwise indemnify and hold the US Government harmless.

C.34 VOLATILE ORGANIC COMPOUNDS. All coatings and solvents used in the performance of this contract shall meet the required performance specifications and shall not exceed the volatile organic compound limits of the

Air Pollution Control Districts where they aroused.

C.35 ABOVE-GROUND STORAGE TANKS. Any Above-ground Storage Tanks (ASTs) allowed on site shall have secondary containment, venting and spill/overflow protection. Anti-siphon valves are required. The Contractor shall visually inspect such tanks daily for leaks. All ASTs shall be installed or erected in accordance with National Environmental Protection Agency (NFPA) 30 and 40 CFR 112.7, *General Requirements for Spill Prevention, Control, and Countermeasure Plans*.

C.36 EROSION AND SEDIMENT CONTROL

36.1 All construction operations shall comply with the requirements of the Georgia Erosion and Sediment Control Act. Hay bales shall not be used for erosion control and inlet protection from storm water run-off. The Contractor shall submit alternate method of protection to the KO at the pre-construction conference for review and approval. The KO will notify the Contractor of their decision prior to issuance of Notice to Proceed (NTP).

36.2 In case of a conflict or discrepancy between environmental regulations or laws and the contract specifications, the Contractor shall immediately submit the matter in writing to the KO for a determination. Without such determination any actions taken shall be at the Contractor's own risk and expense.

C.37. PRECAUTIONS AGAINST HAZARDS

37.1 In addition to the requirements of the Employee Health and Safety (Section C.28.), the Contractor shall comply with the following when engaged in hazardous operations performed under this contract.

37.2 Definition of Hazardous Materials

37.2.1 Refer to hazardous and toxic materials/substances included in Subparts H and Z of 29 CFR 1910, *Occupational Safety and Health Standards, (Hazardous Materials (Subpart H) and (* and to others as additionally defined in Fed. Std. 313. Those most commonly encountered include asbestos, lead paint, polychlorinated biphenyls (PCBs), explosives and radioactive material, but may include others.

The most likely products to contain asbestos are sprayed-on fireproofing, insulation, boiler lagging, and pipe covering.

37.3 Standards and Applicable Publications

37.3.1 The publications listed below form a part of this requirement to the extent referenced. The publications are referred to in the text by basic designation only.

37.3.1.1 Code of Federal Regulations (CFR): OSHA General Industry Safety and Health Standards (29 CFR 1910, OSHA Construction Industry Standards (29 CFR 1926). One source of these regulations is OSHA Publication 2207, which includes a combination of both Parts 1910 and 1926 as they relate to construction safety and health. They are for sale by the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402.

37.3.1.2 National Emission Standards for Hazardous Air Pollutants (40 CFR, Part61).

37.3.1.3 Material Safety Data Sheets, Preparation and the Submission to the Bioenvironmental office on each installation. Safety and Health Requirements Manual, EM 385-1-1.

37.3.1.4 Use of Asbestos Containing Material or any Class 1 ozone depleting chemical compounds are prohibited, Department of Army (DA) Circular 40-83-4.

37.3.1.5 All welding and cutting operations shall be done in accordance with nationally recognized good practice. The current publications of the American Welding Society, 2501 NW 7th Street, Miami FL 33125, and the National Fire Protection Association, 470 Atlantic Ave, Boston MA 02110, shall be used as a minimum standard of nationally recognized safety procedures in welding and cutting.

37.4 The Contractor shall provide the necessary methods of fire extinguishment and fire prevention. Before operations begin, the Contractor shall clear all welding and cutting operations with the COR/Government Inspector before preparing for such operations.

37.4.1 The Contractor shall discontinue all burning, welding, or cutting operations 30 minutes prior to the end of the workday. The Contractor shall provide a workman to remain at the site for thirty minutes after discontinuing the above operations. This workman shall make a thorough inspection of the area for possible sources of latent combustion. Any unsafe conditions shall be reported to the Fire Department for their investigation – EMERGENCY PHONE NO 911 from a land line or (706) 545-2222 (Fort Benning) / (706) 864-3364 x612 (Camp Merrill) by cell phone.

37.4.2 The use of open-flame heating devices will not be allowed except by special permission of the Fire Department. Such permission will not be granted unless the contractor has taken all venting precautions. Burning trash, brush or trees on the job site will not be allowed unless Fire Department grants specific approval for each incident. Approval for the use of open fires and open-flame heating devices will in no way relieve the contractor from the responsibility of any damage resulting from such fires.

37.5 Flammable liquids shall be stored and handled in accordance with the Flammable Liquids Code of the National Fire Protection Association (No 30). Flammable liquids shall not be stored in the Contractor's storage trailers.

37.6 The Fire Department, Directorate of Emergency Services (DES) office, (706) 545-9235 (Fort Benning) / (706) 864-3364 x612 (Camp Merrill), are available for assistance concerning fire hazard questions.

C.38 SMOKING IN GOVERNMENT FACILITIES. The Army has banned use of all tobacco products in all government facilities. Contractor employees and visitors are subject to the same restrictions as are Government personnel. Smoking is permitted only in designated smoking areas.

C.39 OCCUPANCY. Areas in which work is required may be occupied or have public or Government presence during the performance of work under any TO. Other maintenance and/or repair construction may also be concurrently being performed at the site by other contractors. The Contractor shall cooperate with the Government to minimize conflict, and to facilitate the Government's operations by scheduling the Work to accommodate Government occupancy. Additional compensation due to the conditions brought about by this occupancy and usage by the Government will not be granted to the Contractor. Should conflicts occur with other concurrent work, the Contractor shall immediately notify the KO.

C.40 TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER

40.1 This provision specifies the procedure for the determination of time extensions for unusually severe weather. The listing below defines the adverse weather days that are anticipated monthly. The listing is based upon data from the National Oceanographic & Atmospheric Administration (NOAA) or similar data.

40.2 Monthly Anticipated Adverse Weather Calendar Days:

JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
11	9	10	8	9	9	13	10	8	6	8	9

40.2.1 The above schedule of anticipated adverse weather will constitute the baseline for monthly (or portion thereof) weather time evaluations. Upon acknowledgment of the NTP and continuing throughout the contract on a monthly basis, actual adverse weather days will be recorded on a calendar-day basis (include weekends and holidays) and compared to the monthly anticipated adverse weather in the schedule above.

40.2.2 The number of actual adverse weather days shall be calculated chronologically from the first to the last day in each month. Once the number of actual adverse weather days anticipated in the schedule above have occurred, the KO, upon the Contractor's written request, will examine any subsequently occurring adverse weather days to determine whether the Contractor is entitled to a time extension. Before adverse weather entitlement is granted, the Contractor must demonstrate that fifty percent or more of their workdays were affected by the subsequent adverse

weather. The adverse weather must also delay work critical to the timely completion of the project. The KO will convert any delays meeting the above requirements to calendar days and issue a modification.

40.3 For all weather dependent activities, the Contractor's schedule must reflect the anticipated adverse weather delays that are noted above.

40.4 The following is considered as adverse weather: Weather of a nature that workers cannot perform work as scheduled or get to work site (e.g., hurricane, tornado, high winds, floods, extremely cold weather, ice storm, sleet, heavy snow storm, etc).

C.41 SEASONAL HVAC REQUIREMENTS. The Contractor shall provide temporary heating or cooling to existing occupied facilities if the air conditioning system or heating system is shut down to perform any work. Any proposals to shut down heating or cooling without providing temporary service must be approved through the KO at least two (2) workdays prior to interruption of service. The Contractor shall submit shop drawings for approval of proposed method for providing temporary heating or cooling.

C.42 INSPECTIONS, TESTS AND REPORTS

42.1. Any required inspections, tests, and reports made by the Contractor, subcontractors, specifically trained technicians, equipment manufacturers, and others as required by a TO shall be furnished upon request to the Government in accordance with the terms of the TO.

The Contractor shall request on-site inspection review from the COR/Government Inspector before the backfill of any trenches, pouring of concrete and/or utility tie-ins. The Contractor agrees that authorized Government Representatives of the KO shall have access to and the right to examine the sites or areas where work under this contract is being performed to determine the adequacy of the Contractor's performance.

C.43. TEMPORARY SANITARY FACILITIES (WORK RELATED)

43.1 The Contractor shall provide adequate sanitary conveniences of a type approved for the use of persons employed on the work, properly secluded from public observation. Sanitary facilities, such as chemical toilet, shall be located far enough from a well, live stream, or pond to prevent pollution of the water. The Contractor shall maintain these conveniences at all times without nuisance or as required or approved by the KO. Upon completion of the work, the Contractor shall remove the conveniences from the premises, leaving the premises clean and free from nuisance.

43.2 In most cases, the Contractor's personnel will *not* be permitted to use any existing U.S. Government sanitary facilities.

C.44 SEWAGE, ODOR, AND PEST CONTROL. The Contractor shall dispose of sewage through connection to a municipal, district, or station sanitary sewage system. Where such systems are not available, the Contractor shall use chemical toilets or comparably effective units, and periodically empty wastes into a municipal, district, or station sanitary sewage system, or remove waste to a commercial facility. The Contractor shall include provisions for pest control and elimination of odors.

C.45 DISPOSAL OF REMOVED MATERIAL. The Contractor shall not use Government waste disposal facilities including garbage cans, trash piles or dumpsters. The Contractor shall at the end of each working day, remove from the site all debris resulting from the performance of work. Contractor's dumpsters shall be emptied before becoming full as to spill onto the surrounding area. The area around the dumpster shall be kept free of debris.

C.46 WASTE DISPOSAL

46.1 All waste materials generated by work under this contract and performed on a Government installation, shall be handled, transported, stored, and disposed of by the Contractor (or subcontractor) and shall be in accordance with the specifications, or applicable Federal, state, or local laws, ordinances, regulations, court orders, or other types of rules or rulings having the same effect of law. These include but are not limited to Executive Order 120S, 13 October 1978; the Federal Water Pollution Control Act, as amended (33 USC Sec 1251 ET SEQ); The Clean Air

Act, as amended (42 USC Sec 1857 ET SEQ); The Endangered Species Act, as amended (16 USC Sec 1531, ET SEQ); The Toxic Substances Control Act, as amended (15 USC Sec 2601, ET SEQ); The Solid Waste Disposal Act, as amended (42 USC 6901 ET SEQ); and the Archaeological and Historic Preservation Act, as amended (16 USC Sec 469, ET SEQ).

46.2 Loose debris on trucks leaving the site shall be loaded in a manner that shall prevent dropping of materials on streets and conform to local ordinances/laws. The Contractor shall fasten suitable cover, such as a tarpaulin, over the load before entering surrounding streets.

46.2.1 The Contractor shall submit, upon request, all trip tickets from the landfill facility to show all debris is being land filled in accordance with all Federal requirements and in an approved location.

46.3 Contractors are reminded that the construction site must be operated and maintained according to good construction practice standards and subject to inspection and enforcement according to all federal, state and local codes/regulations.

C.47 RECYCLING. Recycling requirements will be addressed on each individual Task Order as appropriate to the project.

C.48 SALVAGE

48.1 The title to all materials and equipment to be demolished shall be vested to the Contractor upon removal from the military installation. The Government will not be responsible for the condition, loss or damage to such property after issuance of NTP. All unsalvageable material will be disposed of legally off the installation.

48.2 Salvaged materials shall be cleaned, sorted, identified, bundled, boxed, etc. and delivered to the collection location identified in individual TO.

C.49 GRASSY AREAS. Grass and weed growth in excavated materials that are stockpiled on site shall be controlled and/or cut weekly. Weeds and grass within the construction site shall also be controlled and/or cut weekly. Areas disturbed by construction and/or those areas required by the plans to be “re- seeded” shall be re-established by hydro seeding or sod.

C.50 RESIDUAL ASPHALT. During the laying of asphalt roads, streets and/or parking surfaces, areas soiled by residual asphalt shall be cleaned on a daily basis.

C.51 ACCESS ROUTES. Access routes to project sites shall be limited to only those as indicated in the RTOR documents or as discussed at the project pre-construction conference.

C.52 OADS

52.1 The Contractor is solely responsible for spillage from their vehicles, and such spillage shall be cleaned up immediately. On a daily basis for the duration of the TO, the Contractor shall remove from all roads and/or streets any asphalt, mud, soil, rocks, trash, and debris that result from their construction operation on the government installation. All roads and/or streets affected shall be cleaned before close of business on the particular day affected. In the case of asphalt, roads will be cleaned and/or treated with lime immediately upon detection.

52.2 ROADS, UTILITY CUTS: The Contractor must bore and jack under roads and streets for all utilities, do not cut across the road and surface patch.

C.53. AIRFIELD REQUIREMENTS

53.1 When applicable, the Contractor shall contact the COR/Government Inspector for construction restrictions involving the flight line, taxiway and runway areas and shall comply with all regulations. Specific airfield requirements will be provided at the individual RTOP level.

53.2 Two-way radio contact on VHF Radio, capable of providing clear communications with the Air Traffic Control

Tower is required at all times for all personnel and groups of personnel working on the flight line, taxiways and runways.

C.54. RECORDING AND PRESERVING HISTORICAL & ARCHEOLOGICAL FINDS

54.1 Artifacts Discovered During Construction: Any historical or archaeological finds (arrowheads, potshards, etc.) encountered during Contractor operations requires cessation of all activity in the affected area. The Contractor shall promptly notify the KO and the environmental office of the installation where such find was discovered. The Government will determine the significance of the findings, if necessary, after consultation with the Georgia State Historic Preservation Officer, prior to authorizing the Contractor to resume operations in that area.

54.2 Some MATOC projects may affect a resource that is eligible for listing on the National Historic Register and qualifies as an “undertaking” as defined by the National Historic Preservation Act, Section 301(7). As such, all design, repair, maintenance, and construction must be completed in a manner that is consistent with the Secretary of the Interior’s “Standards for Historic Preservation Projects” and the Secretary’s ‘Illustrated Guidelines for Rehabilitating Historic Buildings.’”

54.3 Prior to the final design submittal, the contractor shall obtain written verification from the installation’s Cultural Resource Manager that consultation with applicable state and federal authorities has been completed. Also, all comments necessitating a change in the project design have been considered, incorporated, and reviewed by the Cultural Resource Manager.

54.4 The Secretary of the Interior’s Standards for Rehabilitation: The Standards that follow were originally published in 1977 and revised in 1990 as part of Department of the Interior regulations (36 CFR Part 67, *Historic Preservation Certifications*). They pertain to historic buildings of all materials, construction types, sizes and occupancy and encompass the exterior and the interior of historic buildings. The Standards also encompass related landscape features and the building’s site and environment as well as attached, adjacent or related new construction.

54.5 The Standards are to be applied to specific rehabilitation projects in a reasonable manner, taking into consideration economic and technical feasibility.

54.6 A property shall be used for its historic purpose or be placed in a new use that requires minimal change to the defining characteristics of the building and its site and environment.

54.7 The historic character of a property shall be retained and preserved. The removal of historic materials or alteration of features and spaces that characterize a property shall be avoided.

54.8 Each property shall be recognized as a physical record of its time, place and use. Changes that create a false sense of historical development, such as adding conjectural features or architectural elements from other buildings, shall not be undertaken.

54.9 Most properties change over time. Those changes that all have acquired historic significance in their own right shall be retained and preserved.

54.10 Distinctive features, finishes, and construction techniques or examples or craftsmanship that characterizes a property shall be preserved.

54.11 Deteriorated historic features shall be repaired rather than replaced whenever possible. Where the severity of deterioration requires replacement of a distinctive feature, the new feature shall match the old in design, color, texture, and other visual qualities and, where possible, materials. Replacement of missing features shall be substantiated by documentary, physical, or pictorial evidence.

54.12 New additions, exterior alterations, or related minor new construction shall not destroy historic materials that characterize the property. The new work shall be differentiated from the old and shall be compatible with the massing, size, scale and architectural features to protect the historic integrity of the property and its environment.

54.13 New additions and adjacent or related minor new construction shall be undertaken in such a manner that if

removed in the future, the essential form and integrity of the historic property and its environment would be unimpaired.

C.55 PUBLIC RELEASE OF INFORMATION. The Contractor and subcontractor personnel shall not publicly release information, photographs, or other documents concerning any aspect of the materials or services relating to this contract or TOs without the prior written approval of the KO.

C.56 DAVIS-BACON WAGE RATES

56.1 Applicable Davis-Bacon Wage rates in effect at the time of issuance of a RTOR will be incorporated into the TO. The wage determinations apply to those laborers and mechanics employed by a contractor or sub-contractor at the site of the work, including drivers who transport to or from the site materials and equipment used in the course of contract operations.

56.2 If highly specialized crafts or trades are required in the performance of a TO project for which no wage is listed in the Department of Labor Wage Decision provided, the KO shall be notified in writing.

C.57. CONTRACTOR PERFORMANCE

57.1 The Contractor Performance Assessment Reporting System (CPARS) is a web-enabled application that collects and manages the library of automated contractor performance reports. CPARS is for UNCLASSIFIED use only.

57.2 The Construction Contractor Appraisal Support System (CCASS), which is located within the CPAR system, is used to document contractor performance on construction contracts. The CCASS evaluation assesses a contractor's performance and provides a record, both positive and negative, on a given contract. Each evaluation is based on objective facts and supported by contract management data, such as contract performance elements that evaluate quality, timely performance, effectiveness of management, and compliance with contract terms, labor standards, and safety requirements.

57.2.1 Contractors performance will be evaluated upon completion of each individual TO valued over \$550,000.00 or at any valued amount if terminated for Cause or Default. The Government reserves the right to complete performance evaluations for individual TOs valued at less than \$550,000.00. Interim evaluations may be prepared at any time during the TO period of performance when determined to be in the best interest of the Government. All performance evaluations, to include those derived from other sources, will be reviewed when considering exercising of option periods.

57.3 As may be required, the Federal Awardee Performance & Integrity Information System (FAPIS) application will be used to collect contractor and grantee performance information on Terminations, for Cause or Default.

57.4 Completed performance reports are made available in the Past Performance Information Retrieval System (PPIRS).

C.58. SPECIFIC REQUIREMENTS FOR DESIGN-BUILD TASK ORDERS

58.1 Concept Documents

58.1.1 At a minimum, the Government will provide a 35% design concept for each Design-Build requirement. Design concept will define the project and state the Government's requirements. The scope of work may include criteria and preliminary design, budget parameters, and schedule or delivery requirements. May need a requirement for registration of designers. Architects or engineers registered to practice in the particular professional field involved in a State or shall prepare or review and approve the design of architectural, structural, mechanical, electrical, civil or other engineering features of the work. Not stamped drawing by A&Es.

The Contractor shall identify a Designer of Record ("DOR") for each area of design. All design disciplines shall be accounted for by listed, registered Designer(s) of Record. Each DOR shall be responsible for ensuring integrity of their design and design integration in all construction submittals and extensions to design developed by others, such as the constructor, subcontractors or suppliers. The DOR shall review and

approve all construction submittals and extensions to design, in accordance with the procedures, described in Section 01330 SUBMITTALS. Each DOR shall be responsible for the responses to “Requests for Information” (“RFI’s”), applicable to their area of design responsibility. Each DOR shall sign, and date all design drawings under their responsible discipline at each design submittal stage and all submittals under their responsible discipline, in accordance with the submittal review procedures. The DOR shall sign-off on all applicable RFI responses. The drawings and other data become property of the Government.

58.1.2 Design Concept documents will consist, if applicable to project, of the following:

58.1.2.1 Project Description: Narrative description of the project.

58.1.2.2 User Information and Requirements: Narrative describing the functions of personnel, equipment and facility.

58.1.2.3 Area Development Plan: This will include site location, how it is to be developed, and what special considerations need to be given to the treatment of the site.

58.1.2.4 Infrastructure Requirements: List and/or narrative describing known base systems and subsystems necessary to and/or providing support to the facility.

58.1.2.4.1 Civil/Structural

58.1.2.4.2 Mechanical

58.1.2.4.3 Plumbing

58.1.2.4.4 Electrical

58.1.2.4.5 Fire Protection

58.1.2.4.6 Safety

58.1.2.4.7 Communications

58.1.2.5 Environmental Concerns: Environmental problems affecting the construction or creating any type of hazard should be described in this section.

58.1.2.6 Design Guidelines: The parameters for the design effort with detailed requirements spelled out under the below subheadings.

58.1.2.6.1 General Design Considerations

58.1.2.6.2. General Construction Considerations

58.1.2.6.3. Special Construction Considerations

58.1.2.7 Appendices: Whatever else is needed to provide a more descriptive picture of the project requirements.

58.1.2.7.1 Maps/Plans

58.1.2.7.2 Sketches

58.1.2.7.3 Photos

58.1.2.7.4 Literature

58.1.2.7.5Plans

58.1.2.7.6 Command Policy – such as carpet, furnishings, etc.

58.1.2.7.7. Maintainability

58.1.2.7.8. Glossary

58.1.3 MATOC Contractors shall receive one copy of all applicable concept documents with each RTOR issued. The Government does not guarantee the accuracy or adequacy of any design concept document, to include existing record drawings, provided.

58.1.4 The Contactor shall check all concept documents furnished by the Government and promptly notify the KO, in writing, of any discrepancies. Written notifications must be submitted in a RFI format.

58.1.5 Upon award of the Design-Build TO, it shall be the Contractor's responsibility to verify information provided as well as field-verify all as-built drawings.

58.2 Design Drawings

58.2.1 The RTOR will indicate the specific sizes and amounts required during the design submittal process. Upon award of the Design-Build TO, the successful contractor shall develop all drawings, past the government provided drawings (minimum of 35%) and prepared in format utilizing Standard D (24" x 36"), Standard B (11" x 17"), or as indicated in the RTOR. All TO design submittal drawings shall be in the same electronic format and drawn to Standard English scale as appropriate for the size of drawing. Drawings shall be delivered in both .PDF and .DWG format. Government provided cover sheet template and title blocks shall be used.

58.2.2 Each sheet shall be on Computer-Aided Design (Auto CAD 2002 or newer and/or Microstation V8) format and have an approved title block and border. All final design drawings shall have required signature and certification of licensed Project Engineer or registered architect as requested. The title block shall contain project information including but not limited to the Government project number, TO number, project name, and date. Required level (i.e., 65%, 95%, and 100%) of design will be indicated in the RTOR. Each design phase must receive Government approval prior to the start of next design phase, and prior to construction. The Contractor shall prepare the following, as applicable, drawings and specifications, based on the Government's design concept and SOW.

58.2.2.1 Cover sheet with Title and Approval block

58.2.2.2 Existing Site Plan

58.2.2.3 Final Site Plan

58.2.2.4 Grading Plan

58.2.2.5 Underground Utility Plan and Profiles

58.2.2.6 Demolition Drawings (As Required)

58.2.2.7 Floor Plans

58.2.2.8 Exterior Elevations

58.2.2.9 Finish Schedule

58.2.2.10 Wall and Roof Sections

58.2.2.11 Window and Door Schedules and Elevations

58.2.2.12 Ceiling Plan

58.2.2.13 Roof Plan

58.2.2.14 Interior Elevations

58.2.2.15 Window and Door Details

58.2.2.16 Millwork and Cabinet Details

58.2.2.17 Mechanical Plan

58.2.2.18 Plumbing and HVAC Riser Diagrams

58.2.2.19 Electrical Site Plan

58.2.2.20 Power Plan and Panel Schedule

58.2.2.21 Electrical Plan and Lighting Plan with Schedule

58.2.2.22 Fire Protection Plan (Life Safety)

58.2.2.23 Telephone Plan

58.2.2.24 Fire Suppression Detection (Riser diagram IAW NFPA 13, 72, and 70E)

58.2.2.25 Landscaping Plan

58.2.2.26 Provide Reflective Ceiling Plan Drawings for Fire Suppression Systems and all ceiling mounted devices. Also, renovations and new facilities shall have heavy-duty key-access lock boxes installed where deemed applicable.

58.2.3 Additionally, approved 100%/Final CAD drawings shall be submitted on 24" x 36" Mylar (minimum 4 mil thick) sheets, as well as CAD Compact Discs (CDs). The plot area of each sheet shall be 22" x 34".

58.2.3.1 The Government reserves the right to request mylars be only submitted at the Final completion of a project and that only a paper copy be submitted at 100% design (for commencement of construction). Such deviation will be indicated in the RTOR and will require the TO Contractor to incorporate all as-built information prior to submitting Final mylar to Government.

58.2.4 Template cover sheet shall be modified as required for each project. At a minimum, the cover sheet shall indicate drawing/project number, access route, job location, lay-down areas, abbreviation list, job title, index to drawings, etc. The drawing number will also be provided upon request.

58.2.5 All CAD drawing files shall meet the National CAD Standard (NCS) for layering, line type, color schemes, etc. All abbreviations and drawing symbols used throughout the drawings shall be listed on drawings and defined per each discipline.

58.2.6 Where areas of work are not clearly dimensioned, an approximate quantity shall be listed on the drawings identifying the work effort.

58.2.7 As built drawings: Stamped drawings are required at final completion of the entire Design-Build project and shall be provided prior to final acceptance. All as-built information shall be included in all final documents. See deviation at Section 58.2.3.1.

58.3 Rendered Perspective (when required)

58.3.1 When a rendered (color) perspective is required, the perspective shall clearly reflect the Architect-Engineer's (A-E) intent to make the new building compatible to existing buildings in the vicinity of the site. The perspective shall be approximately 24" x 36" in size and shall be mounted on a standard presentation board (form core board), complete with a small site plan and supporting data (i.e., size, cost of landscaping, site work, building, etc.) affixed to the presentation board, or as indicated in the RTOR.

58.3.2 A black-line concept perspective shall be provided with the first submittal. The rendered perspective shall be delivered with the 95% submittal, or as indicated in the RTOR. Quantities shall be indicated in the RTOR.

58.4 Specifications

58.4.1 Designer shall be ultimately responsible for incorporating and tailoring specifications required to complete the Final design. Specifications shall be developed by utilizing the Unified Facilities Guide Specifications (UFGS), MasterFormat 2010, and its associated software, SpecsIntact.

58.4.2 Quantities shall be indicated in the RTOR. All approved 100%/Final specifications shall be submitted on Compact Discs.

58.4.3 Designer shall complete design in accordance with the most current version of the following references and other references that may be indicated elsewhere in this Statement of Work and/or RTOR:

American Association of State Highway and Transportation Officials (AASHTO), Guidelines for the design of roadways, pavements and roadside safety
Air-conditioning and Refrigeration Institute (ARI) American Concrete Institute (ACI)
American Hardboard Association (AHA)
American National Standards Institute (ANSI) Standards
American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE) Standards American Society of Mechanical Engineers International (ASME)
American Society of Testing and Materials (ASTM) Standards American Water Works Association (AWWA)
American Welding Society (AWS)
Americans with Disabilities Act (ADA) Title III to provide Public Accommodations in accordance with the Act and ADA Compliance Guide
ANSI C-2, National Electrical Safety Code (QIESC) ANSI/ASCE 7-95
Architectural Barriers Act
ASHRAE 62-1989 Ventilation for Acceptable Indoor Air Quality Performance Standards for New Federal Buildings 10 CFR 435 (Appendix 13)
ASHRAE 90A-1980 Energy Conservation in New Building Design ASHRAE Handbook of Fundamentals
Clean Air Act Clean Water Act
Concrete Reinforcing Steel Institute (CRSI)
Consumer Product Safety Commission 16 CFR 1201 Safety Standards for Architectural Glazing Materials
Forest Stewardship Council (FSC) Fort Benning Design Guide
GDOT State Highway Specifications for streets, pavements, and roadway structures International Building Code (IBC)
International Code Council (ICC)
International Energy Conservation Code with Georgia State Supplements and Amendments International Fire Code (IFC)
International Fuel Gas Code with Georgia State Amendments International Mechanical Code (IMC)
International Plumbing Code (IPC)
Life Safety Code, NFPA 101 MIL Handbook 1190
National Electrical Code (NEC)
National Electrical Manufacturers Association (NEMA) National Fire Protection Association (NFPA) Codes
National Fire Protection Association (NFPA) 101 Life Safety Code National Institute of Standards and Technology
National Sanitation Foundation International NSF)
Occupational, Health, and Safety Act (OSHA) Underwriters Laboratories (UL)
Sheet Metal and Air Conditioning Contractors National Association, Inc (SMACNA) Standards Society for Protective Coatings (SSPC)

State Site Erosion and Sediment Control Regulations
 Unified Facilities Criteria 3-600-01, Latest Edition Fire Protection Engineering for Facilities Unified Facilities
 Criteria 4-010-01 DoD Minimum Antiterrorism Standards for Buildings Unified Facilities Criteria 4-010-02 DoD
 Minimum Antiterrorism Distances for Buildings Unified Facilities Criteria 4-021-01, Latest Edition Mass
 Notification System
 Uniform Federal Accessibility Standards (UFAS)
 U.S. Department of Commerce (DOC)
 U.S. Environmental Protection Agency (EPA)
 U.S. General Services Administration (GSA)
 U.S. Green Building Council (USGBC)
 Applicable manufacturer or industry specifications associated with material, supplies, or systems.

58.4.3.1 Contractor shall notify the KO if any discrepancy exists between these documents. The most stringent requirement shall be utilized in preparing design projects.

58.4.4 The bottom of each page shall have the following relative information indicated in the format noted:

Project Number	Section Number	Page Number of the Section
----------------	----------------	----------------------------

58.4.5 When the last page of a section is encountered, the following shall be noted (centered) after the last paragraph:

XXX END OF SECTION XXX

58.5 Design analysis

58.5.1 As specified in the RTOR, design calculations may be required, to include code references, as applicable for each discipline, to show compliance. These calculations shall be provided by the contractor and included with the appropriate design submittal. The following is a list of calculations which might typically be required under this contract.

58.5.1.1 Civil/Site work

58.5.1.1.1 Sizing and grades for sanitary & storm sewers

58.5.1.1.2. Sizing for water mains & services

58.5.1.1.3. Sizing for gas mains & services

58.5.1.2 Structural

58.5.1.2.1 Foundation sizes and reinforcing

58.5.1.2.2. Superstructure framing

58.5.1.2.3. Wind & snow loading analysis

58.5.1.2.4. LL & DL calculations

58.5.1.2.5. Wall sizes and reinforcing

58.5.1.2.6. Equipment supports

58.5.1.2.7 Elevated platforms

58.5.1.2.8 Floor member sizing /reinforcing

- 58.5.1.2.9. Lintel sizing
- 58.5.1.2.10. Sizing for roof joists & decking
- 58.5.1.3 Architectural
 - 58.5.1.3.1 Building type, area and height limitation, occupancy
 - 58.5.1.3.2. Emergency egress calculations
 - 58.5.1.3.3 Fire-rated wall requirements
 - 58.5.1.3.4 Minimum plumbing fixture calculations
- 58.5.1.4 Mechanical
 - 58.5.1.4.1 Cooling and heating load analysis
 - 58.5.1.4.2. Pump sizing and pump curves
 - 58.5.1.4.3. Pipe sizing
 - 58.5.1.4.4. Duct size
 - 58.5.1.4.5. Static pressure loss
 - 58.5.1.4.6. Control valve sizing
 - 58.5.1.4.7. Psychometric chart analysis
 - 58.5.1.4.8. Fan sizing and fan curves
 - 58.5.1.4.9. Heat exchanger selection
 - 58.5.1.4.10. Catalog cuts of selected equipment
 - 58.5.1.4.11. Water demand and sewer flow
 - 58.5.1.4.12. Gutter and downspout calculations
- 58.5.1.5 Electrical
 - 58.5.1.5.1. Load calculations
 - 58.5.1.5.2. Short circuit calculations
 - 58.5.1.5.3. Lighting level calculations
 - 58.5.1.5.4. Branch circuit calculations
 - 58.5.1.5.5. Motor feed requirements
 - 58.5.1.5.6. Panel sizing
- 58.5.1.6 Fire Protection
 - 58.5.1.6.1 Sprinkler layout and pipe sizing

58.5.1.7 Others as applicable to a specific project and identified in the RTOR.

58.6 Design-Build Schedule

58.6.1 The Contractor shall submit a Design-Build Schedule which encompasses the entire Design-Build process, to include excusable weather day(s) (for construction) as indicated in Section C.39. Amount of working days required to perform Government Design Reviews, Design Submittal Phases, and Design Review Meetings will be provided by the Government and indicated in the Schedule of Design-Build at the RTOR level. Contractors schedule shall be compiled based on calendar days.

C.59. SPECIFIC REQUIREMENTS FOR CONSTRUCTION TASK ORDERS

59.1 Documents

59.1.1 The Government will provide specifications, drawings, and other project related documents. However, construction projects may or may not require incidental professional design services (i.e., shop drawings).

59.2 Specifications

59.2.1 The Contactor shall check all specifications furnished and promptly notify the KO, in writing, of any discrepancies. Written notifications must be submitted in a Request for Information (RFI) format.

59.3 Drawings

59.3.1 The Government will provide drawings depicting project requirements. Drawings may contain details and notes that may not be covered in the specifications.

59.3.2 The Contactor shall check all drawings furnished and promptly notify the KO, in writing, of any discrepancies. Written notifications must be submitted in a RFI format.

59.3.3 Omissions from the drawings or specifications or the wrong description of details of work that are manifestly necessary to carry out the intent of the drawings and specifications, or that are customarily performed, shall not relieve the Contractor from performing such omitted or incorrectly described details of the work. The Contractor shall perform such details as if fully and correctly set forth and described in the drawings and specifications.