

Statement of Work

A. Project Title

Stryker Neptune OR Waste Management Support and Service Contract

B. Procurement Type

Sole Source

C. Background

VA Midwest Healthcare Network (VISN 23) requires a support and service agreement contract for existing Stryker Neptune Rover and Docking System operating room (OR) waste management equipment in the Surgery department at VISN 23 facilities. The equipment is a constantly closed waste management system that collects, transports and disposes of surgical waste fluid helping protect staff from exposure while increasing efficiencies in the operating room. The equipment also includes a built in smoke evacuator to help protect staff from the hazards of surgical smoke.

D. Scope

VISN 23 is seeking a base year plus two (2) option year contract for Stryker Neptune Rover and Docking System OR waste management equipment services and support, currently installed at V23 facilities. The Contractor shall include all equipment, materials, tools, parts, kits, labor, transportation (including travel and expenses), and expertise necessary to provide training, technical support, preventive and corrective maintenance, and repair services required to support and maintain the system, equipment and technology at the following VISN 23 facilities: Black Hills, Central Iowa, Fargo, Iowa City, Minneapolis, Omaha, St. Cloud and Sioux Falls.

E. Place of Performance

Unless otherwise noted, the Contractor shall provide service and support at the following VA VISN 23 facilities and addresses outlined in the table below.

VISN 23 Site	Address
568-BHH-Black Hills, Fort Meade, SD	113 Comanche Rd, Fort Meade, SD 57741
636A6-CIH-Central Iowa, Des Moines, IA	3600 30th St, Des Moines, IA 50310
437-FAR, Fargo, ND	2101 Elm Street N, Fargo, ND 58102
6368-IOW, Iowa City, IA	601 Highway 6 West, Iowa City, IA 52246
618-MIN, Minneapolis, MN	1 Veterans Dr, Minneapolis, MN 55417
636-NWI, Nebraska Western Iowa, Omaha, NE	4101 Woolworth Ave, Omaha, NE 68105
656-STC, St. Cloud, MN	4801 Veterans Dr, St. Cloud, MN 56303
438-SUX, Sioux Falls, SD	2501 West 22nd St, Sioux Falls, SD 57117

F. Period of Performance

Overall period of performance shall begin 10/15/25 and shall include one base year and two (2) option years:

Ordering Period	Period of Performance
Base Year	10/15/2025-10/14/2026
Option Year 1	10/15/2026-10/14/2027
Option Year 2	10/15/2027-10/14/2028

Unless otherwise noted, work shall be performed during normal business days and hours at each VA facility, which is typically comprised of Monday through Friday each week (except federal holidays) between 8:00 a.m. and 4:30 p.m. local standard time. Contractor shall confirm each facility normal business days and hours with facility Point of Contacts (POCs).

G. Inventory

The Contractor shall provide support services for the Stryker products listed below at each facility:

Model	Serial #	Location	Site
NEPTUNE DOCKING STATION	1916816473	218-113-FM	BHH
NEPTUNE 3 ROVER	1917031853	218-113-FM	BHH
NEPTUNE 3 ROVER	2425020073	B28-113-FM	BHH
NEPTUNE 3 ROVER	2425019833	B28-113-FM	BHH
NEPTUNE 3 ROVER	2425019823	B28-113-FM	BHH
NEPTUNE DOCKING STATION	2420809113	B28-113-FM	BHH
NEPTUNE DOCKING STATION	2419804123	B28-113-FM	BHH
NEPTUNE DOCKING STATION	2419804503	B28-113-FM	BHH
NEPTUNE 2 DOCKING STATION	1824207593	4216-01W-D	CIH
NEPTUNE 2 DOCKING STATION	1824339253	1712A-001-D	CIH
NEPTUNE 2 DOCKING STATION	1824905633	4301-001-D	CIH
NEPTUNE 3 ROVER	1829230253	4302A-001-D	CIH
NEPTUNE 3 ROVER	1828901233	4211-01W-D	CIH
NEPTUNE 3 ROVER	1829230443	4211-01W-D	CIH
NEPTUNE 3 ROVER	1829129993	4207-01W-D	CIH
NEPTUNE 3 ROVER	1829130113	1804-001-D	CIH
NEPTUNE 3 ROVER	1829230273	4206-01W-D	CIH
NEPTUNE 3 ROVER	1829224473	4302A-001-D	CIH
NEPTUNE 3 ROVER	1829230383	4220-01W-D	CIH
NEPTUNE 3 ROVER	1915120253	1B80	FAR
NEPTUNE 2 DOCKING STATION	1915031323	1B80	FAR
NEPTUNE 2 DOCKING STATION	1420204813	2B58	FAR
NEPTUNE 3 ROVER	1829601523	2B61	FAR
NEPTUNE 3 ROVER	1829601473	2B61	FAR

NEPTUNE 3 ROVER	1829601493	2B61	FAR
NEPTUNE 3 ROVER	1829601553	2B61	FAR
DOCKING STATION NEPTUNE 3	1821111543	1-IC-8E33	IOWACITY
DOCKING STATION NEPTUNE 3	1820823713	1-IC-4S18A	IOWACITY
DOCKING STATION NEPTUNE 3	1820823723	1-IC-4S18A	IOWACITY
NEPTUNE 3 ROVER	1825414823	1-IC-4W102	IOWACITY
NEPTUNE 3 ROVER	1825604083	1-IC-4S05	IOWACITY
NEPTUNE 3 ROVER	1825515483	1-IC-4S18A	IOWACITY
NEPTUNE 3 ROVER	1825414873	1-IC-8E34	IOWACITY
NEPTUNE 3 ROVER	1825308173	1-IC-4S18A	IOWACITY
NEPTUNE 3 ROVER	1825414813	1-IC-4W118	IOWACITY
NEPTUNE 3 ROVER	1825515563	1-IC-8E41	IOWACITY
NEPTUNE 3 ROVER	1825414913	1-IC-8E37	IOWACITY
NEPTUNE 3 ROVER	1825515463	1-IC-4W116	IOWACITY
NEPTUNE 3 ROVER	1825414713	1-IC-8E33	IOWACITY
NEPTUNE 3 ROVER	1825604013	1-IC-4W108	IOWACITY
NEPTUNE 3 ROVER	1825515493	1-IC-4S18A	IOWACITY
NEPTUNE 3 ROVER	1821200853	3V130-70	MIN
NEPTUNE 2 ROVER DOCKING	1824820823	2M114-70	MIN
NEPTUNE 2 ROVER DOCKING	1414807013	3V124B-70	MIN
NEPTUNE 2 ROVER DOCKING	1414806963	1M127-70	MIN
NEPTUNE 3 ROVER	1821111423	3V136-70	MIN
NEPTUNE 3 ROVER	1821111323	2M114-70	MIN
NEPTUNE 3 ROVER	1826810623	2Q110-70	MIN
NEPTUNE 3 ROVER	1821111353	2N101-70	MIN
NEPTUNE 3 ROVER	1821200963	2Q106-70	MIN
NEPTUNE 3 ROVER	1821106813	2Q104-70	MIN
NEPTUNE 3 ROVER	1821106753	2R117-70	MIN
NEPTUNE 3 ROVER	1821200833	3V133-70	MIN
NEPTUNE 3 ROVER	1821111433	2N101-70	MIN
NEPTUNE 3 ROVER	1826810603	2Q113-70	MIN
NEPTUNE 3 ROVER	1821200863	2Q118-70	MIN
NEPTUNE 3 ROVER	1826810663	2Q128-70	MIN
NEPTUNE 3 ROVER	1821111283	1M127-70	MIN
NEPTUNE 3 ROVER	1821106843	2Q118-70	MIN
NEPTUNE 3 ROVER	1821201063	3V131-70	MIN
NEPTUNE 3 ROVER	1821305943	2Q131-70	MIN
NEPTUNE 2 ROVER DOCKING	1122200133	2N101-70	MIN
NEPTUNE 3 ROVER	1821200873	3V134-70	MIN

NEPTUNE 3 ROVER	1821200923	3V132-70	MIN
NEPTUNE 3 ROVER	1821201073	1M127-70	MIN
NEPTUNE 3 ROVER	1932902023	2407-101-OM	NWI
NEPTUNE 3 ROVER	1932902333	2402-101-OM	NWI
NEPTUNE 3 ROVER	1933107173	4750-1	NWI
NEPTUNE 3 ROVER	1932901963	4786-1	NWI
NEPTUNE 3 ROVER	1933030163	4750-1	NWI
NEPTUNE 3 DOCKING UNIT	1926900103	2414-101-OM	NWI
NEPTUNE 3 ROVER	1712509383	4324-1	NWI
NEPTUNE 3 ROVER	1712509153	4324-1	NWI
NEPTUNE 2 DOCKING UNIT	1415411263	4324-1	NWI
NEPTUNE 3 DOCKING UNIT	1926922643	2414-101-OM	NWI
NEPTUNE 3 ROVER 0703-001-000	2425017153	B069C	NWI
NEPTUNE 3 ROVER 0703-001-000	2425018193	B069C	NWI
NEPTUNE 3 ROVER 0703-001-000	2425018203	B069C	NWI
NEPTUNE 3 ROVER 0703-001-000	2425019713	B069C	NWI
NEPTUNE 3 ROVER 0703-001-000	2425019733	B069C	NWI
NEPTUNE 3 ROVER 0703-001-000	2425019753	B069C	NWI
NEPTUNE 3 ROVER 0703-001-000	2425019763	B069C	NWI
NEPTUNE 3 ROVER 0703-001-000	2425019793	B069C	NWI
NEPTUNE 3 ROVER 0703-001-000	2425019843	B069C	NWI
NEPTUNE 3 ROVER 0703-001-000	2425020883	B069C	NWI
NEPTUNE 3 DOCKING 0770-100-000	2419804103	B069C	NWI
NEPTUNE 3 DOCKING 0770-100-000	2419804163	B069C	NWI
NEPTUNE 3 ROVER	1826810733	A222-001	STC
NEPTUNE 3 ROVER	1826810633	251-001	STC
NEPTUNE 3 ROVER	1826810693	A230-001	STC
NEPTUNE 3 ROVER	1826810653	249-001	STC
NEPTUNE 3 ROVER	1826704483	251-001	STC
NEPTUNE 3 ROVER	1826810703	A223-001	STC
NEPTUNE 3 ROVER	1826810673	A219-001	STC
DOCKING STATION-NEPTUNE 2	1824820833	250-001	STC
DOCKING STATION-NEPTUNE 2	1824905623	A230-001	STC
NEPTUNE DOCKING STATION	2002416263	513-5	SUX
NEPTUNE DOCKING STATION	1417401563	423-5	SUX
NEPTUNE DOCKING STATION	1416702623	G32-5	SUX
NEPTUNE 3 ROVER	2013913773	511-5	SUX
NEPTUNE 3 ROVER	2012617083	519-5	SUX
NEPTUNE 3 ROVER	1812206163	423-5	SUX

NEPTUNE 3 ROVER	1812206213	G27-5	SUX
NEPTUNE 3 ROVER	1812206193	G02-5	SUX
NEPTUNE 3 ROVER	1812206183	G02-5	SUX
NEPTUNE 3 ROVER	1812206223	G02-5	SUX
NEPTUNE 3 ROVER	1812100173	423-5	SUX
NEPTUNE 3 ROVER	1812206203	423-5	SUX

H. Equipment Changes

Equipment may be deleted from this agreement if replaced or "in excess" during the period of this contract at the discretion of the CO. New equipment may be added as needed at the discretion of the CO. Deleted equipment will be credited in the full amount if deleted before any scheduled maintenance has been performed on it. The Government reserves the right to purchase additional equipment not contained within this agreement as well as delete existing items upon the approval of the CO. The agreement shall be updated with the addition of new equipment and existing items that are taken out of service shall be deleted upon contract renewal and upon request.

J. Scheduled and Unscheduled Maintenance

The Contractor shall perform the service necessary to keep the equipment in good working order at each site. The Contractor will provide the necessary personnel and supervision to properly execute the preventative and corrective maintenance of the equipment specified in the "Inventory" section of this SOW. The Contractor must provide, upon request, documentation of factory certified service/maintenance training on the specific equipment under the terms of this contract.

The Contractor shall have field service representatives (FSRs) located within five hours of each facility listed under "Places of Performance." FSR shall have been trained by the Original Equipment Manufacturer (OEM) on the specific model of equipment they are being asked to work on. The Contractor shall provide the training documentation upon request.

The Contractor shall supply and bear the cost of all parts required for service repair and maintenance and, as a result of normal wear and tear, restore equipment to full performance system in operating condition as originally designed by the manufacturer. Parts may be repaired or replaced, as the Contractor deems appropriate. No used parts will be used to repair this equipment.

The Contractor shall have spare parts available required for maintenance and repairs. If equipment is defective or fails to operate, the Contractor shall repair or replace defective parts or the equipment. All parts used shall be OEM parts only. Reverse engineered and/or refurbished parts shall not be utilized under the terms of this contract without explicit permission, in writing, from the Contracting Officer (CO) after CO consultation with VA Technical Representative (VATR). Subcontracting of any ensuing award of this solicitation will not be allowed without written permission of the CO.

The Contractor shall ensure that the equipment/system functions in conformance with the latest published edition of NFPA-99, OSHA. The Contractor shall provide and utilize procedures and checklists with worksheet originals indicating work performed and actual values obtained (as applicable) provided to the on-site POC(s) at the completion of the service.

The Contractor test equipment calibration shall be traceable to National Institutes of Standard Technology standards. Each service report shall list test equipment used and date calibration to NIST is due. Test equipment out of calibration shall not be used.

Scheduled Maintenance: The Contractor shall perform scheduled (preventive) maintenance in accordance with manufacturer's recommendations of all system hardware and equipment installed at all VISN 23 facilities. The Contractor shall initiate corrective maintenance with the COR and facility POC(s) concurrence, whenever equipment defects are discovered as a result of the Contractor performing scheduled/preventive maintenance services. Any defects found during scheduled maintenance shall be fixed.

The Contractor shall provide scheduled maintenance for the system equipment during normal working hours at a mutually agreed upon time by the COR, facility POC(s) and the Contractor. The Contractor shall contact the COR and facility POC(s) to schedule mutually agreeable times for the performance of any scheduled activities. The Contractor shall recommend to the COR and facility POC(s) when equipment should be made available for scheduled maintenance. Upon COR and facility POC(s) approval, the Contractor shall finalize that schedule.

The Contractor shall provide at least sixty (60) day notice to on-site POC(s) when downtime is required for routine maintenance and training. Emergency maintenance shall be planned with the on-site POC(s).

Unscheduled Maintenance: The Contractor shall provide the VISN and VA facilities with an unlimited number of unscheduled maintenance, corrective maintenance and technical support incidents during the task order performance period with COR and facility POC(s) concurrence. Support includes both remote and on-site support. All support requests shall be tied to a Contractor provided ticketing system for tracking purposes. The Contractor shall be liable for any incidents caused by damage or neglect on their part. The Contractor shall troubleshoot, repair and/or resolve, on request by the COR or facility POC(s), all equipment installed at each VISN 23 site. All equipment repaired by the Contractor shall be restored to manufacturer's specifications.

Equipment replacement due to maintenance remediation shall be the Contractor's responsibility. In the event that the Contractor is unable to repair or resolve an equipment problem, including all system associated components such as cables, the Contractor shall promptly replace all system hardware and equipment installed at each VISN 23 site at no additional cost.

K. Electrical/Power

The components shall use existing electrical services of VA facilities and operate with a line of power of 120 Volts AC and current draw less than 20 Amps.

L. Telephone and Online Support and Technical Consultation

The Contractor shall provide VA with toll-free corporate office telephone numbers and email addresses for the Contractor's key staff for normal hours. The Contractor shall provide telephone and online remote support for maintenance and technical support. The Contractor shall allow an unlimited number of requests.

The Contractor shall provide customer support assistance for technical problems, functional incidents, or general questions during business hours. The Contractor shall provide the following communication

options: a Contractor help desk number, for incidents or general questions. For each request, the Contractor shall communicate the following via email or telephone to VA facilities or make available online, in response to each event communicated by VA to the Contractor:

1. Brief Description of the problem.
2. What equipment or component is being affected.
3. If this issue affects patient safety.
4. Workaround (if any) and expected remediation date.
5. Status and estimated completion date/time.

The Contractor shall communicate known material or equipment issues to the COR and facility POC(s) monthly via monthly service reports. The Contractor shall respond to a request for unscheduled corrective maintenance for material or equipment issues, malfunctions, or failures, by a fully qualified representative, in accordance with response time requirements defined in this SOW.

M. Response Time

The Contractor shall provide the maintenance and technical support within a specified time published in the response time requirements below. If the Contractor cannot resolve the problem over the phone or remotely, then an authorized representative from the Contractor shall commence work within the designated time identified, and rectify the problem without undue delay and at no additional cost to the government. The Contractor shall be responsible to coordinate the method of response with the COR and facility POC(s).

1. Urgent priority is defined as any issue that affects patient safety and/or regulatory compliance, which affect life and/or property. Urgent priority applies when malfunction or failure can result in patient injury or death or significant damage to equipment. This includes any issue that adversely impacts patient care. Examples include partial or complete system outages, interruptions making a critical functionality inaccessible, interruptions causing a severe impact on application availability, or data corruption resulting in missing or incorrect patient information, duplicate records, loss of data, etc. Urgent priority requires a response from the Contractor to be on-site within 24 hours.
2. High priority is defined as having a potential to affect patient care such as degradation in performance or functionality, work flow interruptions or delays, etc. High priority warrants special attention and takes precedence over normal and low priorities. Examples include interruption to critical functionality, access denied to data and systems, sustained degraded or unusable capabilities, not life threatening but having a potential for impact on services availability if not resolved. High priority also requires immediate action by the Contractor in order to minimize risk of becoming an urgent priority event.
3. Normal priority is defined as a defect or fault event but the system is operable with no impact to patient care. Normal priority requires same day initial action but resolution may take more time. Examples include impairment of non-critical functions or procedures, capabilities that have become unusable or hard to use but with no direct impact on patient care services or system availability. Normal priorities will typically have a workaround available. Normal priorities take precedence over low priorities.
4. Low priority is defined as preventive maintenance or issues that do not require immediate action or attention.

Below is a list response times by priority types as defined by VA. The Contractor shall meet the response time requirements associated with each priority:

Priority	Call Back Response	On-Site Response
High-Urgent	1-2 hours	24 hours
Low-Normal	2-4 hours	72 hours

The Contractor shall provide on-site support for repairs that are unable to be resolved via phone or email support and have a technician on site within seventy-two (72) hours for low or normal priority repairs and within twenty-four (24) hours for high or urgent priority repairs.

If Full Performance cannot be restored within the above timelines, the Contractor shall notify the Government as soon as restoration time is known. The notification shall include a projected repair completion time and the reason for the delay.

N. Service Reports and Electronic Service Log

The Contractor shall provide a Service Report to the VA facility POC emails within 72 hours of completion of a remote or on-site service call.

The Contractor shall provide and maintain an Electronic Service Log with consolidated service report data for tracking of all services performed under this contract for all system and product installations. This Electronic Service Log shall be VA-accessible. The content of the log shall include all service calls, repairs, special service requests generated throughout the duration of the contract.

The Service Report and each service item on the Electronic Service Log shall document the services rendered and, when applicable, shall include a unique reference number, equipment description, model, equipment entry (barcode) number, serial number, date and time of failure reported, date, time and location of service, description of services, detailed descriptions of the issue or scheduled and unscheduled maintenance procedures performed, root cause, corrective action taken including replaced parts, follow up action required, estimated completion time, date complete, results of services, VA submitter, name of individual who performed the services, and travel, labor and parts information.

This log can be web-based for easy access by the Government and the Contractor. The Contractor shall provide a sample of the above log for approval by the COR and facility POC(s) before implementing the Electronic Service Log.

O. Product Modifications, Removal or Recall

The Contractor shall guide the VISN and facilities through obtaining any additional hardware needed to avoid obsolescence during the performance period. The Contractor shall notify the COR and facility POC(s) when supplied hardware will approach EOL/EOS and shall offer replacement that hardware. The Contractor shall promptly notify the COR and facility POC(s) of any recalls and end of life/service cycles.

If any product supported under this agreement and subsequent task orders requires modification, is removed or recalled by the Contractor or manufacturer, or if any required modification, removal or recall is suggested or mandated by a regulatory or official agency (such as the manufacturer, Food and Drug Administration, The Joint Commission), the Contractor shall notify the COR and facility POC(s) within forty-eight (48) hours via email notification that includes the following information:

1. Complete item description and identification.
2. Reasons for modifications, removal, or recall.

3. Necessary steps for return for credit of the equipment, devices and products replacement, or corrective action.

The Contractor shall provide the above information to the Contracting Officer, COR, and facility POC(s) for all VA Facilities who purchased the product. The COR shall be provided a copy of the notification and a list of all VA facilities notified. The Contractor shall perform all steps required for return for credit, replacement, or corrective action for all affected facilities.

P. Security

The Contractor shall comply with all VHA security protocols, procedures and requirements of the VA's Office of Information Technology including filling out and providing all necessary forms upon request within ten (10) days from receipt from the VA.

Q. Check In/Out Procedures

The Contractor shall coordinate Check In/Out with the facility POC(s). For any services performed on-site the Contractor shall, upon arrival at the facility, report to the facility POC to check in before proceeding to the any department and before performing any services. Prior to leaving the medical center, the Contractor shall check out with the facility POC. This check in and check out is mandatory as well as wearing the Contractor badge issued upon checking in.

The Contractor personnel shall follow all VA policies, standard operating procedures, applicable laws and regulations while on VA property. Violations of VA regulations and policies may result in citation and disciplinary measures for persons violating the law.

1. The Contractor personnel shall comply with VA Privacy Training requirements.
2. The Contractor personnel shall wear visible identification at all times while they are on the premises. Identification shall include, as a minimum, the employee's name, position, and the Contractor's trade name. In addition, if required the Contractor shall submit fingerprints through the VA police for issuance of a VA identification badge that shall be worn at all times while working at a VA facility.
3. VA does not provide parking space at the work site; the Contractor must obtain parking at the work site if needed. It is the responsibility of the Contractor to park in the appropriate designated parking areas. VA will not invalidate or make reimbursement for parking violations of the Contractor under any conditions.
4. Smoking is prohibited inside/outside any building other than the designated smoking areas.
5. Possession of weapons is prohibited.
6. The Contractor shall obtain all necessary licenses and/or permits required to perform the work. The Contractor shall take all reasonable precautions necessary to protect persons and property from injury or damage during the performance of this agreement.
7. The Contractor shall comply with any additional safety guidelines in place at a VA facility, which may include providing their own PPE.

R. Manuals and Service Bulletins

VA will not provide service manuals to the Contractor. The contractor shall obtain, have on file, and make available to its Field Service Engineers (FSEs) all operational and technical documentation, (such as: operational and service manuals, schematics, and parts list), which are necessary to meet the performance requirements of this contract. The location and listing of the service data manuals, by name, and/or the manuals themselves shall be provided to the COR and facility POC(s) upon request.

Upon request, the Contractor shall provide unlimited electronic copies and ongoing web-based access of the following documentation necessary for the operation and support the system. Any upgrades to these documents shall be provided by the Contractor free of charge.

1. User Operating/Maintenance Manuals and Service Bulletins.
2. Complete technical service manuals including troubleshooting guides, necessary diagnostic equipment, schematic diagrams, and parts lists.
3. Electronic schematics, troubleshooting guides and parts lists for each piece of equipment purchased.
4. Manuals shall include all components and subassemblies, including those not manufactured by the Contractor.
5. Manuals and documentation shall be identical to the ones supplied to the manufacturer's service representatives and shall contain the diagnostic codes, commands, and passwords used in maintenance, repair and calibration of the equipment.
6. Training videos and materials for future staff.

S. Disinfecting Instructions

The Contractor shall provide training instructions, procedures, and documentation necessary to disinfect the equipment and accessories properly and safely.

T. Training

The Contractor providing the equipment, support and maintenance service will be responsible for staff/user clinical and Biomed Technician service and support technical training remotely and/or on-site. Training would include setup and user training, super user training and follow-up training. Training materials provided (instructional texts, audio-visual materials) will become the property of the government and will be reproduced as needed.

Upon request, the Contractor shall coordinate with facility POC(s) and COR to provide staff education at a day/time that works for each VA facility. A System Technology and Services education professional (not sales reps) that is familiar and knowledgeable on the products installed shall administer the training. Education curriculum must include the following:

1. Clinical training:
 - a. Clinical training for super-users, nurses, physicians, and other clinical staff.
 - b. Training shall be provided on the equipment, system, and its features.
 - c. Training shall provide super-users and end-users with the capability of being self-sufficient in operating the equipment and system by the end of the training session.
 - d. Provide quick notes and/or reference guides during on-site training for each site.
2. Technical training:
 - a. Technical training for maintenance and service for technical personnel at each site. Training should at minimum address the following topics but not limited to:
 - i. Preventive maintenance procedures.
 - ii. Operations, configurations and set-up.
 - iii. User maintenance.
 - iv. Repair in house.
 - v. Safety.
 - vi. User troubleshooting tips.

U. Delivery, Shipping and Materials Requirements

The Contractor shall coordinate in advance with on-site designated facility POC(s) and COR the delivery of parts to final destination and obtain the appropriate Supply Chain Management POC to include in the communication plan. All equipment must be processed through Supply Chain Management prior to going to final destination. Prior to shipping any equipment or other material, the Contractor shall notify facility POC(s) and COR by email of all incoming deliveries including line-by-line details for review of requirements and to ensure sites have adequate storage space. Parts shall not be delivered more than one week prior to installation. Parts shall be stored no longer than one week in the warehouse. The Contractor shall make any changes to the delivery schedule at the request of facility POC(s) and COR. The Contractor shall provide parts delivery, shipping and tracking information to the facility POC(s) and COR in advance before equipment arrival at the facility.

The Contractor shall provide overnight, next-day delivery of parts when needed to maintain full performance of the system. The Contractor shall provide shipping to return any defective parts from VA Facilities to the Contractor. There shall be no additional cost to the Government for shipping.

The Contractor is responsible for inventorying materials prior to delivery to VA sites to check for accuracy in quantity and part number. Materials provided shall be new parts, and accessories. Hardware shall be the newest, state of the art available and shall provide the highest level of development at time of replacement. The Contractor shall deliver materials to the job site in OEM's (Original Equipment Manufacturer) original unopened containers, clearly labeled on the external shipping labels and associated manifests or packing lists with the OEM's name, equipment model and serial identification numbers, Purchase Order (PO) number and facility Technical POC. The Contractor shall tag the bill of materials by area/room for ease of installation.

In the case of multiple container deliveries, a statement readable near the VA PO number shall indicate total number of containers for the complete shipment (i.e., "Package 1 of 2"), clearly readable on manifests and external shipping labels. Facility POC (s) may reject items that do not conform to any of these requirements.

V. Disposal of Waste and Job Site Cleanup

All waste will be removed by the Contractor. The Contractor shall maintain and dispose of all material waste and packaging associated with the delivery of all items and/or waste generated during the services provided. The Contractor will be responsible for moving waste materials daily from job site(s) to a Contractor-provided vehicle and waste container, and then to an off-site location. The Contractor shall provide a waste removal plan to the COR and facility POC(s).

W. Inspection and Acceptance

The Contractor shall inspect, adjust, repair and test to ensure safe reliable equipment and service within all tolerances as required by manufacturer's specifications. The Contractor shall conduct a joint inspection of equipment and services with the facility POC(s) upon completion of the service. In the event deficiencies are identified, the Contractor shall provide the date when the identified deficiencies will be addressed if not addressed on the date of installation. The Contractor shall conduct a joint inspection of equipment and services with the facility POC(s) after addressing all deficiencies. All deficiencies identified in the joint inspections shall be fixed by the Contractor prior to government acceptance of the item. Any disputes shall be resolved by the Contracting Officer.