



Office Workplace Furniture – Tier II Statement of Work

Date: 02/17/2025

Facility# 20015

Area B

1864 Fourth Street

Wright-Patterson Air Force Base, OH 45433

RM163 Additional Desks and Storage (RTW)

[REDACTED]

[REDACTED]



Revision History

Author Name	Date	Reason For Changes	Version



1.0 Background cover sheet or appendix

This project is being solicited in compliance with the Department of Air Force Office Workplace Furniture Program. Manufacturers (Tier I) have established discounted prices for their product lines and have authorized specific small business dealers (Tier II) to propose on projects using the discounted pricing.

2.0 Scope

This project will be proposed using product lines with discounts as described in the tier I contract. Discounted product pricing has been previously established by the Tier I manufacturer for each product line, but the contractor in this case, an authorized Tier II dealer of said manufacturer, will propose discounted pricing for those items or services on the Tier I discount list. This project will be awarded on a competitive basis using total project cost.

- The Contractor shall provide all supervision, labor, materials, equipment, and when applicable Certified Electrician to hook up the Systems Furniture to Building power, including transportation to accomplish this project in accordance with this Statement of Work (SOW), project drawings.
- The Contractor shall provide 30 days storage and the requirements contained in the soliciting documents.
- The Contractor shall provide Reconfiguration/Relocation of Existing Typical H to allow for Maximization of Workstations ***RECONFIG-1, see section 2.0 scope product chart for details.***
- The Contractor shall include an itemized quote that includes labor to receive, inspect, deliver to project job site, and install product per approved final design layout.
- The Contractor may include AutoCAD design hours for all phases of design (initial, revisions and final).
- The Contractor may include design hours for in person meetings to review all phases of design (initial, revisions and final), finish selections, site visits (field measurement), and any other means and methods for the contractor to execute the project.
- Reference section 3.2.11 for updated power harness requirements per UFC 3-520-01 (Change 2, 12 April 2021).
- For this project provide power poles for the workstations. A certified electrician shall provide hardwire connection complete from the workstations to building power. Provide break box labeling for new and/or altered circuit.
- For this project repair/replace flooring and ceiling, where applicable if damaged upon furniture installation of project.
- The Contractor shall provide overall 2D Floor Plan and 3D Image of each typical.

For this project we require the following product types: *Systems Furniture, Modular Freestanding, Storage, and Seating.*



PRODUCT –Basis of Design-Haworth Compose

<u>TAG/TYPICAL</u>	<u>DESCRIPTION</u>	<u>QTY</u>
RECONFIG-1	RELOCATION TYPICAL H - INDICATED ON THE 05A-PLN IN GRAY HATCH.. Relocate (1) Typical H from Area 10 to Area 3; Relocate (4) Typical H from Area 2 to Area 1; Relocate (1) Typical H from Area 10 to Area 9. If the relocation requires additional part to make a full connection in new configuration – include all parts/labor to make fully functional workstations.	6
RECONFIG-2	RELOCATION OF LK-3 (LOCKER GARAGE AND MOBILE PEDS) PER PLAN - INDICATED ON THE 05A-PLN IN LIGHT GREEN	12
	MODULAR SYSTEM FURNITURE -- Minimum Technical Requirements MODULAR SYSTEM PANEL, Minimum Technical Requirements, Basis of Design - Haworth(Compose), Panel Mounted Components, Laminate Worksurface with Vinyl Edge, Metal Storage, Locking Storage, Taper Pulls, Computer Accessories (monitor arms, power modules, keyboard pull out, etc). 3" Thick Welded Cold-Rolled Steel Stack Panel Frame, Stack Panel Permits Stacking Modules In-Field, STC Panel Rating -20, Metal to Metal Interlocking Panel Connectors, 3" Adjustment Range on Base Levelers, Combination of Interchangeable Segmented Tiles to Include: Acoustical Fabric/Tackable/Glass/WhiteBoard/Laminate/Open Tiles, Sliding and Hinge Door Available for 81" +/- Panel Height, Power and Non-Power Panels, Power/Communication Shielded Distribution, Capable of Running Max 30 Data Cables (horizontal and vertical), Power Panels to Include 3-4 Receptacles, 2 Knock-Out Voice Data Quad Port Per Cubicle, Base/Ceiling Power Input, All Connectors, Finish Trim, Hardware and Supports for a Complete Install to be included for Full Installation. Furniture Contractor to Provide Certified Electrician to Make connections from Building Power to Modular Panels. See Plan for Panel Elevation and COMM/Power Input Ceiling Feed locations. Final Finish Selection to be Selected After Award.	
H2-r	TYPICAL H2-r Hoteling Stations, 6x4, 24 SqFt Note: Galley Panels on End only, Acoustic Panel between Stations depending on layout. Reference Floorplan.	13



	2 - P36-POWER PANEL 48-50"H, Acoustical Tiles Gr B, 9" Frameless Glass Stack GS60, 3-4 Power Outlets and 1 Data Knockout per Station 2 - P36-NON-POWER PANEL 48-50"H, Acoustical Tiles Gr B, 9" Frameless Glass Stack GS60, Use between desk for additional acoustical value (as seen in Quad Station reference on left) 2 - GALLERY END PANEL, 72"Wx50"H; Laminate (Double Station), 9" Frameless Glass Stack GS 1 - WS1 - WORKSURFACE, Rectangular, Top, 60X30, Center Grommet, Cable Management, Wire Basket and Cover, HAW Electric Base 1 - HAW - Height Adjustable Base, Sit to Stand, 58x28, Electric Control (no memory settings), Powder Coated Base - Silver/Putty 1 - CS2 - COMPUTER SUPPORT TOOLS - Monitor Arms, Dual Monitor with Individual Crossbar, Clamp and Grommet Mount Capability, Wire Management Down Arm, Gas Assist Lifting, One Finger Adjustment, 360 degree movement, Hold Monitor Weight 12lbs to 38lbs, Warranty 15 yr., color-Black 1 - POWER MODULE - Personal Desktop Power, Clamp Mounted, 2 AC outlets, 1- USB-A and 1- USB-C quick charge, with attached power strip mounted below surface, UL and cUL listed, 8' power cord, color-Black 1 - TASK LIGHT - LED, Personal Task Light, Clamp Mounted or Panel Mounted-Black 1 - LK3 - PANTRY STORAGE LOCKER - Single, Pull-Out, 12"WX30"Dx50"H, Laminate, 2 Fixed Shelves, 2 Adjustable Shelves, 2 Accessory Rails, 1 Hook 1 - H-r Return, Mobile, Freestanding Storage, Locking Casters, Laminate 1 - WS2 - WORKSURFACE, Rectangular, Common Top, 42x18, No Grommet 1 - PED - PEDESTAL Storage, Box/File, with Pencil Tray and Rails 1 - OS30 - OPEN SHELVING, 1 Adjustable Shelf, Laminate	
--	--	--



H-r	TYPICAL H-r H-r Return, Mobile, Freestanding Storage, Locking Casters, Laminate 1 - WS2 - WORKSURFACE, Rectangular, Common Top, 42x18, No Grommet, Wood Laminate 1 - PED - PEDESTAL Storage, Box/File, with Pencil Tray and Rails, Wood Laminate 1 - OS30 - OPEN SHELVING, 1 Adjustable Shelf, Solid Color Laminate	24
H	TYPICAL H Hoteling Stations, 4x5, 20 SqFt Note: Galley Panels on End only, Acoustic Panel between Stations depending on layout. Reference Floorplan. 1 - P60-POWER PANEL 48-50"H, Acoustical Tiles Gr B, 9" Frameless Glass Stack GS60, 3-4 Power Outlets and 1 Data Knockout per Station 2 - P36-NON-POWER PANEL 48-50"H, Acoustical Tiles Gr B, 9" Frameless Glass Stack GS60, Use between desk for additional acoustical value (as seen in Quad Station reference on left) 2 - GALLERY END PANEL, 72"Wx50"H; Laminate (Double Station), 9" Frameless Glass Stack GS 1 - WS1 - WORKSURFACE, Rectangular, Top, 48X24, Center Grommet, Cable Management, Wire Basket and Cover, HAW Electric Base 1 - HAW - Height Adjustable Base, Sit to Stand, 46x22, Electric Control (no memory settings), Powder Coated Base 1 - CS2 - COMPUTER SUPPORT TOOLS - Monitor Arms, Dual Monitor with Individual Crossbar, Clamp and Grommet Mount Capability, Wire Management Down Arm, Gas Assist Lifting, One Finger Adjustment, 360 degree movement, Hold Monitor Weight 12lbs to 38lbs, Warranty 15 yr., color-Black 1 - POWER MODULE - Personal Desktop Power, Clamp Mounted, 2 AC outlets, 1- USB-A and 1- USB-C quick charge, with attached power	4



	strip mounted below surface, UL and cUL listed, 8' power cord, color-Black 1 - TASK LIGHT - LED, Personal Task Light, Clamp Mounted or Panel Mounted 1 - LK3 - PANTRY STORAGE LOCKER - Single, Pull-Out, 12"WX30"Dx50"H, Laminate, 2 Fixed Shelves, 2 Adjustable Shelves, 2 Accessory Rails, 1 Hook	
T.MU	T.MU - TASK CHAIR, SIT ON IT (Focus 2.0) or Equal, High-Back, Mesh Back Task Chair: Metal or glass reinforced nylon 5-star 360 swivel base with dualwheel carpet casters, black finish on base and structural components, pneumatic height adjustment, synchronized tilt mechanism or multi-tilt mechanism, height-adjustable lumbar support, adjustable tension control, adjustable forward tilt and back lock, adjustable seat pan with "waterfall" seat edge, separate seat and back, seat width minimum of 18 inches, fully adjustable armrests (up/down, in/out, front/back, pivot left/right), weight capacity of 300 lbs., approved mesh and fabric to be selected from catalog at time of ordering, Upholstery Back: Black Mesh-Freeway, Upholstery Seat: CF Stinson LaredoL18 Onyx, Base: Black Plastic, Accent Color: Nickel, Casters: Carpet - match existing	17
	FINISHES: Laminate-Amber Cherry/Putty Solid Laminate, Panel Fabric - Gr. B (Fields-Prairie), Metal- Standard Paint (Putty), Accessories- Silver, Glass-Clear Final Finish Selection to be Selected After Award - match existing stations <i>All finishes to be finalized after award.</i>	

See Detail Documents Below of Typical Furniture Plans and Cutsheets Attached:
FURNITURE PLANS

05a -PLN- F20015-163 Additional Desk-RTW 2025TP094

CUTSHEETS

05b-CTS-01-H2r- F20015-163 Additional Desk-RTW 2025TP094

05b-CTS-02-Hr- F20015-163 Additional Desk-RTW 2025TP094

05b-CTS-03-H- F20015-163 Additional Desk-RTW 2025TP094

05b-CTS-04-T.MU- F20015-163 Additional Desk-RTW 2025TP094

Once the contract has been awarded, it becomes the responsibility of the contractor to validate the actual site conditions as well as any specific programming needs of the customer. In no case shall prices exceed discounted price amount established in the Tier I contract. It is understood that the actual site parameters or certain customer requirements may deviate from the standard typical layouts; therefore, any deviation that causes an increase in the price submitted during the bid process must be documented in writing and submitted to the Contracting Officer for review,



along with a floorplan reference to show just cause. A final furniture layout and Bill of Materials (BOM) will then be provided that meets the customer requirements and accommodates the physical environment. Design parameters and expectations are followed in Section 3.2

3.0 Description of Work

Once the contract has been awarded, it becomes the responsibility of the contractor to validate the actual site conditions as well as any specific programming needs of the customer. Contractor will also meet in person with Interior Designer (**Tina Penick; tina.penick@us.af.mil**) and end user to finalize finishes.

3.1 General Services

Coordination and management of all products, equipment and people required to create, deliver, and install new office workplace furniture within an Air Force location. This includes ongoing servicing of any items defective due to manufacturing error as well as for replacement or repair of any damaged item after purchase.

- 3.1.1 The contractor shall perform tasks on Office Workplace Furniture in accordance with the requirements stated in this contract and the tier I Contract.
- 3.1.2 The contractor shall be responsible for all personnel, equipment, tools, materials, supervision, storage, assembly, transportation, incidentals and all other items and services necessary to provide and install office workplace furniture.
- 3.1.3 The contractor shall be knowledgeable of and shall comply with all applicable federal, state, and local laws, codes, permits, DoD, AF, and base requirements and instructions required for the performance of the duties in this Statement of Work (SOW).
- 3.1.4 The contractor shall ensure policies and procedures are established that protect the safety and welfare of customers, employees, and the community to minimize or eliminate safety or environmental risks. These policies shall be in compliance with Federal and Installation policies and procedures.
- 3.1.5 The contractor shall provide a contract manager who shall be responsible for the performance of the work. The name of this person and an alternate or alternates who shall act for the contractor when the manager is absent shall be designated in writing to the Contracting Officer (CO) within 10 days after contract award. The contract manager or alternate shall have full authority to act for the contractor on all contract matters relating to the daily operations of this contract on the installation.



- 3.1.6** The contractor shall provide a Project Manager with a minimum of 3 years of experience installing your company's product, responsible for project site management, scheduling, coordination, and technical assistance to the Air Force representative as required throughout the project. Resumes and letters of intent shall be provided upon request.
- 3.1.7** Any electrician provided by the contractor shall be a licensed electrical contractor.
- 3.1.8** The contractor shall submit a complete list of personnel in accordance with installation policy, including deliverymen, who will be expected to work on the installation. This list will contain Privacy Act information as required as well as the expectation that each individual will be able to present a current and valid state/federal identification complying with the REAL ID Act, to meet local Air Force security requirements. (Please note that many installations require this information be coordinated days in advance).
- 3.1.9** The contractor shall not employ persons for work on this contract if such employee is identified to the contractor by the CO as a potential threat to the health, safety, security, general well-being or operational mission of the installation and its population. Contractor personnel shall present a neat appearance and be easily recognized as contractor employees.
- 3.1.10** The contractor shall be the authorized dealer of the specific office workplace furniture manufacturer proposed for the project.
- 3.1.11** The contractor shall manage ordering, shipment, delivery, and installation of all new furniture from manufacturer to final acceptance by the Government Project Manager (GPM).
- 3.1.12** The contractor shall provide customer service during normal duty hours, 0730-1630 hours, Monday through Friday; except for federal holidays.
- 3.1.13** Recognized US Federal Holidays are as follows: New Year's Day, Birthday of Martin Luther King Jr., Washington's Birthday, Memorial Day, Juneteenth National Independence Day, Independence Day, Labor Day, Columbus Day, Veterans Day, Thanksgiving Day, and Christmas Day. If the holiday falls on a Saturday, it is observed on Friday. If the holiday falls on Sunday, it is observed on Monday.
- 3.1.14** When the contractor desires to work other than standard times, a written request shall be submitted to the GPM for approval. Written approval from the CO must be received before proceeding with the work. The request shall be submitted at least five (5) workdays prior to the proposed performance of work, and it shall indicate the day/days, time/amount of work, and reason why performance is necessary during nonstandard hours.
- 3.1.15** The contractor shall provide alternate work locations for employees or allow employees to take vacation during designated Government non-workdays or other periods where government offices are closed.



- 3.1.16 All Air Force inquiries shall be responded to by a contractor representative within two business days.
- 3.1.17 Meetings may periodically be held between base personnel and contractor management to discuss contract status. The CO will notify the contractor in writing in advance of the place and time of required meetings.
- 3.1.18 Reserved
- 3.1.19 The contractor shall be responsible for coordination of an escort through any controlled areas through the local GPM.
- 3.1.20 Lost vehicle and entry passes shall be reported immediately to the Security Police as well as the GPM in accordance with the local security forces policy.
- 3.1.21 The contractor shall be responsible for any storage up to maximum of 30 days of all office workplace furniture, components, parts, and assemblies prior to and during installation in accordance with the agreed upon delivery schedule.
- 3.1.22 Reserved
- 3.1.23 The contractor shall maintain the capability to adjust workforce in the event of unforeseen circumstances such as extended duty hours, travel, classes and education, and mission related changes. These expenses are reimbursable with prior approval of the GPM and the CO.
- 3.1.24 The contractor shall maintain continuity between the support operations at **FACILITY 20015, WPAFB, Ohio** and all other assigned performance locations and the contractor's corporate offices. The contractor shall provide the necessary resources to manage and administer the contract. The contractor shall, as a minimum, maintain a single point of contact for this effort to be available in person to the 88ABW Civil Engineering Directorate, CENM, **Tina Penick**, Interior Design Specialist, **937-656-3452** or thru email at **tina.penick@us.af.mil** during the same business day.
- 3.1.25 The contractor shall provide for the management and support of personnel, to include: making necessary arrangements for employees required to travel; supporting personnel co-located at **FACILITY 20015, WPAFB, Ohio**, and other locations specified with additional resources, expertise, advice; necessary infrastructure to support work to be accomplished off-base; conducting personnel meetings; providing administrative support for employees in a timely fashion; and providing facility and staff security requirements.
- 3.1.26 All personnel attending meetings, answering Government telephones, and working in other situations where their contractor status is not obvious to third parties are required to identify themselves as such to avoid creating an impression that they are Government officials. They must also ensure that all documents or reports produced by contractors are suitably marked as contractor products or that contractor participation is appropriately disclosed.



3.2 Design Service

- 3.2.1** Providing professionals versed in programming, space planning and product specification, able to communicate product capabilities to the customer, to ensure products purchased meets the requirements.
- 3.2.2** As a part of the request for proposal/quote process, the contractor will propose products and a design that takes into account site layout considerations, as well as other information gathered during initial customer review at the discounted price upon which the award will be based. In no case should product prices exceed the discounted amounts set forth in the Tier I contract applicable to the contractor. The proposal shall show list price and discount and net price.
- 3.2.3** The contractor shall provide design services, including space planning, site verification, material selection and programming as necessary for the project.
- 3.2.4** The contractor shall define and furnish the necessary hardware, software, and all other equipment necessary to accomplish design tasks. Standard equipment in addition to the hardware and software shall include but not necessarily be limited to reproduction machines, plotters, paper, pencils, fax machines, and office furniture.
- 3.2.5** The contractor shall be responsible for collection of information relevant to the design/redesign of a space. Examples could include personnel interviews, questionnaires, and walk-through inspections of the facility, as well as the existing furniture database (if available).
- 3.2.6** Services shall include site evaluation to ensure proper fit of the furniture within the given space and that all structural and other anomalies are taken into account.
- 3.2.7** The contractor is responsible for notifying the GPM of all power requirements regarding location of communication, LAN, and power junction boxes, with the expectation that the government will be responsible for providing and locating those junction boxes within 4'-0" of the ceiling penetration of the power pole location provided by the contractor.
- 3.2.8** Design shall ensure that power poles do not protrude into main walkways.
- 3.2.9** Design shall ensure that all outlets included in the design are accessible to the user, free and clear of obstacles.
- 3.2.10** Design shall not allow more than four cubicles to be served by a single circuit. Per UFC 3-520-01 section 3-6.1.2 Limit loads to a maximum of four (4) workstations per 20A circuit.
- 3.2.11** Design shall include Systems Furniture pre-wired harness per UFC 3-520-01 section 3-18.2 Unless specified otherwise, select a standard wiring harness that meets one of the following configurations:



- 3.2.11.1 8-wire harness consisting of 3 circuit conductors, 3 neutral conductors and 2 equipment grounding conductors
- 3.2.11.2 10-wire harness consisting of 4 circuit conductors, 4 neutral conductors and 2 separate equipment grounding conductors.
- 3.2.12 Design shall ensure that minimum two duplex outlets (four plug in points) are put onto the same circuit. Per UFC 3-520-01 section 3-6.1.2 Receptacle Office, staff-support spaces, and other workstation's locations: Minimum of two duplex receptacles, one double duplex, or one quadraplex receptacle for each workstation.
- 3.2.13 Design shall ensure that no existing wall outlets or thermostats are covered or concealed by panels or other systems furniture components.
- 3.2.14 Design shall consider utilize wall mounted applications where possible.
- 3.2.15 The contractor shall utilize any existing government product to its maximum as applicable when project includes add on parts to existing systems furniture.
- 3.2.16 All designs of furniture layouts, including original designs and any subsequent redesigns, must be accomplished by qualified professional designers and should have three years' experience using software similar to that proposed for this contract.
- 3.2.17 The contractor shall meet with the GPM to review the installation drawings prior to submission of any revised price quote.
- 3.2.18 The contractor shall provide additional drawings of furniture layouts, if requested by base organizations via mutually agreed upon electronic media transfer in both .dwg and .pdf formats unless otherwise specified in the contract.
- 3.2.19 The hardware/software shall perform computerized inventory, computer aided design, automated take-off function, and report generation for all product purchased. The software for this contract shall be compatible software for AutoCAD and Revit. The software shall be fully compatible with Microsoft Windows, the most current version.
- 3.2.20 Design service shall include an initial complete design with up to **three additional revisions** prior to final approval.
- 3.2.21 Designs of each location shall include a Basic component floor plan sheet in which all systems furniture and workstation is tagged: to include graphic symbols for all major hanging components (flipper cabinets, shelves, task lights, tack boards, work surfaces, drawers, etc.) as determined by the government. This design sheet shall include station numbers and movable wall and associated product locations, in 1/4" = 1'-0" scale.
- 3.2.22 Designs of each location shall include a Panel and Hardware Layout sheet: to include all finish colors and fabrics, panel widths (30", 36", 42", etc.), in 1/4" = 1'0" scale, in addition to display hardware, keys and locksets shall be included.



- 3.2.23 Design sheet layouts of each location shall include a Furniture Power Distribution sheet in 1/4" = 1'0" scale to include: the location of all powered panels, powered components, receptacles, communication ports, power poles, powered raceways, base electrical feeds and building connection points.
- 3.2.24 Within ten (10) workdays after the final design has been accepted by the base requesting organization, a bill of materials detailing all inventory, and (electronic) copies of all plans including basic floor plan, movable wall, panel, and electrical layouts will be provided to the GPM for the project.
- 3.2.25 The contractor shall maintain an updated, automated master copy of all furniture layouts, (designs/redesigns) accomplished under this contract for the duration of the warranty, after government acceptance of the project.
- 3.2.26 Drawing changes required to a layout due to contractor errors or omissions shall be the responsibility of the contractor and the corrected drawing and bill of materials shall be delivered to the government within three calendar days of the request.
- 3.2.27 Contractor shall provide the GPM a copy the installation drawings and bill of materials via mutually agreed upon electronic media.
- 3.2.28 Contractor shall make the government aware of any discrepancies to existing conditions not previously identified.
- 3.2.29 Design shall conform to the parameters established in the Architectural Barriers Act regarding accessibility of persons with disabilities.

3.3 Product Markings/Documentation/Tools

- 3.3.1 Items used after product acceptance used to identify or modify a particular product.
- 3.3.2 All documentation (Owner's manuals, warranty information, assembly instructions, maintenance and care instructions, operating instructions, etc.) shall be provided to and reviewed with the GPM upon completion of the installation.
- 3.3.3 Special assembly tools (security hardware wrench, spare parts provided with the furnishings, etc.) shall be provided to the GPM prior to final Government acceptance of products and services.

3.4 Delivery Services

- 3.4.1 Transportation of all products, loading, unloading, storage, and all necessary movement from factory to final onsite set up.



- 3.4.2 The contractor Project Manager shall be responsible for on-site coordination of all staging and deliveries, to include access to and operation of any equipment needed for unloading and movement of materials or product. This includes any products obtained from suppliers other than the holder of the Tier I agreement.
- 3.4.3 Contractor shall be responsible for determination of the appropriate delivery method and handling, based on site conditions to include the non-existence of loading docks and equipment at any given location. Special circumstances may be identified to and negotiated with the CO.
- 3.4.4 Delivery shall be in accordance with the terms of the contractor's agreement. If the ordering activity designates an accelerated delivery schedule it will be identified in the contract.
- 3.4.5 A maximum of 30 days offsite storage shall be included in the contractor's agreement.
- 3.4.6 Work shall comply with applicable building standards and codes, specifically: National Electrical Code (National Fire Protection Association (NFPA 70) and National Life Safety Code (NFPA 101).
- 3.4.7 The contractor shall be responsible for following all safety and security guidelines within the area in which work is being performed, to include securing any contractor owned tools or equipment, and any on site storage being utilized.
- 3.4.8 The contractor shall maintain accountability and control of any keys provided and shall return them to the GPM upon completion of work. Duplication of keys or other means of access is not authorized.
- 3.4.9 The contractor shall prevent its personnel from entering any area other than the designated work area.
- 3.4.10 The contractor shall maintain a means of egress within all designated work areas to comply with fire codes.
- 3.4.11 The contractor shall ensure its personnel eat, drink, or smoke only in designated areas.

3.5 Installation and Removal Services

- 3.5.1 Manufacturer certified professionals to install office workplace furniture per the approved design drawings.
- 3.5.2 Contractor shall provide or have capability of obtaining support services to include removal and warehousing of the proposed furniture and demountable walls.



- 3.5.3** The contractor shall appoint an authorized representative who will be the company's senior representation on site for all customer communication and enforce compliance of all requirements for the project. This representative shall have a physical presence during any delivery and throughout installation unless agreed to by the GPM.
- 3.5.4** The contractor representative shall meet with GPM to review the installation drawings prior to installation.
- 3.5.5** The contractor shall install office workplace furniture in accordance with each requirement statement and basic component floorplan, panel plan and electrical plan, designed and provided by the contractor with each purchase.
- 3.5.6** Contractor shall be liable for any damage to government property caused by the contractor or their representatives.
- 3.5.7** During installation the contractor shall protect all furniture and building materials, to include carpet, existing within the space with industry approved protective coverings inclusive of craft paper, moving blankets and such type of material. The contractor shall not use protective materials that will leave any type of residual print, outline or imaging on any furniture or building materials. Contractor shall not repair damage to finishes unless directed by CO but will be responsible to pay for damages. The government will make repairs and back charge the installation contractor.
- 3.5.8** Services shall include product transportation of existing inventory as required.
- 3.5.9** The contractor shall uncrate/unpack all items and perform required assembly in accordance with the manufacturer instructions. Services shall include inspection of product for shipping damage. If damage is found it shall be the responsibility of the contractor to notify the GPM and make all arrangements for replacement or repair of the item(s) damaged. Damaged items are not to be installed unless otherwise directed by the GPM.
- 3.5.10** Services shall include assembly of product to conform to final Air Force approved design drawings.
- 3.5.11** Any furnishings attached to the building shall be attached securely.
- 3.5.12** Installation of office workplace furniture must be under the oversight of an onsite manufacturer certified installer.
- 3.5.13** The contractor shall ensure that all communication outlet faceplates are provided with the furniture, based on the unique specifications of the IT requirements at that location.



- 3.5.14** Services shall include removal of packing materials from the installation and cleaning of product including steam cleaning reused panels and thorough cleaning of all products.
- 3.5.15** Services shall include removal of all excess product and transport to the GPM approved warehouse or other location as specified.
- 3.5.16** All trash removed from the worksite shall be disposed of in accordance with state laws, and packaging and other recyclable materials shall be recycled wherever possible.
- 3.5.17** The contractor shall maintain environmental controls when working in any government facility, to include but not limited to keeping doors shut and lights off when not in use and turning off vehicle engines when parked.
- 3.5.18** Light fixtures shall have appropriate lamps and be in working order.
- 3.5.19** Prior to acceptance, the contractor shall clean all furniture only with the manufacturer's recommended cleaning agents/products.
- 3.5.20** The contractor shall provide all components, completely assembled, installed, and operational, including keys in each lock set.
- 3.5.21** Furniture, equipment, and accessories shall be level, square, and in proper alignment with adjoining furniture. All drawers should operate smoothly and stay closed when not in use.
- 3.5.22** The contractor shall inspect to ensure the furniture is free of surface dirt and defects, the installation is complete, and the furniture is ready for use.

3.6 Inspection/Acceptance Checklist

- 3.6.1** Validation between the contractor and the GPM that all product has been installed according to manufacturer guidelines and customer specifications.
- 3.6.2** A post-installation walkthrough shall be coordinated with the contractor's authorized representative and GPM.
- 3.6.3** All areas requiring correction shall be documented in a punch list by the contractor and provided to the GPM upon completion of a joint walk through by the contractor and the GPM. No payment will be authorized while punch list items remain open.
- 3.6.4** A final walk through will be performed with the contractor and the GPM and the CO to ensure all punch list items have been addressed to the satisfaction of the government.

4.0 Product

- 4.1.1** Monolithic Panels and Components



The contractor shall supply all monolithic panel system parts and components needed to fulfill a complete office as referenced on the Office Workplace Furniture Tier I Contracts.

4.1.2 Stackable Panels and Components

The contractor shall supply a stackable panel system product as referenced on the Office Workplace Furniture Tier I Contracts.

4.1.3 Hoteling/Collaboration Furniture/Modular Products

The contractor shall supply furniture product as referenced on the Office Workplace Furniture Tier I Contracts.

4.1.4 Demountable Walls

The contractor shall supply demountable wall product as referenced on the Office Workplace Furniture Tier I Contracts.

5.0 Government Furnished Support

5.1.1 Base support includes Government-controlled working space and utilities.

6.0 Site Conditions

- 6.1.1 Standard site conditions shall be considered those that include:
- 6.1.2 Free and clear hard surface access to the receiving and installation location during regular working hours.
- 6.1.3 Parking and off-loading area suitable for access by a semi-trailer combination or truck within 100 feet of the building entrance closest to product installation area
- 6.1.4 Threat condition level of the base requires dealer personnel to get base access in order to complete the product installation.
- 6.1.5 A staging area adequate to sort, stage and uncrate products along with a waste receptacle suitable for disposal of materials.
- 6.1.6 Includes electric power, working lights, heating and air conditioning, and access to a working freight elevator if location is on a floor other than the first floor.
- 6.1.7 Current and correct CAD drawings of the building shell
- 6.1.8 A building ready for the installation of furniture (i.e. other tasks such as painting and flooring are complete so as not to cause any delays in performance)
- 6.1.9 Contractor shall notify the CO of any deviations from the above standards, as well as any requests for equitable adjustment to the contract price based on a condition not available at site visit.

7.0 Voluntary Protection Program (VPP)/Safety



- 7.1.1 Voluntary Protection Program: The Air Force is part of the AOSHA VPP. All contractors are required to familiarize themselves with the requirements of the VPP. Information on VPP can be accessed at <https://www.osha.gov/vpp>

8.0 Base/Installation Specifics

- 8.1 All commercial trucks must enter through Gate 26A, WPAFB, Ohio, which is located off St. Rt. 235, WPAFB, Fairborn, Ohio, for inspection. In accordance with the Installation 88 ABW/SFS base entry procedures must adhere to delivery vehicle process requirements mandated by the WPAFB AFI 31-101. Once at Gate 16A the driver must have a current pass AF Form 75, Visitor Pass, requested by 88 ABW/PZ, Area A, Building 1, *POC assigned from Interior Designer*, and be able to show:
- A current Vehicle Registration
 - A current Proof of Insurance
 - A valid and current Driver's License for the driver
- 8.2 Gate Procedures:
- Once at **Gate 26A** be prepared to exit the vehicle and allow for vehicle inspection. At this time you may ask for directions to your final destination.
 - If the final destination requires the driver to leave **Gate 26A** and re-enter the base through an alternate gate, the pass received will be sufficient documentation for entry into both gates, within a pre-established time directed by the Security Forces representative.
 - Arrival at the appropriate gate after the designated allotted time will result in non-admittance to the installation.
 - This procedure will occur each time a commercial truck requests access to the base.
- 8.3 Current Bill of Lading (BOL) to get delivery driver and the vehicle on base. BOL must include the AF installation name, date of anticipated delivery, and specific destination (including building number, street address, and point of contact information).
- 8.4 Personnel should the following items when entering an installation:
- Current Registration for all vehicles
 - Current Proof of Insurance for all vehicles
 - Valid driver's license for each driver
 - Valid driver's license or other state identification for each passenger
 - Depending on the current Force Protection Condition, a government representative may be required to sponsor those people in person at Pass & ID, Area A, **Building 286**.
 - The sponsor must state the guest's purpose and destination. It is the responsibility of the contractor to validate this need with their government POC prior to their arrival so as to coordinate the arrival time accordingly. Sponsors may request that a pass be applicable for multiple days if needed.
- 8.5 To sponsor 10 or more people, a typed list of those people must be submitted by the COR in Word or Excel format, stating LAST NAME then FIRST NAME of each person. The sponsor must submit that list to Pass & ID Area A, **Building 286**, no fewer than three days prior to the anticipated arrival. Names listed must be



complete names, (no nicknames), and correspond to the names on the state ID for each person.

8.6 Mission Essential Services: Contractors are not considered mission essential.

8.7 Prohibitions: Firearms may not be brought on base under any circumstances. Individuals with criminal records are not allowed on base. Contractor personnel are prohibited from sponsoring guests onto the installation.

9.0 Delivery

9.1 Installation Details:

9.1.1 Floor and/or floors specifics/phasing – First Floor

9.1.2 Dock details – Receiving Dock

9.1.3 Elevator details – Freight Elevator at Receiving Dock

9.1.4 Receiving Dock times (0800-1500).

9.2 Removal of Existing Furniture: No removal, but see Relocation Requirements in section 2.0 Scope Product Chart RECONFIG-1 for details

9.2.1 list of existing furniture/locations: relocation of typical H per plan

9.3 Period of Performance: to be completed no later than **120 days from contract award**. This is inclusive of in person post award site visit, material finish selection, furniture lead time and installation.

9.4 Delivery to be coordinated with all applicable furniture packages and any additional contracts such as UNICOR and/or SABER/MACC construction project that could be occurring in project site.

9.5 All corridors and aisles to be kept clear during furniture installation.

9.6 The government has full ownership of all formal deliverables and required supporting documentation with regard to use, distribution and reproduction.

9.7 The Government has full ownership of all formal deliverables and required supporting documentation with regard to use, distribution and reproduction.

10.0 Attachments

10.1 Drawings:

10.1.1 ID-1 Furniture Plan

10.2 Furniture Cutsheets per typical

10.3 Provided CAD files are a preliminary drawing set. Once awarded and after completion of construction if applicable, contractor is responsible for field verifying space.