

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE		PAGE 1 OF 8 PAGES	
2. AMENDMENT/MODIFICATION NUMBER 040ADV-25-R-0013-C0001		3. EFFECTIVE DATE 03/19/2025		4. REQUISITION/PURCHASE REQUISITION NUMBER PR-25-GPO-0543		5. PROJECT NUMBER (If applicable)	
6. ISSUED BY CODE				7. ADMINISTERED BY (If other than Item 6) CODE			
				Same As Issuing Office			
8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)				(X)		9A. AMENDMENT OF SOLICITATION NUMBER 040ADV-25-R-0013	
				(X)		9B. DATED (SEE ITEM 11) 03/12/2025	
				()		10A. MODIFICATION OF CONTRACT/ORDER NUMBER	
				()		10B. DATED (SEE ITEM 13)	
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.							
Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.							
CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.						
()							
()	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation data, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).						
()	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:						
()	D. OTHER (Specify type of modification and authority)						
E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)							
AMENDMENT CONTROL NUMBER: 040ADV-25-R-0013							
SUMMARY OF CHANGES: All Prospective contractors, the purpose of this amendment is to provide responses to all submitted questions.							
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
				Troy D. White, Contracting Officer			
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED	
				Troy D. White Digitally signed by Troy D. White Date: 2025.03.18 15:01:36 -04'00'			
(Signature of person authorized to sign)				(Signature of Contracting Officer)			

Solicitation 040ADV-25-R-0013 Questions and Responses

1. Can you please clarify the quantity of hours in CLIN 0001? Is this a total of 150 hours that will be divided amongst three (3) technicians resulting in 50 hours per technician? Or, is it for 150 hours per technician multiplied by three (3) technicians resulting in 450 hours? Base on the work milestones provided in Section 4, testing start to completion is 5 days, which leads me to believe you're looking for three (3) technicians essentially for almost four (4) full days.

The total workload allows up to 150 hours. We suggest three technicians because of the recent Fire Alarm Assessment performance done at GPO Buildings.

2. Like RFI 1, can you please clarify the quantity of hours in CLIN 0002? Is this a total of 280 hours that will be divided amongst two (2) engineers resulting in 140 hours per engineer? Or, is it for 280 hours per engineer multiplied by two (2) engineers resulting in 560 hours? Similar to the analysis of time in RFI 1, it appears that you're looking for two (2) dedicated "Engineers" for nearly the entire month of April to provide the desired consultation services.

The total workload allows up to 280 hours. At least one of them must be Licensed Fire Protection Engineer.

3. Can you define "Engineers" as specified in CLIN 0002? Are you looking for two (2) licensed fire protection engineers? Or are you looking for two (2) consultants with the ability to perform system surveys and provide advanced technical knowledge of NFPA standards beyond the capabilities of the technicians required in CLIN 0001? It is not typical for a licensed fire protection engineer to perform surveys and inspect systems. This type of work is typically performed by a NICET Level III or IV engineering technologist and final recommendations are reviewed and approved by a licensed fire protection engineer. To ensure the government receives a cost-effective solution, we recommend CLIN 0002 be 240 hours for two (2) NICET Level III or IV consultants, and a 3rd CLIN be added for 40 hours for one (1) licensed fire protection engineer. This will significantly reduce the cost to the government for these services while maintaining the integrity of the deliverables.

We are looking for at least one Licensed Fire Protection Engineer for the final report and consultation. The testing and certification can be performed by NICET Level III/IV technician.

4. Based on internal knowledge we have from a previous contract at this facility, we believe the "Engineer" hours are to provide a comprehensive survey and analysis of the building and existing fire alarm systems to prepare for a full system replacement. As an alternative to requesting a fixed number of hours for this, would you be willing to consider offerors provide a three (3) phase fixed fee price to execute the system replacements? Phase 1 Due Diligence – Code call, obtain and review current as-builts, survey, gather all stakeholder information to develop the best possible approach for the next phase. Phase 2 Design – Design to the codes and requirements that were found during Due Diligence. Layout, calculations, and full submittal package to AHJ. The design could be used for pricing the upgrade. Phase 3 Upgrade Installation – complete installation including acceptance testing by AHJ and any stakeholder GPO requires. Our team has extensive experience in implementing this process successfully for various private customers and government agencies.

No, we are looking for onsite consultation. The three phase approach goes above and beyond the scope of this solicitation.

5. Section 1 – Background states the fire will provide post repairs, system testing, and consultation service for the entire system... by a Licensed Fire Protection Engineer...”. Can you please clarify the extent of work/hours the Licensed Fire Protection Engineer is required to perform? This ties into RFI 3 above, as we recommend less Licensed Fire Protection Engineering time (40 hours) and more NICET Level III or IV consultant time (240 hours) to ensure cost-effective solutions are provided.

The Licensed Fire Protection Engineer will provide the final report and consultation services to upgrade the current Fire Alarm and Sprinkler Systems. The technicians will be testing and certifying the repairs done by GPO Shop Technicians.

6. Section 1 – Background states the intent of the RFP is to certify repairs, presumably completed by others. Section 3.1 states, “Under the Terms and Conditions of the resultant Contract, the selected Contractor, shall be responsible for... other services required to perform all aspects of repairs...”. Can you clarify the intent of this solicitation is to inspect repairs completed by others, and not for the awarded contractor to perform any repairs?

The intention of this solicitation is testing and certifying of previously completed repairs done by GPO Shop Technicians. Any required repairs will be accomplished by GPO Shop Technicians.

7. Section 4 – Tasks is quite extensive and appears to be full system inspections. Can you please confirm the tasks are applicable to only the repairs that were previously completed by others? Or are you looking for full annual system inspection and testing to be performed on all devices for the fire alarm and sprinkler systems?

The task requires only inspection and testing of previously completed repairs.

8. At the bottom of the page for Section 4, the * states qualified personnel with appropriate certifications for fire alarm and sprinkler systems. Can you please confirm you’re referring to NICET certified inspection and testing technicians? Or are there additional or different certifications required? If so, please define.

For testing and inspections, we are referring to at least one of the technicians must be NICET certified

9. Can you please confirm a minimum of two escorts will be available for retesting?

GPO will provide the required number escorts as needed to perform this task.

10. Can you please confirm the GPO can provide three parking spaces in the GPO parking lot?

The GPO parking lot has enough space to accommodate contractors. Contractors shall be responsible for parking fees, which is \$9 per day/vehicle.

11. Can you please confirm if retesting of the horn strobes or fire pump these can be performed during business hours between Monday and Friday? From past experience, we had to test these on a Saturday.

All testing and inspection can be performed Monday-Friday during normal business hours.

12. Based upon award date, the project completion dates do not allow enough time to schedule properly. Can we provide a schedule that would allow time to ensure proper staffing with the understanding of a quick period of performance?

We can provide some flexibility and work with the proposed schedule.

13. Can the government provide more specific information on the type of engineer that is needed for consultation? Are there specific certifications that the engineers must have?

GPO is seeking a Licensed Fire Protection Engineer for the consultation.

14. Can the government provide the name of the contractor who is completing the repairs?

All repairs have been completed by GPO shop technicians.

15. Can the government provide reasoning for 3 technicians being needed for testing the fire alarm and suppression systems?

We request three technicians due to past experience where one technician positioned at the command center and the other two technicians were performing the test on field.

16. Is the post-repair testing and certification to be completed during normal business hours or after-hours? Some of the required re-testing and certification may require alarms to sound, and this would be disruptive to GPO employees.

All testing and certification can be completed during normal business hours.

17. Can the government provide a list of the repairs that need to be certified?

Please find below the list of Fire Alarm and Sprinklers Systems Discrepancies.

Building A Fire Alarm System Discrepancies

Phone Station:

- 7th floor stair 1 failed annunciation, alarm came to panel as stair 2
- 7th floor stair 2 failed annunciation, alarm came to panel as stair 1

Horn/Strobe:

- 5th floor next to A500F speaker INOP
- 6th floor next to column 6F15 strobe INOP

Duct Detector:

- 3rd floor mech room A310 failed annunciation, alarm came to the panel as A301
- 3rd floor mech room A316 failed annunciation, alarm came to the panel as A301
- 3rd floor mech room A318 failed annunciation, alarm came to the panel as A302-2

Heat Detector

- 3rd floor by room A310 failed annunciation, alarm came to the panel as A301
- 3rd floor by room A316 failed annunciation, alarm came to the panel as A302
- 3rd floor by room A318 failed annunciation, alarm came to the panel as A302

Pull Station

- 7th floor outside of room A740 out of service

Smoke Detector

- Basement machine shop failed to report
- 1st floor shipping platform failed to test, doesn't report to the panel as a alarm
- 6th floor by room A656 failed annunciation
- 7th floor by restricted area defective, there is no power to the smoke detector
- 7th floor room A727A not connected, wires are cut, no power to the smoke detector
- 8th floor men's locker room failed description, panel shows as a car shop
- 8th floor women's locker room failed description, panel shows as a men's locker room

Building B Fire Alarm System Discrepancies

Horn/Strobe:

- Rooftop horn and strobe INOP

Smoke Detector

- 3rd floor elevator 21-22 failed annunciation, showing wrong location
- 3rd floor elevator 24-25 smoke detector is not connected

Building C Fire Alarm System Discrepancies

Horn/Strobe:

- 1st floor inside the power branch room horn and strobe INOP
- 2nd floor outside of room C228 strobe INOP

Pull Station

- 1st floor inside the power branch room C127 failed annunciation, shows wrong location
- 3rd floor by shaft #36 failed test, shows wrong location
- 4th floor by shaft #36 failed test, shows wrong location
- 6th floor by shaft #36 failed test, shows wrong location by shaft #34
- 7th floor by shaft #36 failed test, shows wrong location by shaft #34

Smoke Detector

- 2nd floor by column 2E14 programming error, the panel doesn't show the location
- 2nd floor room C240B programming error, the panel doesn't show the location
- 2nd floor room C240B programming error, the panel doesn't show the location
- 2nd floor by column 2E17 failed test, the panel shows wrong location
- 7th floor room C721 failed annunciation, not responding to the panel
- 7th floor by women's locker T374 failed annunciation, not responding to the panel
- 8th floor room C829 failed annunciation, wrong location the alarm shows at 6th floor

Building D Fire Alarm System Discrepancies

Pull Station

- 2nd floor stair 1 failed annunciation, shows wrong address

Smoke Detector

- 2nd floor by room 5D-211 failed operation, old device not linked to the EST system
- 2nd floor by column 30 failed operation, old device not linked to the EST system

Building A Sprinklers System Discrepancies

Tamper Switch

- At the basement inside room 41000 failed annunciation, came to the panel as A004
- At the basement inside room A019 failed annunciation, came to the panel as A009
- 1st floor inside stair 2 failed test, did not send supervisory alarm to the panel
- 3rd floor inside stair 3 dry system failed test, device did not send signal to the panel, even when manually tested

Waterflow Switch

- 4th floor inside stair 3 failed flow test, did not go into alarm within 90 seconds
- 7th floor inside stair 3 failed flow test, did not go into alarm within 90 seconds

Building B Sprinklers System Discrepancies

Waterflow Switch

- 2nd floor Inside Stair 2 failed flow test, did not go into alarm in time
- 5th floor Inside Stair 2 failed flow test, alarm did not come in while flowing

Building C Sprinklers System Discrepancies

Control Valve

- Basement Power Section/Pump Room Failed annunciation, comes in as fire pump fault.
- Basement Outside Stair 3 (Dry Valve Air Isolation), leaking a good amount of air when operated.
- Basement Outside Shaft 33 Leaking, It's blowing a lot of air needs to be replaced
- 1st floor inside power branch leaking, leaks when operated

Quick Opening Device

- Basement Outside Stair 4 (Dry Valve) Damaged/Worn, reset knob is broken off cannot reset. Needs to be replaced
- Basement by Shaft 33 (Dry Valve) Will not set up, once tripped the device will not setback up. Tried multiple times. This is also a leak on the air line connected to it.

Tamper Switch

- Basement power section/pump room backflow valve 2 failed annunciation comes in as a fire pump fault.
- Basement power section/pump room backflow valve 1 failed annunciation comes in as a fire pump fault.
- Basement power section/pump room main incoming valve failed annunciation comes in as a fire pump fault.
- Basement behind column BD14 Failed annunciation came to panel as tamper by Stair 3. should say outside power section by column BD14
- 7th floor outside stair 2 failed annunciation, came in to panel as 7th floor stair 1
- 7th floor outside stair 4 failed annunciation, came in to panel as 7th floor stair 1
- 7th floor outside Stair 3 failed annunciation, came in to panel as 7th floor stair 1

Building D Sprinklers System Discrepancies

Pressure Switch

- Basement Dry System By Column B-G30 Out of service, replace with new high Low air device.
- Basement Pump Room Out of service, replace with new high Low air device.